

VOLUME IIR
NPDES PERMIT RENEWAL APPLICATION
MIXING ZONE DEMONSTRATION

Prepared for:

AMOCO OIL COMPANY
WHITING REFINERY
Whiting, Indiana

Prepared by:



Golden, Colorado

and



The ADVENT Group, Inc.
1925 Lynn Street, Suite 702
Rosslyn, VA 22209

March 1998

TABLE OF CONTENTS

TABLE OF CONTENTS

| <u>Section No.</u> | <u>Title</u> | <u>Page No.</u> |
|--------------------|--|-----------------|
| | Table of Contents..... | ii |
| | Forward..... | v |
| | Executive Summary | vi |
| SECTION 1.0 | INTRODUCTION..... | 1-1 |
| 1.1 | FACILITY DESCRIPTION | 1-1 |
| 1.2 | WATER QUALITY MANAGEMENT PROGRAM..... | 1-2 |
| 1.3 | APPROPRIATENESS OF MIXING ZONE FOR THE AMOCO WHITING REFINERY..... | 1-3 |
| 1.4 | BASIS FOR ALLOWANCE OF A MIXING ZONE | 1-4 |
| 1.5 | INDIANA MIXING ZONE REQUIREMENTS..... | 1-6 |
| SECTION 2.0 | MIXING ZONE DISPERSION ANALYSIS..... | 2-1 |
| 2.1 | MULTIPORT DIFFUSER MODELING | 2-1 |
| 2.1.1 | Model Input Parameters and Diffuser Design | 2-2 |
| 2.1.2 | Model Results | 2-4 |
| 2.2 | SUMMARY | 2-5 |
| SECTION 3.0 | MIXING ZONE DEMONSTRATION | 3-1 |
| 3.1 | INTRODUCTION..... | 3-1 |
| 3.2 | INDIANA MIXING ZONE REGULATORY REQUIREMENTS (327 IAC 5-2-11.4(b)(4))..... | 3-3 |
| 3.3 | OVERALL SUMMARY..... | 3-18 |
| SECTION 4.0 | MIXING ZONE DEMONSTRATION CONCLUSION..... | 4-1 |

LIST OF TABLES

| <u>Table No.</u> | <u>Title</u> |
|------------------|---|
| ES-1 | Indiana Mixing Zone Criteria |
| 1-1 | NPDES Outfall 001 Discharge Limitations and Effluent Quality |
| 1-2 | Water Quality Management Program Elements |
| 1-3 | Mixing Zone Terminology |
| 1-4 | Indiana Water Quality Criteria |
| 2-1 | Port Sizes and Spacing for a 90-ft Multiport Diffuser |
| 2-2 | CORMIX2 Model Input Parameters |
| 2-3 | Lake Michigan Water Quality Data |
| 2-4 | Summary of Lake Michigan Current Measurements |
| 3-1 | Comparison of Outfall 001 Characteristics to Federal Primary Drinking Water Standards |

LIST OF FIGURES

| <u>Figure No.</u> | <u>Title</u> |
|-------------------|--|
| 1-1 | Location Map, Whiting, Indiana |
| 1-2 | Area Map, Amoco Oil Company - Whiting Refinery |
| 1-3 | Wastewater Treatment Plant - Water Flow Diagram Amoco Oil Company, Whiting Refinery |
| 2-1 | Water Depth at the Proposed Diffuser Location (S3500) |
| 2-2 | CORMIX2 Results for Multiport Diffuser |
| 3-1 | Alternate Mixing Zone Delineation |
| 3-2 | Mixing Zone Shape and Location in Lake Michigan |
| 3-3 | Conceptual Community Sensitivity |

LIST OF ATTACHMENTS

| <u>Attachment No.</u> | <u>Title</u> |
|-----------------------|--|
| 1 | Federal Mixing Zone Guidances |
| 2 | Preliminary Diffuser Design |
| 3 | Wind Rose |
| 4 | CORMIX2 Model Output |
| 5 | South End of Lake Michigan Bibliography |
| 6 | Lake Michigan Biomonitoring Program Database and Summary Report |
| 7 | STORET System Retrieval for Whiting Intake |
| 8 | Southern End of Lake Michigan Representative Fisheries |
| 9 | 1997 Indiana Endangered, Threatened, and Rare Species Lists 1995 Michigan Non-Indigenous Aquatic Nuisance Species State Management Plan: Executive Summary |

FOREWARD

FOREWORD

This report is Volume IIR of the Amoco Oil Company, Whiting Refinery, application to renew NPDES Permit Number IN0000108. This document supplements Volume II submitted to the Indiana Department of Environmental Management in August, 1994.

Volume IIR provides information to demonstrate that a mixing zone can safely be integrated into the renewed Amoco NPDES Permit. This mixing zone demonstration addresses the requirements of state rules and federal law and guidance. Amoco is providing information based on hydrodynamic and biological field studies, chemical and biological laboratory tests, computer modeling, and literature review of the physical, chemical, and biological characteristics of the receiving water, effluent, and the specific areas of the mixing zone. As a replacement for the current Outfall 001 configuration, Amoco proposes to install and operate a multi-port high-rate diffuser to discharge its treated effluent. A multi-port high-rate diffuser will assure rapid and immediate mixing, thus further minimizing potential aquatic organism exposure. Based on the information provided in this report to satisfy Indiana rules (327 IAC 2-1.5-8 and 5-2-11.4, etc.), a mixing zone is appropriate to be included in Amoco's NPDES permit.

The report is organized into the following sections:

- Section 1 introduces background information on the Amoco Whiting facility, the technical and regulatory basis for allowing a regulatory mixing zone in Lake Michigan, and the applicability of a regulatory mixing zone to Amoco's NPDES permit.
- Section 2 analyzes the mixing zone dispersion of the proposed multi-port high-rate diffuser, using a USEPA-accepted and supported computer model.
- Section 3 demonstrates that a mixing zone meets all Indiana mixing zone regulatory requirements as well as federal guidance. The demonstration includes information on the magnitude and extent of the mixing zone, receiving water and effluent characteristics, and the results of a bioassessment field study.
- Section 4 summarizes the findings of this mixing zone demonstration and recommends the specific mixing zone (size and dispersion ratio) to be incorporated into wasteload allocation procedures necessary to derive water quality-based effluent limits for the NPDES Permit renewal process.

EXECUTIVE SUMMARY

EXECUTIVE SUMMARY VOLUME IIR

INTRODUCTION

In August of 1994, Amoco submitted an application to renew its NPDES permit that authorizes Amoco to discharge treated water into Lake Michigan. Amoco requested that the 1990 ambient water quality standards be applied at the edge of a proposed mixing zone. Amoco's proposed mixing zone would not result in an increase in concentration or mass over currently permitted levels that are discharged into Lake Michigan from Amoco's state-of-the-art wastewater treatment plant.

This document supplements Volume II ("Mixing Zone Demonstration") of the 1994 permit application. This document (referred to as "Volume IIR") reorganizes the information contained in the original Volume II (referred to as "Volume II") to correspond to new mixing zone rules adopted by IDEM in February of 1997. The substance of the mixing zone demonstration has not changed. While Volume II should remain a part of the permitting docket, Volume IIR is a free-standing document that can be relied on without reference to Volume II. Volume I ("NPDES Permit Renewal Application") has not changed and remains an integral component of the overall application. Volume III ("Permit Limits Derivation Report") completes Amoco's NPDES permit application.

In February of 1997, Indiana adopted new water quality standards (WQS)¹. The 1997 WQS are based on the United States Environmental Protection Agency's (USEPA) Water Quality Guidance for the Great Lakes System (commonly referred to as the GLI), 40 CFR Part 132. The GLI WQS establish numeric criteria for some specific chemicals and a procedure for developing numeric water quality criteria or values for other specific chemicals. In addition, the GLI WQS specify mixing zone criteria for use in converting the numeric water quality criteria or values into water quality-based effluent limits

¹ Water Quality Standards (WQS) include numeric criteria and narrative standards that address designated uses, antidegradation, criteria development methods, and implementation procedures, including mixing zones. Mixing zones are, in fact, part of WQS.

(WQBELs). Table ES-1 sets forth the 1997 mixing zone criteria verbatim. As demonstrated herein, the 1997 water quality criteria or values should be applied at the edge of a small, well-defined mixing zone.

WHAT IS A MIXING ZONE?

A mixing zone is an area contiguous to a discharge where the treated effluent mixes with the receiving waters. Since water quality criteria or values are exposure-based, they do not apply within a mixing zone; the criteria or values are met at the edge of a mixing zone. Compliance is determined by sampling the effluent prior to discharge and comparing the results to permit limits that account for the dispersion which occurs within the mixing zone.

This technique is common for health-based environmental standards. For example, USEPA promulgates national ambient air quality standards (NAAQS) to protect public health and welfare. 42 USC 7408(a), 7409(a). The various states then adopt rules that apply to specific sources to ensure that the ambient air meets the NAAQS. 42 USC 7410 (a). Individual sources are not required to meet the NAAQS. In fact, individual sources may exceed the NAAQS at the end of a smoke stack and remain in compliance with their individual permits as long as the ambient air meets the NAAQS at the point of exposure (e.g., outside the plant's fenceline). The NAAQS, like water quality standards, are set at a level to protect against excessive exposure in the real world. It is not reasonable (or necessary) to assume that an individual will be perched at the top of a smoke stack for eight hours inhaling the emissions. Likewise, it is not reasonable (or necessary) to assume that a fish will take a position at the end of a discharge pipe and remain there for a sufficient duration to result in any harm. Instead, the regulatory procedures for health-based standards allow for demonstrated dispersion to be included and an emissions limit that accounts for that dispersion.

USEPA and the States, including Indiana, have used mixing zones as a tool for implementing water quality criteria or values since the 1960's. USEPA reaffirmed its view that mixing zones are an appropriate tool for implementing water quality criteria or

values in the recently promulgated GLI. IDEM modeled its mixing zone rules on the GLI.²

Like the NAAQS, one of the main objectives in applying the water quality standards is to determine a point at which the standards must be met. In the case of the NAAQS, it may be at the fenceline. In the case of the WQS, it is at the edge of a mixing zone. In practice, this means that a dispersion ratio is established at the edge of the mixing zone and is used to translate water quality criteria to an end-of the-pipe limit. For example, with 100:1 dispersion at the edge of a mixing zone, a mass balance of 1 part effluent with 100 parts receiving water (at background concentration) is calculated to develop an end-of-pipe limit, with compliance determined based on samples of the effluent prior to mixing with the receiving water.³ An end-of-the-pipe limit is necessary because it is often not feasible to obtain compliance samples at the edge of a mixing zone.

WHY ARE MIXING ZONES APPROPRIATE?

USEPA has endorsed mixing zones for four decades. Mixing zones are appropriate given that the water quality criteria are exposure-based and exposure is of very limited duration inside a mixing zone. Water quality criteria include numerical limits based on three principles⁴:

- magnitude of exposure
- duration of exposure, and
- frequency of exposure

Chemical specific and whole effluent toxicity (WET) water quality criteria are based on both the acute (or short-term) effects and the chronic (or long-term) effects on aquatic life. Numeric water quality criteria are developed for specific chemicals and for WET.

² The USEPA GLI and IDEM rules (327 IAC ARTICLE 5) set forth several important limitations on the use of mixing zones.

First, mixing zones are only appropriate if the subject waterbody meets the water quality standards. In other words, there must be assimilative capacity to accommodate the increased loading. Second, mixing zones are not appropriate for substances that bioaccumulate. Third, mixing zones should not be used to adjust any technology-based limits (as opposed to water quality-based limits). Amoco's proposed mixing zone is consistent with these limitations.

³ Based on a review of approved mixing zones, dispersions can vary significantly from 2:1 to 500:1. The USEPA GLI uses a default mixing zone for lakes of 10:1.

⁴ WQS also include narrative standards that address designated uses, antidegradation, and implementation including mixing zones.

This approach prevents impacts from individual chemicals, as well as from the cumulative, additive and/or synergistic effects of the combination of chemicals in the whole effluent.

Acute Aquatic Criteria (AAC) are based on protecting the most sensitive species from acute effects. For instance, Indiana's AAC for chlorides is 860 mg/L (*magnitude*) as a one-hour average (*duration*) concentration, not to be exceeded more than once every three years on average (*frequency*). By contrast, Chronic Aquatic Criteria (CAC) are derived to protect the most sensitive species from chronic effects and are expressed as a specified concentration (*magnitude*) over a four-day average (*duration*), not to be exceeded more than once every three years on average (*frequency*). The Indiana CAC for chlorides is 230 mg/L (*magnitude*) as a four-day average (*duration*) not to be exceeded more than once every three years (*frequency*). Due to the duration and frequency principles underlying the derivation of criteria, the criteria are referred to (by USEPA and others) as "instream criteria", highlighting the fact that these are not to be attained at end-of-pipe. 327 IAC 2-1.5-7.

The numeric water quality criteria are converted into water quality-based effluent limitations (WQBELs) as part of the permitting process. This process considers whether a permit applicant's effluent (as measured at the end-of-pipe) has the reasonable potential to exceed (RPE) an instream water quality criteria. If so, a permit limit should be developed based on a wasteload allocation that accounts for the permittee's discharge, as well as the combined impact of other discharges (point and nonpoint sources) and naturally occurring background concentrations. The permit limit must ensure that the water quality criteria or values will be met in the receiving water.

If a permit applicant demonstrates that it has engineered a mixing zone that meets the regulatory requirements, then, by definition, the mixing zone will not result in exposure for a duration and/or frequency that exceeds a numeric water quality criteria. Thus, permit limits can be developed, taking into account a mixing zone. For example, in many cases the initial momentum from the discharge of effluent into the receiving water minimizes the time organisms would be exposed to concentrations above the magnitude criteria. Though the exposure will exceed the magnitude of the criteria, the duration of exposure can be limited to ensure that there is no adverse effect. USEPA and the

states have developed rules and guidance over the years to determine the limitations on the duration of exposure that are necessary to protect human health, aquatic life, and wildlife. IDEM has adopted these rules as part of the GLI. If an applicant meets the requirements set forth in 327 IAC 5-2-11.4(b)(4) (see Table ES-1), it has by definition established that the duration of exposure within a defined mixing zone will not interfere with the waterbody's designated uses.

IS AMOCO'S PROPOSED MIXING ZONE APPROPRIATE?

Amoco's proposed mixing zone is appropriate because it meets all of the documentation and demonstration requirements set forth in Indiana rules (see Table ES-1). Addressing these regulatory demonstration criteria calls on two different disciplines: hydrodynamics and biology. Amoco's hydrodynamic and biological studies are discussed in this document and summarized below.

The hydrodynamic investigations involve studies of the physical properties of mixing. Amoco has previously demonstrated that its present discharge (Outfall 001) provides significant mixing through the dispersion created by its existing discharge configuration. Nonetheless, Amoco is proposing to install a multi-port submerged high-rate diffuser to enhance mixing and to reduce the size and area of the resulting mixing zone. A diffuser is a structure engineered to enhance mixing by discharging effluent at a relatively high velocity into the water column and directed away from the lake bottom.

Amoco proposes to install the multi-million dollar diffuser at a depth of approximately 30 feet at a location approximately 3,500 feet northeast of the present side-channel outfall. The rationale for this site is to maximize mixing with ambient waters by locating the diffuser in deeper waters where more water volume is available for rapid mixing than is available than the current Outfall 001. After installation of the diffuser, the treated effluent will be pumped through a 3,500-foot feeder pipe and discharged at high velocities (e.g., 10 feet/second) through ten small ports evenly spaced over the last 90 feet of the pipe (the diffuser header).

To determine the dispersion ratio that can be achieved by the proposed diffuser, Amoco researched historical records, conducted its own field measurements, and consulted with widely recognized experts. The data gathered were entered into an USEPA-

endorsed computer model used to project mixing (CORMIX2). Based on the modeling and field studies, Amoco proposes a mixing zone that is equivalent to the discharge-induced mixing zone under Indiana rules. This area encompasses a 50-foot radius around the diffuser. At the edge of this zone, the effluent is dispersed by a 54:1 ratio. Organism exposure inside this mixing zone will be less than the duration component used to derive water quality criteria. In fact, exposure time for free floating organisms in the discharge-induced mixing zone is less than 90 seconds, which is significantly less than the one-hour or four-day exposure duration component used to determine acute or chronic water quality criteria, respectively. Thus, to establish daily maximum and monthly average end-of-pipe limits, a mass balance of one part effluent and 54 parts of background receiving water is applied to the instream water quality criteria.

In addition to the mixing hydrodynamics discussed above, Amoco conducted a series of biological assessments of the present discharge location and the proposed diffuser site. These assessments found no evidence of adverse effects to aquatic life or the designated uses of the receiving water at the present site (presented in 1994 Volume II). Given that the proposed mixing zone includes dispersion enhancements when compared to the current discharge (i.e., a diffuser in deeper water and away from shore), the proposed mixing zone will not adversely impact the designated uses of southern Lake Michigan.

The biological assessments evaluated bottom-dwelling, free-floating, and attached aquatic communities. Species from these particular communities were collected, identified, and counted because they are either (a) the most sensitive aquatic communities in the area where mixing between effluent and receiving water occurs, or (b) the most critical communities in the Great Lakes ecosystem food chain. The overall findings from the biological assessment were that the present discharge has not adversely affected aquatic life or the designated uses of the receiving water. With a submerged multi-port high-rate diffuser located in deeper waters, the dispersion effects are enhanced as effluent will be quickly mixed throughout the deeper water column, further minimizing the exposure time for organisms.

CONCLUSION

The hydrodynamic studies and biological assessment, taken together, make a compelling demonstration that Amoco's proposed mixing zone will not cause harm to human health, aquatic life, or wildlife. In fact, reducing the duration of exposure by using a submerged high-rate diffuser renders Amoco's proposed mixing zone more protective of human health, aquatic life, and wildlife than the existing discharge. Under Indiana law, IDEM must include the mixing zone in Amoco's permit because Amoco has met all of the conditions for approval set forth in 327 IAC 5-2-11.4(b)(4).

TABLE ES-1. INDIANA MIXING ZONE CRITERIA

| | |
|--------------------------------|--|
| 327 IAC 5-2-11.4(b)(4)(A)(i) | Document the characteristics and location of the outfall structure, including whether technologically enhanced mixing will be utilized. |
| 327 IAC 5-2-11.4(b)(4)(A)(ii) | Document the amount of dilution occurring at the boundaries of the proposed mixing zone and the size, shape and location of the area of mixing, including the manner in which diffusion and dispersion occur. |
| 327 IAC 5-2-11.4(b)(4)(A)(iii) | For sources discharging to the open waters of Lake Michigan, define the location at which discharge-induced mixing ceases. |
| 327 IAC 5-2-11.4(b)(4)(A)(iv) | Document the physical including substrate character and geomorphology, chemical and biological characteristics of the receiving waterbody, including whether the receiving waterbody supports indigenous, endemic or naturally occurring species. |
| 327 IAC 5-2-11.4(b)(4)(A)(v) | Document the physical, chemical, and biological characteristics of the effluent. |
| 327 IAC 5-2-11.4(b)(4)(A)(vi) | Document the synergistic effects of overlapping mixing zones or the aggregate effects of adjacent mixing zones. |
| 327 IAC 5-2-11.4(b)(4)(A)(vii) | Show whether organisms would be attracted to the area of mixing as a result of the effluent character. |
| 327 IAC 5-2-11.4(b)(4)(B)(i) | The mixing zone would not interfere with or block passage of fish or aquatic life. |
| 327 IAC 5-2-11.4(b)(4)(B)(ii) | The level of pollutant permitted in the waterbody would not likely jeopardize the continued existence of any endangered or threatened species listed under Section 4 of the ESA or result in the destruction or adverse modification of such species habitat. |
| 327 IAC 5-2-11.4(b)(4)(B)(iii) | The mixing would not extend to drinking water intakes. |
| 327 IAC 5-2-11.4(b)(4)(B)(iv) | The mixing zone would not impair or otherwise interfere with the designated uses of the receiving water or downstream waters. |
| 327 IAC 5-2-11.4(b)(4)(B)(v) | The mixing zone would not promote undesirable aquatic life or result in a dominance of nuisance species. |
| 327 IAC 5-2-11.4(b)(4)(B)(vi) | By allowing the additional mixing: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced. |
| 327 IAC 5-2-11.4(b)(4)(C) | In no case shall a mixing zone for a discharge into the open waters of Lake Michigan be granted that exceeds the area where discharge induced mixing occurs. |

SECTION 1

SECTION 1.0

INTRODUCTION

As part of its comprehensive water quality management program, Amoco Oil Company, Whiting Refinery (Amoco) has performed studies to assess the options available to comply with the Indiana Water Quality Standards (327 IAC 2) promulgated on March 3, 1990, and revised February 13, 1997. These state standards have incorporated the requirements of the federal Clean Water Act of 1987 as well as the Final 1995 Water Quality Guidance for the Great Lakes System (40 CFR Part 132). Part of these requirements include application of water-quality based (chemical-specific and whole effluent toxicity) effluent limits, as well as technology-based limits for direct dischargers.

Based on Amoco's water quality studies and the fact that Lake Michigan is in attainment of water quality standards, Amoco concludes that a mixing zone is appropriate to define a point of application for water quality criteria.

Amoco requests an evaluation of the application of a mixing zone for the discharge of treated effluent into Lake Michigan pursuant to 327 IAC 2-1.5-7 and 327 IAC 5-2-11.4 and federal mixing zone guidance. Results of an effluent dispersion analysis and corresponding mixing zone demonstration as part of this request are presented in this report.

1.1 FACILITY DESCRIPTION

The Amoco Whiting Refinery occupies approximately 1,700 acres near the southern end of Lake Michigan as presented in Figures 1-1 and 1-2. The petroleum refinery includes processes such as distillation, catalytic reforming, hydrodesulfurization, catalytic cracking, alkylation, coking, treating, extraction, dewaxing, grease and lube oil production, asphalt production, sulfur recovery, and power generation. The refining throughput varies with product demand and other market considerations, but its capacity averages 410,000 barrels of crude per day. Amoco produces a variety of products including jet fuel, gasoline, diesel fuel, heating fuel, lubricating oils, asphalt, coke, and waxes.

The refinery generates process waters which are continuously treated on-site at an advanced biological wastewater treatment plant (WWTP) as shown schematically in Figure 1-3. (Volume I NPDES Permit Application, submitted August 29, 1994, presents details of the WWTP). Stormwater run-off and recovered groundwater from refinery areas are also treated at the WWTP. The treated effluent is then discharged to Lake Michigan through a National Pollutant Discharge Elimination System (NPDES) permitted outfall (Outfall 001). The refinery withdraws water from Lake Michigan for use in process units and for once-through cooling. The once-through noncontact cooling water is discharged through NPDES Outfall 002. Both outfalls are regulated by NPDES Permit IN0000108 (the NPDES Permit) which became effective on April 1, 1990. The effluent flow from Outfall 001 ranged from 13 (long-term average) to 23 (maximum monthly average) million gallons per day (mgd) during 1991 to 1994 (Volume I NPDES Permit Application, submitted August 29, 1994). For the same time period, the average flow from Outfall 002 ranged from 110 to 120 mgd.

The NPDES Permit has limits for Outfall 001 derived from technology-based effluent limits, which are presented in Table 1-1. Amoco has consistently attained these permit limits with high quality effluent that meets or is better than "Best Available Technology" (BAT) effluent requirements, as seen by the historical WWTP plant performance also indicated in Table 1-1. It is anticipated that the new permit will contain effluent limits based on the Indiana Water Quality Standards as well as the previously applicable technology-based standards. Amoco is not requesting a mixing zone for technology-based standards. As part of the permit renewal application, Amoco is submitting this report to demonstrate an appropriate implementation of a mixing zone for application of the Indiana water quality standards consistent with 327 IAC 2-1.5-7 and 5-2-11.4.

1.2 WATER QUALITY MANAGEMENT PROGRAM

To meet the goals of the Indiana water quality laws, Amoco developed a comprehensive water quality management program including the elements presented in Table 1-2. For example, wastewater treatment has been optimized by supplementing the aeration system in the bio-tanks (1995) and upgrading the final filters (1996). Details of some of the activities listed in Table 1-2 can be found in Volume I NPDES Permit Application, submitted August 29, 1994. This current report (Volume IIR) presents a discussion of the

program elements relating to defining the point of application for receiving water quality criteria through delineation of a mixing zone in Lake Michigan for Outfall 001.

1.3 APPROPRIATENESS OF MIXING ZONE FOR THE AMOCO WHITING REFINERY

As part of the water quality management program, Amoco considered several factors prior to proceeding with a mixing zone demonstration. There are generic stipulations presented in USEPA guidance⁵ to assess the appropriateness of using a mixing zone to define the point of application of criteria and to develop discharge limits. In light of these USEPA stipulations, Amoco presents the following responses to the appropriateness of using a mixing zone for Outfall 001 permitting. As discussed previously, implementation of a mixing zone for the Amoco facility is not a substitute for BAT wastewater treatment. Amoco has demonstrated that based on USEPA test methods the combined effect of constituents discharged from Outfall 001 is not acutely toxic (presented in Volume I NPDES Permit Application, submitted August 29, 1994). Lake Michigan meets the water quality criteria for its designated uses for the constituents listed in Table 1-4, (i.e., background concentrations are less than the most stringent criteria), hence assimilative capacity exists. The presence of assimilative capacity for these constituents allows the use of a mixing zone in establishing discharge limits. In addition, the proposed mixing zone covers a limited area and will not impair the integrity of the receiving waterbody, as further documented in Sections 2 and 3.

Furthermore, the federal recommendation of mixing zone use to define the point of application for criteria has to be recognized by the state. Indiana concurs with federal guidance that water quality criteria apply in the receiving water and not at end-of-pipe as discussed in the Sections 1.4 and 1.5. Indiana defines a mixing zone as follows:

327 IAC 2-1.5-2 (55) Definitions. *"Mixing zone" means an area contiguous to a discharge where the discharged wastewater mixes with the receiving waters. Where the quality of the effluent is lower than that of the receiving waters, it may not be possible to attain within the mixing zone all beneficial uses which are attained outside the zone. The mixing zone should not be considered a place where effluents are treated.*

⁵ USEPA, 1991, Technical Support Document for Water Quality-based Toxics Control (TSD), and 1993 Water Quality Standards Handbook, Second Edition (WQSH)

Guidelines in the Indiana Water Quality Standards for demonstrating the appropriateness of a mixing zone in State waters are presented in the following paragraph.

327 IAC 2-1.5-7 Mixing Zone Guidelines. "(a) All surface water quality criteria in this rule, except those provided in section 8(b)(1) of this rule, are to be applied at a point outside of the mixing zone as determined under 327 IAC 5-2-11.4 to allow for a reasonable mixture of waste effluents with the receiving waters.

Indiana does have a prohibition for the use of mixing zones in permitting, hence, Amoco is not requesting (nor does it need) a mixing zone for Indiana-defined bioaccumulative constituents of concern (BCCs).

As a mixing zone is appropriate for Outfall 001, Amoco proceeded to fulfill the Indiana requirements to demonstrate that a mixing zone can be defined and is applicable to assure attainment of water quality criteria. The implementation of a mixing zone will continue to maintain water quality standards for Lake Michigan without requiring unnecessary wastewater treatment and increased multi-media impacts.

1.4 BASIS FOR ALLOWANCE OF A MIXING ZONE

In discussing mixing zones, terminology frequently varies with the intent and context of the discussion. For instance, the use of certain terms may depend on whether the discussion relates to engineering (hydrodynamics and modeling), field assessment (scientific measurements), or laws and guidance (regulatory). Federal and individual state laws and guidances often have specific defined mixing zone terms, therefore, selected terms and their corresponding definition used in this report are presented in Table 1-3.

When a liquid effluent is discharged to a lake, a natural area of mixing is created. This area of mixing is where the effluent commingles, spreads out, and disperses in the receiving water. Initially, mixing is driven by the hydraulic force of the discharged water. This zone is defined as the jet entrainment zone. After the hydraulic energy of the effluent is dissipated, differences in density and relative movement of the spreading effluent and the receiving water body combine for further mixing, described as the transition zone. The jet entrainment zone and transition zone combine to form the near-field mixing zone. Eventually, the natural currents of the receiving waterbody become the dominant force.

This area is defined as the far-field mixing zone. Natural driving physical processes such as flow, density differences, temperature gradients, or variable chemical concentrations, continue to drive mixing between effluent and receiving water in this zone.

Water quality criteria based on Indiana Water Quality Standards are listed in Table 1-4 for metals and conventional constituents. Water quality criteria are defined by three factors:

- magnitude,
- duration, and
- frequency.

These factors are necessary to define criteria to protect the designated use of the waterbody. The criteria consider both the acute (short-term) effects and the chronic (long-term) effects. Short-term and long-term effects are measured through laboratory toxicity bioassay testing of a chemical. Acute criteria are based on protecting the most sensitive species from acute effects and are expressed as Acute Aquatic Criteria (AAC). For example, Indiana's AAC for chlorides is expressed as: 860 mg/L (magnitude) of chlorides as a one-hour (duration) average concentration not to be exceeded more than once every three years (frequency) on average. The Chronic Aquatic Criteria (CAC) are derived to protect the most sensitive species from chronic toxic effects and are expressed as a four-day average concentration. For instance, Indiana's CAC for chlorides is expressed as: 230 mg/L (magnitude) of chlorides as a four-day (duration) average not to be exceeded more than once every three years (frequency) on average.

As stated in 327 IAC Articles 2 and 5, the AAC and CAC, due to their duration (exposure) and frequency (time) elements, are to be met in the receiving water. To ensure protection of the receiving water, the point of application of criteria are:

- AAC at edge of the Discharge-Induced Mixing Zone (DIMZ) (327 IAC 2-1.5-8(b)(1)(E)(i))
- CAC at the edge of the applicable mixing zone (327 IAC 2-1.5-8(b)(2))

Indiana Articles 2 and 5 also state that the Continuous Chronic Criteria (CCC), which includes the CAC as well as any other Tier II chronic criteria, apply at the edge of the

"applicable mixing zone"⁶. Similarly, Tier II acute criteria apply at the edge of the "discharge-induced mixing zone" (DIMZ).

The USEPA⁷ has determined that travel time through an acute mixing zone (DIMZ) must be roughly less than fifteen minutes if a one-hour average exposure is not to exceed the acute criterion. In addition, USEPA has recommended receiving water flow or velocity design conditions to establish the mixing zone to mimic the three-year return interval. This type of assessment for receiving water quality addresses the magnitude (acute criteria concentration to be attained at edge of DIMZ), duration (rapid mixing of less than 15 minutes to minimize exposure), and frequency (critical/conservative receiving water velocity or flow) of exposure.

To reconcile hydraulic and Indiana regulatory terms, this mixing zone demonstration equates the "discharge-induced mixing zone" to the "jet entrainment zone". The "applicable mixing zone" equates to the "far-field zone" and is also referred to as an "alternate mixing zone"⁸ when a site-specific mixing zone demonstration is requested. For a Lake Michigan discharge, the extent of the alternate mixing zone is limited to the discharge-induced mixing zone (327 IAC 5-2-11.4(b)(2)(A)(v)), hence, only one delineated area and one dispersion ratio will apply to the DIMZ. At this point, both the AAC and CAC criteria are to be attained. Therefore, this demonstration delineates the discharge-induced mixing zone for the Amoco Outfall 001.

1.5 INDIANA MIXING ZONE REQUIREMENTS

In February of 1997, Indiana adopted new water quality standards (WQS). The 1997 WQS are based on the USEPA Water Quality Guidance for the Great Lakes System (commonly referred to as the "GLI") 40 CFR Part 132. The GLI WQS establish numeric standards for some specific chemicals and a procedure for developing numeric WQS for other specific chemicals. In addition, the GLI WQS adopt mixing zone criteria for use in converting the numeric criteria into water quality-based effluent limits (WQBELs).

⁶ 327 IAC 2-1.5-8(b)(2) refers to applicable mixing zones and 327 IAC 5-2-11.4(b)(2)(A)(ii) refers to alternative mixing zones in defining where chronic criteria are to be attained.

⁷ USEPA, 1991 TSD, and 1993 WQSH

⁸ Pursuant to 327 IAC 5-2-11.4(b)(2)(A)(i), (ii), and (iii) and (b)(3)(B)(i) and (ii) and (C)

An applicant must address the following items in an application for a mixing zone:

- Document the characteristics and location of the outfall structure, including whether technologically enhanced mixing will be utilized.
- Document the amount of dilution occurring at the boundaries of the proposed mixing zone and the size, shape, and location of the area of mixing, including the manner in which diffusion and dispersion occur.
- For sources discharging to the open waters of Lake Michigan, define the location at which discharge-induced mixing ceases.
- Document the physical, including substrate character and geomorphology, chemical and biological characteristics of the receiving waterbody, including whether the receiving waterbody supports indigenous, endemic or naturally occurring species.
- Document the physical, chemical, and biological characteristics of the effluent.
- Document the synergistic effects of overlapping mixing zones or the aggregate effects of adjacent mixing zones.
- Show whether organisms would be attracted to the area of mixing as a result of the effluent character.

327 IAC 5-2-11.4(b)(4)(A)(i)-(vii).

IDEM must grant the mixing zone if an applicant demonstrates the following:

- The mixing zone would not interfere with or block passage of fish or aquatic life.
- The level of pollutant permitted in the waterbody would not likely jeopardize the continued existence of any endangered or threatened species listed under Section 4 of the ESA or result in the destruction or adverse modification of such species habitat.
- The mixing would not extend to drinking water intakes.
- The mixing zone would not impair or otherwise interfere with the designated uses of the receiving water or downstream waters.
- The mixing zone would not promote undesirable aquatic life or result in a dominance of nuisance species.
- By allowing the additional mixing: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other

matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced.

- In no case shall a mixing zone for a discharge into the open waters of Lake Michigan be granted that exceeds the area where discharge induced mixing occurs.

327 IAC 5-2-11.4(b)(4)(B)(i)-(vi).

If an applicant documents the required information and demonstrates the listed items, IDEM must grant the request for a mixing zone:

...unless the commissioner determines that the mixing zone should be denied based upon a consideration of harm to human health, aquatic life, or wildlife. The commissioner shall evaluate all available information, including information submitted by the public, relevant to the consideration of harm to human health, aquatic life, or wildlife. The commissioner shall identify the harm to human health, aquatic life, or wildlife, and document the rationale for this decision.

326 IAC 5-2-11.4(b)(4)(B)(6).

If an applicant satisfies its specified obligations under the rule, the burden shifts to IDEM to prove some specific harm that warrants the denial of the mixing zone.

As documented in Sections 2 and 3, Amoco has satisfied its obligation under the rule in demonstrating that a mixing zone is appropriate for Outfall 001.



TABLE 1-1. NPDES OUTFALL 001 DISCHARGE LIMITATIONS AND EFFLUENT QUALITY

| PARAMETER | UNITS | 1990 PERMIT LIMITS (a) | | HISTORICAL PERFORMANCE (b) | |
|---------------------|---------|------------------------|---------------|----------------------------|---------------|
| | | MONTHLY AVERAGE | DAILY MAXIMUM | MONTHLY AVERAGE | DAILY MAXIMUM |
| TBOD5 | lbs/day | 4,161 | 8,164 | 721 | 3,580 |
| TSS | lbs/day | 3,646 | 5,694 | 2,059 | 4,904 (c) |
| COD | lbs/day | 30,323 | 58,427 | 7,973 | 18,515 |
| Oil & Grease | lbs/day | 1,368 | 2,600 | 463 | 1,594 |
| Phenolics (4AAP) | lbs/day | 20.33 | 73.01 | 3.1 | 17.9 |
| Ammonia as N | lbs/day | 1,030 | 2,060 | 551 | 1,446 |
| Sulfide | lbs/day | 23.1 | 51.4 | 6.7 | 14.3 |
| Total Chromium | lbs/day | 23.90 | 68.53 | 2.4 | 5.3 |
| Hexavalent Chromium | lbs/day | 2.01 | 4.48 | 0.6 | 1.2 |

Notes:

- (a) 1990 Permit Limits are based upon previous permit effluent limitations since they were more stringent than BPT/BAT limits.
- (b) Historical performance based on monthly DMR data for April 1991 to April 1994 (consistent with Form 2C).
- (c) Daily maximum does not include a 24-hour time period when the WWTP experienced a known upset condition on August 31, 1993.

BPT - Best Practicable Control Technology Currently Available

BAT - Best Available Technology Economically Achievable

TABLE 1-2. WATER QUALITY MANAGEMENT PROGRAM ELEMENTS

| ELEMENT | DATE INITIATED | DATE COMPLETED |
|---|-----------------------|-----------------------|
| EFFLUENT CHARACTERIZATION | | |
| - Chemical Specific | 1990 | Ongoing |
| - Flow/Hydraulics | 1991 | Ongoing |
| - Whole Effluent Toxicity Studies | 1991 | 1993 |
| TREATABILITY STUDIES | 1991 | 1994 |
| SOURCE CONTROL | 1991 | Ongoing |
| WWTP UPGRADES | 1991 | Ongoing |
| BENZENE NESHAP CONTROL PROJECTS | 1990 | 1994 |
| SARA (TRI) EMISSION REDUCTION PROJECTS | 1990 | Ongoing |
| ZEBRA MUSSEL CONTROL | 1992 | Ongoing |
| STORMWATER QUALITY CONTROL PROJECTS | 1992 | Ongoing |
| RECEIVING WATER CHARACTERIZATION | | |
| - Hydraulics | 1990 | Ongoing |
| - Chemical Bioavailability | 1991 | Ongoing |
| - Aquatic Biological Community & Habitat Characterization | 1992 | Ongoing |
| - Background Water Quality | 1991 | Ongoing |
| POINT OF APPLICATION ESTABLISHMENT FOR IN-STREAM WATER QUALITY CRITERIA (Mixing Zone Delineation) | 1990 | 1997 |
| WASTELOAD ALLOCATION DETERMINATION | 1992 | 1997 |
| SITE-SPECIFIC WATER QUALITY CRITERIA ASSESSMENT | 1991 | 1993 |
| PRELIMINARY DIFFUSER DESIGN | 1994 | 1994 |

TABLE 1-3. MIXING ZONE TERMINOLOGY FOR LAKE MICHIGAN




TABLE 1-3. MIXING ZONE TERMINOLOGY (continued)

| FOOTNOTES | ABBREVIATION | DEFINITION |
|-----------|--------------|---|
| (1) | DIMZ | <p>Discharge-Induced Mixing Zone:</p> <p>Concentrations of toxic substances shall not exceed the CMC outside the zone of initial dilution ... unless an alternate mixing zone demonstration is conducted and approved in accordance with 327 IAC 5-2-11.4(b)(4), in which case, the CMC shall be met outside the discharge-induced mixing zone ... (327 IAC 2-1.5-8(b)(1)(E)(i)).</p> <p>In no case shall a mixing zone for a discharge into the open waters of Lake Michigan be granted that exceeds the area where discharge-induced mixing occurs. (327 IAC 5-2-11.4(b)(4)(C)).</p> |
| (2) | MZ | <p>Mixing Zone:</p> <p>An area contiguous to a discharge where the discharged wastewater mixes with the receiving waters. Where the quality of the effluent is lower than that of the receiving waters, it may not be possible to attain within the mixing zone all beneficial uses which are attained outside the zone. The mixing zone should not be considered a place where effluents are treated. (327 IAC 2-1.5-2(55)).</p> <p>In addition, this is equivalent to the designated mixing zone and the approved mixing volume. (327 IAC 5-2-11.3(b)(1)(C)(iii)(HH) and 5-2-11.7(c)(4)).</p> <p>At all times, all waters outside of the applicable mixing zones determined in accordance with 327 IAC 5-2-11.4(c) through (f) shall be free of substances in concentrations ... chronically toxic to, or be carcinogenic, mutagenic, or teratogenic to humans, animals, aquatic life, or plants. (327 IAC 2-1.5-8(b)(2)).</p> <p>For discharges into the open waters of Lake Michigan, ... for allocations based on acute aquatic life criteria of values, the CMC shall not be exceeded ... , unless a mixing zone demonstration is conducted and approved under subdivision (4), in which case the CMC shall be met outside the alternative mixing zone. (327 IAC 5-2-11.4(b)(2)(A)(i)).</p> <p>... chronic criteria or value shall not be exceeded ... unless an alternative mixing zone is demonstrated ... (327 IAC 5-2-11.4(b)(2)(A)(ii)).</p> <p>Historical Footnote:</p> <p>In the March 23, 1995 federal GLI, USEPA used the term "alternate mixing zone" to differentiate a demonstrated mixing zone using site information from a 10:1 default dilution. Indiana adopted this terminology but eliminated the default dilution in its regulations when implementing the GLI.</p> |
| (3) | AAC | Acute Aquatic Criteria: Receiving water application point. (327 IAC 5-2-11.4(b)(2)(i)(AA)). |
| | CAC | Criterion Aquatic Concentration: Receiving water application point. (327 IAC 5-2-11.4(b)(2)(ii)(AA)). |
| | AAC/CAC | For a discharge with an approved alternate mixing zone, acute and chronic wasteload allocations are calculated using the same mixing ratio. (327 IAC 5-2-11.4(c)(4)(B) and (5)). |

TABLE 1-4. INDIANA WATER QUALITY CRITERIA

| Parameter | Acute Aquatic Life CMC, total (µg/L) | Chronic Aquatic Life CCC, total (µg/L) | Human Health Noncancer Drinking (µg/L) | Human Health Noncancer Nondrinking (µg/L) | Background Concentration (b) (µg/L) |
|------------------------------|--------------------------------------|--|--|---|-------------------------------------|
| Tier I (a) | | | | | |
| Ammonia-N Summer | 3,600 | 820 | | | 2.7 |
| Ammonia-N Winter | 6,940 | 1,580 | | | 2.7 |
| Arsenic (III), Total (c) | 339.8 | 147.9 | | | 0.84 |
| Chlorides | 860,000 | 230,000 | | | 12,640 |
| Chromium (VI), Total | 16.02 | 10.98 | 134 | 14,000 | 0 |
| Chromium (III), Total (d)(e) | 2,402.88 | 114.85 | 410,000 | 43,000,000 | 0 |
| Copper, Total (e)(g) | 19.48 | 12.59 | 280 | 56,000 | 22.13 |
| Cyanide, Free (f) | 22 | | | | 0.3 |
| Cyanide, Total | | | 600 | 48,000 | 0.3 |
| Fluoride | 11,000 | 1,000 | | | 127 |
| Iron, Dissolved | | 300 | | | 41.3 |
| Nickel, Total (e) | 631.20 | 70.18 | 460 | 42,000 | 0.14 |
| Selenium, Total | | 5.00 | | | 0.05 |
| Sulfates | | 250,000 | | | 25,866 |
| Total Dissolved Solids | | 750,000 | | | 167,270 |
| Zinc, Total (e) | 161.27 | 161.27 | 9,000 | 246,000 | 5.27 |

Notes:

- (a) Tier I criteria presented for compounds detected or believed present in Outfall 001 (except As (III), which is not detected in Outfall 001).
- (b) Background concentration = Whiting Intake Jan 1992 to Dec 1995 calculated as per 327 IAC (5-2-11.4(a)(8)).
- (c) Assume Arsenic (III) background is equal to value from arsenic, total database.
- (d) Assume Chromium (III) background is equal to value from chromium, total database.
- (e) Chromium (III), Copper, Nickel, and Zinc are Hardness dependent (Hardness = 142 mg/L).
- (f) Assume Cyanide, free background is equal to value from cyanide, total database.
- (g) Background database is for both total and dissolved copper is under evaluation by IDEM due to concerns with current database validity.



AMOCO OIL COMPANY - WHITING REFINERY
WHITING, INDIANA





FIGURE 1-1
LOCATION MAP
WHITING, INDIANA


**FIGURE 1-2
AREA MAP
AMOCO OIL COMPANY - WHITING REFINERY**



SOURCE: USGS 7.5 min. TOPOGRAPHIC MAPS LAKE CALUMET ILL. AND WHITING, IND. 1991

FIGURE 1-3

**WASTEWATER TREATMENT PLANT - WATER FLOW DIAGRAM
AMOCO OIL COMPANY - WHITING REFINERY**



SECTION 2

SECTION 2.0

MIXING ZONE DISPERSION ANALYSIS

Amoco proposes to install a multiport diffuser for the discharge of treated effluent from Outfall 001. Though it is not necessary to satisfy Indiana mixing zone demonstration requirements, the use of a multiport diffuser provides an additional amount of environmental protection by ensuring more rapid and immediate mixing than is provided by the existing outfall.

2.1 MULTIPORT DIFFUSER MODELING

Amoco has evaluated a proposed diffuser location (Site S3500) in Lake Michigan as shown in Figure 2-1. The rationale for this site is to maximize mixing with ambient waters by locating the diffuser in deeper waters where more water volume is available for rapid mixing than is available at the current Outfall 001. Site S3500 is located in Lake Michigan approximately 3,500 ft from the current Outfall 001 in water depths measured at 28 to 30 ft. Specific benefits of a multiport diffuser at this location include:

- 1) The diffuser, by design, provides even more rapid and immediate mixing in a small area.
- 2) The diffuser would be located offshore, thereby minimizing plume contact with Lake Michigan shoreline.
- 3) The diffuser site would be exposed to the general nearshore current/circulation patterns that enhance local mixing.
- 4) The discharge would be present in deeper waters completely submerged and surrounded by lake water available for entrainment (induced mixing). Vertical mixing throughout the water column would be achieved as the positively buoyant plume rises toward the surface.

In order to evaluate the dispersion and size of a mixing zone from a multiport diffuser, the USEPA-endorsed computer model CORMIX, developed by Dr. Gerhard Jirka at Cornell University, was used for analysis. Specifically, the CORMIX2 expert system was utilized to determine achievable dispersion at the edge of the Jet Entrainment Zone, the Near-

Field Zone, and the Far-Field Zone. CORMIX2 calculates plume characteristics (i.e., dispersion, plume width) for specific regions (modules) of the mixing zone which are defined by discharge and ambient water classification criteria. The specific regions are linked together by transition equations resulting in a complete projection of the plume up to a user-specified distance. Although several computer models are listed in the USEPA 1991 TSD, CORMIX2 has been commonly used by regulators as a useful analysis tool for NPDES permitting. CORMIX2 was also selected because it integrates both near-field and far-field projections with customized transition equations. The CORMIX2 model also features additional sensitivity to receiving water boundaries. CORMIX2 provided the model estimates given in the remainder of this report. As noted in Attachment 1, computer models usually underestimate achievable dispersion. This overestimate of exposure leads to a conservative estimate of the evaluation of risk impact.

2.1.1 Model Input Parameters and Diffuser Design

The main criterion for development of an effective diffuser design is to maintain a specific port exit velocity at the average effluent flowrate. The USEPA 1991 TSD recommends maintaining a 10 ft/sec port exit velocity to ensure rapid mixing. If the effluent flow rate and exit velocity are known, the port diameter can be determined for a selected number of diffuser ports. Table 2-1 presents various configurations for a diffuser discharging the average Outfall 001 flowrate of 13 mgd. For this analysis, a 90-ft diffuser (approximate length) with ten 6-in diameter ports spaced 10 ft apart was chosen as an appropriate design for the Amoco discharge (see Attachment 2). The diffuser is unidirectional with all 10 ports pointing toward the center of the lake (due north, away from shore). The 6-in diameter ports and 10-ft port spacing provide standard dimensions for ease of installation and still maintain a 10 ft/sec exit velocity (actually calculated as 10.3 ft/sec). Other configurations could be used for final design; however, port diameters should not be too small where clogging from debris might occur and spacing should be large enough where immediate entrainment of adjacent ports is avoided. Modeling results for various diffuser designs (Table 2-1) revealed slight differences in jet entrainment zone dispersion for alternate design configurations, yet were within the relative range of accuracy of the model of the 10 port design.

Table 2-2 presents the remaining input parameters for the CORMIX2 simulations. Bathymetry measurements taken May 11, 1994 verified that Site S3500 is located at a lake depth of 28.5 ft. Long-term average effluent and lake temperatures revealed an annual average temperature difference of 17 °C. The effluent plume is usually warmer than the receiving water and a temperature difference of 20 °C was used in the model. Field measurements of lake temperature and conductivity taken during the long term bioassessment program (1994 to 1997), as shown in Table 2-3, revealed no significant temperature or conductivity gradients (i.e., no thermal stratification) in the Lake Michigan at the S3500 location. Furthermore, field measurements of conductivity confirmed that differences between the effluent and lake were negligible with respect to density in fresh water. Therefore plume buoyancy is driven solely by temperature differences. The positively buoyant condition (effluent temperature greater than receiving water temperature by 20 °C) resulted in the use of a 0 degree (horizontal) port discharge angle, where the plume rises to the surface and is exposed to the full vertical water column.

Lake velocity (current) in nearshore Lake Michigan is influenced by several forces (primarily wind) and changes in both speed and direction. Ambient velocity is a significant mixing force, especially in the far-field zone, as increased lake velocity will increase plume dispersion. Localized wind currents and along-shore physical features create a continuously dynamic condition in the lake. For the location of S3500, wind currents provide the predominant transport mechanism. Based on Midway Airport meteorological data compiled by NOAA (Attachment 3), the prevailing wind direction for the south end of Lake Michigan is out of the south at an average speed of around 10 knots. A general engineering rule for estimating lake currents generated by surface wind is to multiply the wind speed by one-thirtieth (1/30) to obtain the wind-induced lake velocity. Therefore, this would result in an average lake velocity of around 0.18 m/sec (0.59 ft/sec). A summary of measured nearshore Lake Michigan currents, primarily for Argonne National Laboratory studies conducted in the Calumet area, is presented in Table 2-4. For purposes of this analysis, a condition representing conservative lake velocity (0.10 m/sec) was used. The 0.10 m/sec lake velocity is less than velocity values derived from prevailing wind data and is consistent with the range of actual measured values.

2.1.2 Model Results

For the input parameters described above, model runs were conducted for dispersion estimation as a function of distance from the diffuser at S3500. The model output is given in Attachment 4 and graphically presented in Figure 2-2. At S3500, the plume is projected to be fully vertically mixed in the jet entrainment zone (per CORMIX2 classification) and extends to a distance of one-half of the diffuser length (45 to 50 ft). The one-half to one diffuser length distance provides a conservative guide for establishing the extent of the jet entrainment zone, or the Discharge-Induced Mixing Zone (DIMZ) (1980 Lee and Jirka). The dispersion projected at this distance is 54:1 for S3500. As discussed in Section 1, the USEPA's 1991 TSD states that if the travel time through the acute mixing zone (DIMZ) is less than 15 minutes, then the AAC (based on one-hour exposure) is not exceeded. CORMIX2 projects a time of plume travel of less than 90 seconds to reach the edge of the DIMZ (45 to 50 ft).

After the jet entrainment zone, the CORMIX2 model projects a transition zone that is "insignificant in spatial extent and will be bypassed" (see CORMIX Model output, Attachment 4). Therefore, there is no additional dispersion gained in the transition zone and the extent of the Near-Field Zone is equal to the extent of the DIMZ. At the DIMZ, the extent of discharge-induced mixing is equal to 45 to 50 ft from the diffuser where a dispersion of 54:1 is achieved. Since Indiana law limits the mixing zone to the DIMZ for a Lake Michigan discharger, Amoco proposes a mixing zone of 50 feet around the diffuser structure.

Past the Near-Field Zone, physical mixing continues, and CORMIX2 dispersion projects into the Far-Field Zone up to a user-specified distance of 3,300 ft. The actual extent of the Far-Field Zone, used for regulatory application is determined from regulatory definitions, not from hydrodynamic principles since the plume will continue to disperse at the molecular level over great distances. The 1991 TSD suggests that the DIMZ occupy 10 percent of the far-field zone, therefore, an appropriate far-field distance of 500 ft can be established for the Amoco diffuser. At this distance, CORMIX2 projects an effluent dispersion of 77:1 for the far-field zone. A total mixing zone of 500 feet radius around the diffuser structure is consistent with USEPA approaches to protecting the environment.

2.2 SUMMARY

The mixing zone dispersion analysis for a multiport diffuser located at S3500, conducted in accordance with USEPA guidance, shows that the proposed discharge configuration adds a margin of safety to protect the quality of the receiving waters compared to the existing outfall structure. This enhanced environmental protection is due to the rapid and immediate mixing that occurs within a small area as a result of the diffuser.



TABLE 2-1. PORT SIZES AND SPACING FOR A 90-FT MULTIPORT DIFFUSER

| NUMBER OF PORTS | EFFLUENT FLOW (mgd) | EFFLUENT FLOW (cfs) | EXIT VELOCITY (ft/sec) | PORT AREA (sq ft) | PORT DIAMETER (in) | DIFFUSER PORT SPACING (ft) |
|-----------------|---------------------|---------------------|------------------------|-------------------|--------------------|----------------------------|
| 1 | 13.0 | 20.1 | 10 | 2.01 | 19.2 | |
| 2 | 13.0 | 20.1 | 10 | 1.01 | 13.6 | 90.0 |
| 3 | 13.0 | 20.1 | 10 | 0.67 | 11.1 | 45.0 |
| 4 | 13.0 | 20.1 | 10 | 0.50 | 9.6 | 30.0 |
| 5 | 13.0 | 20.1 | 10 | 0.40 | 8.6 | 22.5 |
| 6 | 13.0 | 20.1 | 10 | 0.34 | 7.8 | 18.0 |
| 7 | 13.0 | 20.1 | 10 | 0.29 | 7.3 | 15.0 |
| 8 | 13.0 | 20.1 | 10 | 0.25 | 6.8 | 12.9 |
| 9 | 13.0 | 20.1 | 10 | 0.22 | 6.4 | 11.3 |
| 10 | 13.0 | 20.1 | 10 | 0.20 | 6.1 | 10.0 |
| 11 | 13.0 | 20.1 | 10 | 0.18 | 5.8 | 9.0 |
| 12 | 13.0 | 20.1 | 10 | 0.17 | 5.5 | 8.2 |
| 13 | 13.0 | 20.1 | 10 | 0.15 | 5.3 | 7.5 |
| 14 | 13.0 | 20.1 | 10 | 0.14 | 5.1 | 6.9 |
| 15 | 13.0 | 20.1 | 10 | 0.13 | 5.0 | 6.4 |

Note:

10-port diffuser selection based on design experience.

TABLE 2-2. CORMIX2 MODEL INPUT PARAMETERS

| PARAMETER | VALUE | RATIONALE |
|----------------------------|--------------------------|--|
| Effluent flow | 13 mgd | Long term average |
| Port exit velocity | 10.3 ft/sec | EPA TSD recommendation |
| Number of ports | 10 | Standard design (Table 2-1) |
| Port diameter | 6 in | Standard design (Table 2-1) |
| Diffuser length | 90 ft | Standard design (Table 2-1) |
| Port spacing | 10 ft | Standard design (Table 2-1) |
| Port discharge angle | 0 degrees | Optimizes plume buoyancy |
| Diffuser height off bottom | 1.6 ft (0.5 m) | Practical estimate |
| Effluent temperature | 30 °C | Long term average = 28 °C |
| Lake temperature | 10 °C | Long term average = 11 °C |
| Temperture difference | 20 °C | Conservative input (average = 17°C) |
| Minimal lake velocity | 0.33 ft/sec (0.10 m/sec) | Conservative input (average = 0.59 ft/sec) |

In each case, selection of each parameter value was made to result in smaller dispersion values than would have been calculated with average values. The aggregate result is that the dispersion in Lake Michigan is underestimated herein.

TABLE 2-3. LAKE MICHIGAN WATER QUALITY DATA

| | | Temperature (°C) | | | | | | | | | | | | | |
|------------|---------|------------------|---------|---------|---------|---------|---------|---------|--------|----------|----------|----------|----------|---------|---------|
| Date | 5/10/94 | 5/23/95 | 5/24/95 | 5/25/95 | 5/23/95 | 5/24/95 | 5/25/95 | 5/25/95 | 6/5/96 | 10/21/96 | 10/24/96 | 10/21/96 | 10/22/96 | 4/28/97 | 4/29/97 |
| Location | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 |
| Depth (ft) | | | | | | | | | | | | | | | |
| surface | 11.87 | 13.3 | 13.3 | 13.7 | 14 | 13.3 | 13.5 | 15 | 14.8 | 13.6 | 14.7 | 15.1 | 9.7 | 10.7 | 8.5 |
| 2 to 3 | | | | 13.7 | 14 | | | 15 | 14.8 | 13.6 | 14.7 | 15.1 | 9.7 | 10.7 | 8.5 |
| 5 to 6 | 11.87 | 13.3 | 13.3 | 13.7 | 13.3 | 13.3 | 13.5 | 15 | 14.8 | 13.6 | 14.7 | 15 | 9.1 | 10.7 | 8.5 |
| 8 to 9 | 11.85 | | | 13.7 | 13.2 | | 13.5 | 14 | 14.6 | 13.6 | 14.7 | 14.7 | 8.4 | 8.9 | 8.5 |
| 11 to 12 | 11.86 | 13.3 | 13.3 | 13.7 | 13 | 13.3 | 13.5 | 14 | 14.5 | 13.6 | 14.4 | 14.5 | 8.2 | 8.4 | 8.4 |
| 14 to 15 | 11.84 | 13.3 | 13.3 | 13.7 | 13 | 13.3 | 13.5 | 14 | 14.5 | 13.6 | 14.4 | 14.3 | 8 | 8.2 | 8.4 |
| 17 to 18 | 11.86 | | | 13.7 | 13 | | 13.5 | 14 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 8.1 | 8.3 |
| 20 to 21 | 11.84 | 13.3 | 13.3 | 13.7 | 12.7 | 13.3 | 13.5 | 14 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 8 | 8.3 |
| 24 to 25 | 11.85 | | | 13.7 | 12.5 | | 13.5 | 13 | 14.4 | 13.6 | 14.3 | 14.2 | 7.8 | 7.9 | 8.3 |
| 27 to 28 | | 13.3 | 13.3 | 13.7 | 12.2 | 13.3 | 13.5 | 13 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 7.8 | 8.3 |

| | | Conductivity (µmhos/cm) | | | | | | | | | | | | | |
|------------|---------|-------------------------|---------|---------|---------|---------|---------|--------|----------|----------|----------|----------|---------|---------|---------|
| Date | 5/10/94 | 5/23/95 | 5/24/95 | 5/25/95 | 5/23/95 | 5/24/95 | 5/25/95 | 6/5/96 | 10/21/96 | 10/24/96 | 10/21/96 | 10/22/96 | 4/28/97 | 4/28/97 | 4/29/97 |
| Location | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Depth (ft) | | | | | | | | | | | | | | | |
| surface | 285 | 301 | 295 | 298 | 301 | 291 | 289 | 300 | 308 | 294 | 306 | 299 | 313 | 318 | 291 |
| 2 to 3 | | | | 290 | 299 | | | 301 | 308 | 294 | 309 | 298 | 313 | 317 | 286 |
| 5 to 6 | 285 | 296 | 292 | 290 | 296 | 298 | 289 | 304 | 308 | 291 | 305 | 298 | 311 | 315 | 287 |
| 8 to 9 | 285 | | | 291 | 296 | | 290 | 297 | 306 | 294 | 305 | 297 | 303 | 306 | 291 |
| 11 to 12 | 285 | 289 | 289 | 292 | 295 | 301 | 290 | 305 | 305 | 298 | 301 | 294 | 303 | 303 | 290 |
| 14 to 15 | 285 | 305 | 293 | 291 | 296 | 300 | 292 | 300 | 305 | 294 | 304 | 292 | 301 | 304 | 290 |
| 17 to 18 | 285 | | | 294 | 297 | | 289 | 300 | 304 | 294 | 301 | 289 | 301 | 303 | 278 |
| 20 to 21 | 285 | 300 | 301 | 293 | 296 | 297 | 296 | 300 | 300 | 288 | 302 | 289 | 300 | 300 | 290 |
| 24 to 25 | 284 | | | 293 | 294 | | 294 | 300 | 300 | 289 | 300 | 289 | 300 | 298 | 294 |
| 27 to 28 | | 306 | 301 | 292 | 294 | 297 | 280 | 302 | 300 | 294 | 300 | 289 | 300 | 298 | 297 |

TABLE 2-4. SUMMARY OF LAKE MICHIGAN CURRENT MEASUREMENTS


| REFERENCE | DATE | FREQUENCY | NUMBER OF CURRENT METERS | CURRENT METER LOCATION | DEPTH | RESULT |
|------------------------------|-----------------------------|------------|-----------------------------|---|---------------------------|--|
| Snow 1974 | Nov. 8 to Dec. 8, 1973 | 20 min | 3 | At 68th St. Crib (1) Off Inland landfill (2) | 5.2m (1) 3m and 6m (2) | Typical lake currents on the order of 0.05 to 0.15 m/sec |
| Saunders 1976 | June 23 to Dec. 22, 1975 | Continuous | 5 | 3 km offshore from South Water Filtration Plant (SWFP) | 12 m (mid-depth) | Strong currents observed for Nov. 17 to Dec. 22 Speed range = 0.15 to 0.30 m/sec Maximum speed = 1.0 m/sec |
| McCown 1976 | Feb. 11 to Feb. 17, 1976 | 40 min | 3 | 3 km offshore from SWFP | 1m off bottom | Maximum speed observed was 0.15 m/sec |
| Harrison 1977 McCown 1978 | Jan. 4 to Mar. 26, 1977 | 8 min | 4 | 3 km offshore between Indiana Harbor Ship Canal (IHSC) and SWFP | 1.5 m off bottom | Average speed = 0.015m/sec Root-mean-square speed = 0.074 m/sec Maximum speed = 0.15 m/sec Significant ice cover present late Jan-early Feb. |

REFERENCES

Snow, October 1974, "Water Pollution Investigation: Calumet Area of Lake Michigan. Volume 1", IIT Research Institute.
 Saunders, et al., May 1976, "Nearshore Currents and Water Temperatures in Southwestern Lake Michigan (June - December, 1975)",
 Argonne National Laboratory (ANL).
 McCown, et al., July 1976, "Transport and Dispersion of Oil Refinery Wastes in the Coastal Waters of Southwestern Lake Michigan
 (Experimental Design - Sinking Plume Condition)", ANL.
 Harrison, et al, December 1977 "Pollution of Coastal Waters off Chicago by Sinking Plumes from the Indiana Harbor Canal", ANL.
 McCown, et al., November 1978, "Transport of Oily Pollutants in the Coastal Waters of Lake Michigan", ANL.




Figure 2-1
Water Depth at the Proposed Diffuser Location (S3500)



From: Calumet and Indiana Harbors NOAA Chart 14929

FIGURE 2-2. CORMIX2 RESULTS FOR
MULTIPOINT DIFFUSER



SECTION 3

SECTION 3.0 MIXING ZONE DEMONSTRATION

3.1 INTRODUCTION

To grant a mixing zone, the permittee must provide specific information to assure that a mixing zone is appropriate for the discharge. The necessary information for a mixing zone demonstration has been described by USEPA guidance and Indiana state rules to determine the boundaries of the mixing zone, the magnitude of mixing, the impact of the mixing zone on the receiving water, and the steps taken to prevent acute impacts to aquatic life and prevent impairment of the use of the water as follows:

- 327 IAC 5-2-11.4(b)(4)(A)(i) - Document the characteristics and location of the outfall structure, including whether technologically enhanced mixing will be utilized.
- 327 IAC 5-2-11.4(b)(4)(A)(ii) - Document the amount of dilution occurring at the boundaries of the proposed mixing zone and the size, shape and location of the area of mixing, including the manner in which diffusion and dispersion occur.
- 327 IAC 5-2-11.4(b)(4)(A)(iii) - For sources discharging to the open waters of Lake Michigan, define the location at which discharge-induced mixing ceases.
- 327 IAC 5-2-11.4(b)(4)(A)(iv) - Document the physical including substrate character and geomorphology, chemical and biological characteristics of the receiving waterbody, including whether the receiving waterbody supports indigenous, endemic or naturally occurring species.
- 327 IAC 5-2-11.4(b)(4)(A)(v) - Document the physical, chemical, and biological characteristics of the effluent.
- 327 IAC 5-2-11.4(b)(4)(A)(vi) - Document the synergistic effects of overlapping mixing zones or the aggregate effects of adjacent mixing zones.
- 327 IAC 5-2-11.4(b)(4)(A)(vii) - Show whether organisms would be attracted to the area of mixing as a result of the effluent character.

- 327 IAC 5-2-11.4(b)(4)(B)(i) - The mixing zone would not interfere with or block passage of fish or aquatic life.
- 327 IAC 5-2-11.4(b)(4)(B)(ii) - The level of pollutant permitted in the waterbody would not likely jeopardize the continued existence of any endangered or threatened species listed under Section 4 of the ESA or result in the destruction or adverse modification of such species habitat.
- 327 IAC 5-2-11.4(b)(4)(B)(iii) - The mixing would not extend to drinking water intakes.
- 327 IAC 5-2-11.4(b)(4)(B)(iv) - The mixing zone would not impair or otherwise interfere with the designated uses of the receiving water or downstream waters.
- 327 IAC 5-2-11.4(b)(4)(B)(v) - The mixing zone would not promote undesirable aquatic life or result in a dominance of nuisance species.
- 327 IAC 5-2-11.4(b)(4)(B)(vi) - By allowing the additional mixing: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced.
- 327 IAC 5-2-11.4(b)(4)(C) - In no case shall a mixing zone for a discharge into the open waters of Lake Michigan be granted that exceeds the area where discharge-induced mixing occurs.

This information is evaluated to assure that it is environmentally protective to use a mixing zone for the discharge and to define the point of application of receiving water quality standards. Also, to assist the Commissioner regarding additional information for assessing the mixing zone (based on aquatic life, human health, or wildlife), data and references are presented in Volume II (submitted August 1994) and in this revised volume.

Amoco proposes that a mixing zone be included in its renewed NPDES permit. The following discussion describes the physical, chemical, and biological characteristics of the receiving water (southern Lake Michigan). It also describes the Amoco Outfall 001 discharge at the proposed diffuser site. These characteristics are analyzed in the context of the specific points noted in Indiana 327 IAC 5-2-11.4(b)(4) to demonstrate that an appropriate mixing zone can be delineated in southern Lake Michigan consistent with Indiana rules and USEPA guidelines (1993 WQSH - Chpt 5, 1991 TSD - Chpt 2 & 4).

3.2 INDIANA MIXING ZONE REGULATORY REQUIREMENTS (327 IAC 5-2-11.4(b)(4))

As discussed in Attachment 1, the USEPA provides guidance on determining and assessing the applicability of mixing zone implementation for a discharge. As shown in Table A1-1, these USEPA specifications are incorporated into the Indiana Water Quality Standards. The following text presents the Indiana mixing zone demonstration regulatory language and Amoco's responses to the requirements.

327 IAC 5-2-11.4(b)(4)(A)(i) - Document the characteristics and location of the outfall structure, including whether technologically enhanced mixing will be utilized.

Technologically enhanced mixing will be provided by the use of a state-of-the-art high-rate multiport diffuser. A high-rate diffuser maximizes mixing and minimizes organism exposure time. The preliminary design of this diffuser (Attachment 2) includes the following characteristics:

- header length = 90 ft
- number of ports = 10
- port spacing = 10 ft
- port diameter = 6 in
- diffuser orientation = unidirectional with ports pointing due north (away from the shore toward the center of the lake)
- vertical port discharge angle = 0 degrees from horizontal
- diffuser height off lake bottom = 1.6 ft

The diffuser will be located about 3,500 ft northeast of the current Outfall 001 at latitude 87° 28.093'W and longitude 41° 40.976'N. These coordinates correspond to Station S3500 of the current long-term bioassessment program.

327 IAC 5-2-11.4(b)(4)(A)(ii) - Document the amount of dilution occurring at the boundaries of the proposed mixing zone and the size, shape and location of the area of mixing, including the manner in which diffusion and dispersion occur.

The dilution (dispersion) ratio has been optimized by modeling a high-rate submerged multiport diffuser located approximately 3,500 ft from the current Outfall 001. Dispersion estimates were derived from the USEPA-supported model CORMIX2 as discussed in detail in Section 2. Using conservative model input parameters, including plume buoyancy and lake velocity, CORMIX2 projected a DIMZ dispersion of 54:1 at a distance of one-half diffuser length (45 to 50 ft) from the diffuser. The CORMIX2 DIMZ is hydraulically equivalent to the extent of the Near-Field Zone. Far-Field projections indicated an appropriate dispersion of 77:1 achieved at a distance of 500 ft from the diffuser.

As mentioned previously, since the Outfall 001 diffuser will be a discharge to the open waters of Lake Michigan, the applicable mixing zone dispersion is capped, as per 5-2-11.4(b)(4)(C), at the point where discharged induced mixing ceases. Therefore, the applicable mixing zone dispersion and distance are reduced to the corresponding CORMIX2 DIMZ values (54:1 and 50 ft, respectively). The applicable mixing zone would directly utilize a 54:1 dispersion for calculating both acute and chronic wasteload allocation values as presented in 327 IAC 5-2-11.4(c).

Amoco proposes delineating a mixing zone that maintains a 50-ft distance from all points on the diffuser. One can envision the mixing zone plan-view shape as a "racetrack" surrounding the 90-ft-long diffuser; one 100 ft x 90 ft rectangle centered over the diffuser length and one semi-circle area (radius = 50 ft) at each end. For the mixing zone, the vertical profile would occupy the entire average water depth (28 ft) within this area. A mixing zone that completely surrounds the diffuser is necessary to accommodate lake velocities induced by winds of various directions. The mixing zone shape described above corresponds to lateral area of 0.39 acre. A conceptual sketch of the mixing zone is given in Figure 3-1.

The mixing zone area would be located about 3,500 ft northeast of the current Outfall 001 at longitude 87° 28.093'W and latitude 41° 40.976'N as shown in Figure 3-2. The mixing

zone would not overlap any adjacent mixing zones or outfalls. Furthermore, the mixing zone will not contact any shorelines or other receiving waters since they are greater than 50 ft away from the diffuser.

The manner in which diffusion and dispersion will occur is through rapid and immediate mixing of discharged effluent with Lake Michigan receiving water. The diffuser is designed to maintain the USEPA-recommended discharge exit velocity of 10 ft/sec at average effluent flowrate (i.e., 13 mgd). This discharge velocity (in excess of ambient velocity) entrains surrounding Lake Michigan water to effectively mix the effluent within a turbulent local environment.

327 IAC 5-2-11.4(b)(4)(A)(iii) - For sources discharging to the open waters of Lake Michigan, define the location at which discharge-induced mixing ceases.

The diffuser will be located in the open waters of Lake Michigan. Discharge-induced mixing ceases at the edge of the CORMIX2 DIMZ, which is equivalent to the edge of the Near-Field Zone where plume velocity approaches ambient lake velocity. For the model application chosen to simulate initial mixing, plume velocity was not given as a function of distance from the diffuser. However, based on the research references used to develop the model equations, the length of the DIMZ can be defined as one-half to one diffuser length downstream from the diffuser. For the 90-ft diffuser, this corresponds to a DIMZ distance of 45 to 90 ft. Amoco proposes a DIMZ distance of 50 ft as a conservative value consistent with the appropriate means to delineate a mixing zone.

In practice, the exact location where discharge-induced mixing ceases will depend on the magnitude and direction of the wind-induced lake velocity. To accommodate all potential lake current directions a mixing zone that surrounds the entire diffuser is proposed. For this mixing zone, this corresponds to a 0.39 acre area shaped like a "racetrack" that is 50 ft from all points from the diffuser (see Figure 3-1).

327 IAC 5-2-11.4(b)(4)(A)(iv) - Document the physical including substrate character and geomorphology, chemical and biological characteristics of the receiving waterbody, including whether the receiving waterbody supports indigenous, endemic or naturally occurring species.

Information about the southern part of Lake Michigan has been published in numerous studies. Attachment 5 is a bibliography of technical documents relevant to this part of the lake. From a limnological basis, the deeper waters of Lake Michigan (typically termed "open waters" by limnologists) begin about 5 miles offshore in the southern part of the lake and respond to several physical forces (i.e., wind, thermal convection) which, in turn, affect the chemical and biological characteristics. Nearshore waters are most affected by local winds and shoreline and topographical features. These differences mean that the nearshore waters often have different physical, chemical, and biological characteristics than the deeper open waters. Studies within the nearshore zone, especially along the Indiana shore, likely provide more accurate information that may readily be extrapolated to the Amoco site.

Lake Michigan General Characteristics. Several studies have been conducted to characterize the circulation and transport of Lake Michigan waters. The causes and characteristics of Lake Michigan currents are dependent upon the location within the lake. Snow (1974) describes the primary causes of lake transport in the open (deep) waters (away from shore), such as wind forces, thermal convection, and Coriolis forces (rotation of the Earth). Other general lakewide influences include density gradients, weather patterns, and precipitation.

The open waters of Lake Michigan respond to general seasonal transport patterns. Thermal convection (vertical stratification) is a significant seasonal influence on general lakewide mixing and refers to the tendency of lakes to form distinct temperature layers. Stratification is typically observed in summer and winter. During summer, the surface waters, warmed by the sun, become less dense than the cooler, deeper waters. A boundary, known as a thermocline, separates the bottom waters from the surface waters. Algal photosynthesis in the upper, sunlit layer (the epilimnion) may alter the water chemistry, increasing dissolved oxygen levels, and decreasing the level of carbon dioxide and algal nutrients. Biological respiration and excretion below the thermocline (in the

hypolimnion) tend to decrease dissolved oxygen levels and increase levels of carbon dioxide and nutrients. This stratification usually ends in autumn when the surface layer cools and the entire water column can more easily be mixed. During winter, another stratification may be established with the cooler waters on top of the lake and the warmer water below. This type of stratification ends in spring. An important feature of this stratification is the seasonal availability of nutrients, particularly in spring, which can encourage blooms of algae and their consumers, the zooplankton.

Lateral mixing of open waters results in observable lake currents. Baumgartner (1968), in conjunction with the Great Lakes Region of the Federal Water Pollution Control Administration (FWPCA), presented the results of field studies to define the general open water currents in Lake Michigan. The investigators found that currents do exist in the lake with complex interrelated flow patterns. Dr. Baumgartner testified: "[currents] vary in direction and magnitude from surface to depth, from length to width, and from side to side. The variability in time is significant on a seasonal basis, but important variabilities are also observed in shorter periods of time, such as days or even hours. Superimposed on the hourly variation is a continuous process of turbulent mixing of small parcels of water." Mortimer (1975) notes that the FWPCA report "does indeed present diagrams of average circulation for various seasons, depths, and wind regimes, but they are of little use for day-to-day prediction, because of overriding effects of short term fluctuations (internal waves and responses to local winds) and of the spatial complexity of these motions, particularly near shore."

Hence, in developing information for modeling dispersion of a discharge into the nearshore south end of Lake Michigan, there could be multiple influences on lake currents, of which one is wind induced. For a specific nearshore site (e.g., S3500), mixing dynamics could be more influenced by conditions near the area than the general lake-wide circulation. Thus in the CORMIX2 modeling, velocity data was reviewed specific to the area of the proposed diffuser to corroborate the use of wind-induced velocity as a transport mechanism at S3500.

To describe the biological characteristics of the receiving waters, Amoco implemented a Lake Michigan Biomonitoring Program in May 1994 within the area of the proposed diffuser to further evaluate limnological attributes of the nearshore zone and receiving water in

support of Volume II of August 1994. Biomonitoring activities have continued since May 1994 up to and including April 1997. The Biomonitoring Program was designed to document the physical, chemical, and biological components of the receiving water, confirm the observations presented in Volume II (August 1994), and provide information to further characterize Lake Michigan at the proposed diffuser location. Key findings of the Biomonitoring Program that address 327 IAC 5-2-11.4(b)(4)(A)(iv) are presented below for the receiving water and supported by the Biomonitoring Program Database and Summary Report included as Attachment 6.

Nearshore Physical Characteristics. Nearshore lake currents, such as those encountered at the proposed Amoco diffuser site, are caused primarily by localized winds, with less influence from thermal convection or Coriolis forces. Vertical temperature stratification is seldom observable in the shallower depths and, if present at all, not maintained for long periods. As evident from direct measurements at the study sites, the temperature, pH, dissolved oxygen, and specific conductivity profiles are uniform over the 28-ft depth with no direct gradient influences expected. Coriolis forces require travel distances much larger than the delineated mixing zone to be of any consequence to overall transport.

Boundary effects due to shore and topographical features also dominate lake currents in the nearshore area. Nearshore currents will mainly follow the general direction of the wind and, in the instance of the wind blowing toward the shore, the lake water will deflect to follow the shoreline. Wind forces of sufficient duration induce ambient velocities throughout the water column in shallow lake areas, such as the beach zone near Amoco's existing Outfall 001 discharge thereby increasing the mixing.

Direct measurements of lake currents near the southwest Lake Michigan shoreline were made during tracer studies performed by Argonne National Lab in the 1970s. Saunders, et al. (ANL, "Nearshore Currents and Water Temperatures in Southwestern Lake Michigan (June - December, 1975)"), conducted continuous current measurements at five mooring stations located at mid-depth approximately five miles offshore of south Chicago. Currents in the region were predominately parallel to shore. As an example of typical results, the net motion of the water during November 17 to December 22, 1975 was toward the southeast,

but at least 11 major current reversals occurred during this period. The average currents ranged from 0.15 to 0.30 m/sec with maximum observations of approximately 1.0 m/sec. Other current measurement studies are presented in Table 2-4.

Beach dune areas with gently sloping shores characterize the general lakeshore of the Indiana portion of Lake Michigan. Snow (1974) described the major substrate component of the nearshore Calumet area as comprised of sand. Bottom sediments can be resuspended from wave action and storms, as indicated by increased turbidity of nearshore waters during these events. Ayers (1967) also described the sediments of the southwestern corner of the lake to range from silty sand to till, with fine to coarse sands covering most of the area.

Amoco studies show that the substrate of Lake Michigan in the vicinity of the proposed diffuser is a flat plane of less than one percent slope that consists of 76 percent sand, 21 percent silt, and 2 percent clay. Gravel or larger sized particles are widely scattered and typically not encountered. Particle size distributions, presented in Attachment 6, reveal a mottled distribution of silty sand substrates ranging from 49 to 90 percent sand material. Divers have observed that the surface of the sand substrate exhibits surge (oscillation) ripples that are formed in response to wind direction and surface wavelength patterns. The oscillation ripples change in direction and form when bottom wave velocity is less than 0.76 m/sec and water surface wavelength is greater than twice the water depth. The ripples at the study sites typically exhibit a straight orientation over the transect distance observed at the study site (1,500 ft) and follow expected patterns of wave refraction from shoreline obstructions and wind direction (divers' observations). Surface ripples at the study sites have been observed to be from 2 to 4 inches in height and 3 to 10 inches from crest to crest and may change daily (divers' observations).

In summary, the proposed diffuser site is located in the nearshore zone of southern Lake Michigan approximately 3,500 ft from the shoreline in a relatively flat plain of sand-dominated substrates susceptible to disruption and re-arrangement by surface induced turbulence. The diffuser site does not encroach upon any navigation channels (nearest approximately 6,080 ft distance), docks (closest fishing pier 4,200 ft away), harbors (closest boat ramp and harbor approximately 5,125 ft away), or water intakes (closest water intake 1,640 ft away).

Key findings about the physical characteristics at the proposed diffuser site determined from the Biomonitoring Program and discussed in Attachment 6 include the following.

1. Water column measurements at this site indicate complete vertical mixing over the 28 ft depth.
2. Stratification of the water column due to temperature or density has not been observed and likely does not occur.
3. Bottom substrates consist mainly of sand (76 percent) and silt (21 percent) sized particles.
4. Bottom substrates are frequently moved and re-arranged by currents and wave action resulting from storms and other water surface turbulence.

Nearshore Chemical Characteristics. The chemical water quality of the proposed diffuser site is consistent with expected nearshore conditions for southern Lake Michigan. The biomonitoring program field studies showed no significant concentration gradients were present within the water column at the proposed diffuser site. General water quality parameter concentrations determined in the field indicate characteristics of oligotrophic to mesotrophic water quality conditions, fully oxygenated fresh water of low to moderate conductivity, neutral pH, and typical seasonal temperatures. Water chemistry parameters determined from laboratory analyses of water collected at the study sites are presented in Attachment 6. The water chemistry data is consistent with USEPA STORET monitoring data (1982-1995) for many parameters for the Whiting Water Intake Crib. A STORET inventory retrieval with summary statistics is given in Attachment 7.

The receiving water quality and water chemistry conditions at the proposed diffuser site were consistent with IDEM defined background concentrations monitored at the Whiting Intake (see Table 1-4). These background concentrations are based on Lake Michigan monitoring data and indicate that the lake has an assimilative capacity for many constituents without exceeding the Indiana Water Quality Standards.

Key findings for chemical characteristics at the proposed diffuser site determined from the Biomonitoring Program and discussed in Attachment 6 include the following.

1. Water quality attributes measured in the field and observed water chemistry concentrations reflected the oligotrophic to mesotrophic conditions in the region of the proposed diffuser site.
2. General conditions include high dissolved oxygen concentrations, neutral pH, low nutrient concentrations, and normal seasonal temperature fluctuations.
3. Secchi disk (transparency) depths were more dependent upon effects from local wind patterns and storms than chlorophyll-a concentrations which were frequently less than 1.0 milligram per cubic meter.
4. Water chemistry parameters did not indicate thermal stratification of the water column or show horizontal variation in concentration.

Nearshore Biological Characteristics. The extreme southern end of Lake Michigan has been generally classified as mesotrophic (Great Lakes Water Quality Board, 1977). This trophic status is intermediate between oligotrophic (clear water, low nutrient concentration, low biological productivity) and eutrophic (nutrient rich, highly productive). The mesotrophic classification was based on four criteria: phytoplankton, zooplankton, chlorophyll-a, and total phosphorus.

The biological characteristics of the receiving water at the proposed diffuser site are controlled by the natural physical settings. The flat, sandy bottom and naturally constant turbulence combine to exhibit characteristics of a flooded beach. These conditions result in a physically unstable habitat which, combined with fluctuations due to seasonal factors, limit the potential for developing a complex biological ecosystem. Few ecological studies have been conducted previously of this physically unstable "beach water zone" defined as less than 30 ft depth and less than two miles offshore (USFWS, 1970).

Amoco's Lake Michigan Biomonitoring Program was based on the concept that the most exposed communities would be most appropriate to measure (Figure 3-3). Additional focus was directed toward sessile and drifting organisms because of the greater potential for exposure to effluent from a fixed-point discharge. Biomonitoring results presented in Attachment 6 indicated that the phytoplankton drifting assemblage included numerous tychoplanktonic algae (taxa that persist in the water column but more commonly grow

attached to a substrate) that were likely re-suspended from the bottom surface. The assemblage of phytoplankton and zooplankton taxa were consistent with expectations for southern Lake Michigan, though their presence and distribution was likely determined primarily by wind-induced lake currents. Benthic (sessile) organisms in particular showed low density and species richness. The frequent disruption of the lake bottom from storms and surface turbulence within the beach water zone effectively created shifting sand substrates that limited complex benthic community development and productivity. Fish were seldom observed at the study sites⁹.

Key findings for biological characteristics at the proposed diffuser site determined from the Biomonitoring Program and discussed in Attachment 6 include the following:

1. Fish are not common at the study site. A lack of habitat structure, refugia, and food resources prevent the diffuser location from attracting high numbers of fish. Fish observed in the environs of the study site include non-native gobies and alewives.
2. The benthos assemblage exhibits low richness, low diversity, and a patchy distribution with respect to species and abundance.
3. Spatial and temporal variability of the benthos assemblage was high.
4. Frequent bottom surface disturbances from surface water wave action limits development of a complex benthos assemblage. Organisms that burrow into the substrate to avoid abrasion from shifting sands (oligochaete worms) or hard-shelled organisms (snails, clams, and mussels) that are more protected from abrasion appear to be most common.
5. The phytoplankton assemblages contain green algae, yellow-green algae, and diatoms, flagellates and blue-green algae forms. Diatoms dominate the assemblage. Tychoplanktonic algae re-suspended into the water column from the sediment surface were common. Richness and diversity of the phytoplankton were higher than benthos or zooplankton because of the tycho planktonic nature of this community.
6. The zooplankton assemblages exhibited low richness and low diversity. The zooplankton assemblage consisted of rotifers, cladocera and copepods. Dominant organisms included the copepod *Diacyclops bicuspidatus thomasi*, *Diaptomus* sp. and *Mesocyclops edax*, and the rotifer *Asplanchna herricki*. Abundance of these organisms was highly variable and reflected a highly patchy distribution.

⁹ A summary of representative fisheries obtained from USFWS (1996) is presented in Attachment 8.

7. Low values for fish abundance, phytoplankton and zooplankton density, Secchi disk depth, and chlorophyll-a concentrations were consistent with characteristic of oligotrophic to mesotrophic conditions for Lake Michigan at the proposed diffuser site.

327 IAC 5-2-11.4(b)(4)(A)(v) - Document the physical, chemical, and biological characteristics of the effluent.

The Amoco Outfall 001 effluent is freshwater with a temperature greater than the receiving water, thereby resulting in a positively buoyant discharge plume. The long-term average effluent flow rate is 13 mgd and the multiport diffuser is designed to maintain a port exit velocity of 10 ft/sec at this average flow rate. The diffuser will be designed to operate and provide suitable dispersion over an effluent flow range of 7 to 44 mgd. This is the range of short duration flows observed over three years (1991-1994). Chemical and biological characteristics of Outfall 001 are presented in Volume I Form 2C Part V and Part VII of this NPDES Permit Application. There are two major observations regarding effluent quality: 1) all maximum bioavailable concentrations of constituents are below the Indiana acute aquatic criteria; and 2) based on three years of effluent toxicity biomonitoring using standard USEPA methods and procedures, no acute toxicity has been measured or observed for the 001 effluent.

327 IAC 5-2-11.4(b)(4)(A)(vi) - Document the synergistic effects of overlapping mixing zones or the aggregate effects of adjacent mixing zones.

No mixing zones from other local discharges are located within or adjacent to the proposed Amoco diffuser mixing zone. The Amoco mixing zone will not contact the Lake Michigan shoreline or encroach upon drinking water or industrial intakes. The 0.39 acre mixing zone, which is 50 ft from all points on the diffuser header is about 3,500 ft from the current Outfall 001 side channel discharge.

327 IAC 5-2-11.4(b)(4)(A)(vii) - Show whether organisms would be attracted to the area of mixing as a result of the effluent character.

The effluent character will remain the same as currently discharged from Outfall 001. Temperature differences between ambient lake water and the effluent may attract fish.

The dispersion modeling estimates used an annual temperature differential of 20° C between effluent and ambient receiving water. However, heat dissipation through the 3,500-ft pipe and rapid mixing at the diffuser will reduce the temperature differential that currently exists at Outfall 001. The 10 ft/sec exit velocity at the diffuser ports will effectively create an "avoidance zone" immediately near the diffuser because of the excess energy expenditure required of fish to persist at this location. The proposed diffuser configuration and associated rapid mixing provides a smaller area of attraction than currently exists at outfall 001.

327 IAC 5-2-11.4(b)(4)(B)(i) - The mixing zone would not interfere with or block passage of fish or aquatic life.

The mixing zone will not interfere with or block passage of fish or aquatic life. No migratory routes or preferred passages for fish or benthic organisms capable of self-dispersion are known to exist in the proposed mixing zone area. The mixing zone will not interfere with or block passage of aquatic life dependent upon dispersion by currents and wave action. The size of the mixing zone delineated from the proposed diffuser (0.39 acre, 50 ft from all points on the diffuser header) is minimized to provide rapid and complete mixing within a small area. Since the mixing zone will be located in an area unconfined by immediate shoreline or other structures (3,500 ft from the current Outfall 001) and does not contact any shoreline, no obstruction of any migratory routes or passage of any indigenous aquatic species, including fish, can occur. The 90-ft diffuser header located on the lake bottom will also not be an obstruction to any migratory routes of any indigenous aquatic species.

327 IAC 5-2-11.4(b)(4)(B)(ii) - The level of pollutant permitted in the waterbody would not likely jeopardize the continued existence of any endangered or threatened species listed under Section 4 of the ESA or result in the destruction or adverse modification of such species habitat.

The level of pollutant in the waterbody will not jeopardize the continued existence of any endangered or threatened species or result in the destruction or adverse modifications to endangered or threatened species' critical habitat. Based on Indiana rules, there are no bioaccumulative chemicals of concern (BCCs) in the effluent, nor is the mixing zone

proposed for BCCs. Threatened and endangered species that are recognized under Section 4 of the ESA that occur in Indiana are presented in Attachment 9. Organisms that can occur in the nearshore zone of Lake Michigan that may encounter the mixing zone include birds, fish, crustaceans, mussels, and gastropods. No fish, crustaceans, or gastropods listed for the State of Indiana are indicated as federally recognized endangered or threatened species. The mussels identified as federally threatened or endangered are supported by critical habitats that exist in flowing waters. The proposed mixing zone would not be considered a critical habitat or critical food resource for bird species listed for northern Indiana, which include Peregrine falcon, bald eagle, and interior least tern.

327 IAC 5-2-11.4(b)(4)(B)(iii) - The mixing would not extend to drinking water intakes.

The Amoco mixing zone will not encroach upon drinking water or industrial intakes. The 0.39 acre mixing zone, which is 50 ft from all points on the diffuser header will be about 1,640 ft northeast of the City of Whiting/Amoco intake. The diffuser ports will discharge to the north towards the center of the lake. Amoco Outfall 001 effluent currently meets primary drinking water standards.

327 IAC 5-2-11.4(b)(4)(B)(iv) - The mixing zone would not impair or otherwise interfere with the designated uses of the receiving water or downstream waters.

Indiana Water Quality Standards are applied to protect and maintain the designated uses of waters of the state, including Lake Michigan. Lake Michigan is designated for uses as: a public, industrial, and agricultural water supply; full-body-contact recreation; and support for a well-balanced aquatic community. The water quality criteria (numeric and whole effluent) presented in 327 IAC 2-1.5-8 are based on protecting these uses of the water. Water quality standards given in 327 IAC 2-1.5-8 shall apply as defined by their in-stream derivation at appropriate points based on time, exposure, duration, and frequency. Attainment of the water quality standards at their appropriate points assures continued all designated uses of the waterbody. Amoco's mixing zone will not impair or interfere with the designated uses of Lake Michigan.

Lake Michigan is also used as a source of water for drinking water treatment plants. The nearest point of water intake is the Whiting intake located approximately 1,640 ft from the proposed diffuser. The mixing zone extends only to a distance of 50 ft from the diffuser. For those substances with primary drinking water standards, which are human health safety-based, as established by the Federal Safe Drinking Water Act, Outfall 001 maximum effluent concentrations are already less than these drinking water standards at end-of-pipe (prior to mixing with Lake Michigan) as presented in Table 3-1. In other words, Outfall 001 effluent contains smaller quantities of these substances than the concentrations given as the federal primary drinking water standards. Thus, Amoco's projected mixing zone will not adversely affect Lake Michigan as a source of drinking water.

327 IAC 5-2-11.4(b)(4)(B)(v) - The mixing zone would not promote undesirable aquatic life or result in a dominance of nuisance species.

The mixing zone is not expected to promote undesirable aquatic life or result in a dominance of nuisance species. With the exception of a beneficial reduction in area for mixing with receiving water, the character of the effluent will not change from current Outfall 001 conditions. The promotion of undesirable planktonic or benthic aquatic life, or dominance of nuisance species has not been observed, detected, or documented for the existing effluent discharge from Outfall 001. Increases in resident species or introduced exotic organisms that could possibly attain undesirable or nuisance status would likely result from changes in lake-wide water quality or biological dynamics, and not from the Outfall 001 mixing zone.

Indiana-specific nuisance and non-indigenous species information was unavailable; however, organisms listed as Species of Concern in the Nonindigenous Aquatic Nuisance Species State Management Plan (State of Michigan DEQ 1995) that have been observed or recorded at the proposed mixing zone site are the round goby fish and zebra mussel. The planktonic spiny water flea has not been recorded at the proposed diffuser site and distribution of the spiny water flea is dependent upon lake currents. The round goby fish has been observed after storm events feeding upon amphipod crustaceans associated with tangles of unattached organic debris transported along the lake bottom. It is anticipated that the mixing zone will have negligible effect on the occurrence or distribution of unattached organic debris along the lake bottom. Zebra

mussels typically occur on occasional woody debris or small stones that can provide a solid substrate. The construction of the diffuser header and feeder pipe will cause a modification to the lake bottom substrate as the pipeline trench is backfilled and stabilized with rip-rap or similar material that may provide a firm substrate for zebra mussel colonization. It is anticipated that areas of firm substrate exposure will be limited as transport of sand substrate will cover the habitat, hence minimizing overall zebra mussel colonization. The character of the effluent and mixing zone, though, will not promote zebra mussel growth over and above current lake conditions and habitat limitations.

327 IAC 5-2-11.4(b)(4)(B)(vi) - By allowing the additional mixing: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced.

The current Outfall 001 side channel discharge is subject to provisions in the NPDES permit whereupon: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced. The current Outfall 001 complies with this permit stipulation. The effluent character from the proposed diffuser will not change from the current Outfall 001 discharge. Therefore, it is anticipated that the discharge from the diffuser will meet the following conditions: (AA) substances will not settle to form objectionable deposits; (BB) floating debris, oil, scum, and other matter in concentrations that form nuisances will not be produced; and (CC) objectionable color, odor, taste, or turbidity will not be produced.

327 IAC 5-2-11.4(b)(4)(C) - In no case shall a mixing zone for a discharge into the open waters of Lake Michigan be granted that exceeds the area where discharge-induced mixing occurs.

As presented above, the Outfall 001 diffuser will be a discharge to the open waters of Lake Michigan. The applicable mixing zone dispersion is capped to where discharged-induced mixing ceases. Discharge-induced mixing ceases at the edge of the CORMIX2 DIMZ, which is equivalent to the edge of the Near-Field Zone where plume velocity approaches

ambient lake velocity. Therefore, the applicable mixing zone dispersion and distance are reduced to the corresponding DIMZ values (54:1 and 0.39-acre mixing zone 50 ft from all points on the diffuser header).

3.3 OVERALL SUMMARY

The background information on Lake Michigan, the recent biological studies of the proposed Amoco multipoint diffuser site, and compliance with state regulations and federal mixing zone guidelines all demonstrate that implementation of a mixing zone is appropriate for Outfall 001.


**TABLE 3-1. COMPARISON OF OUTFALL 001 CHARACTERISTICS TO FEDERAL
PRIMARY DRINKING WATER STANDARDS**

| CONSTITUENTS (a) | NPDES PERMIT APPLICATION CHARACTERIZATION DATA | | DRINKING WATER MAXIMUM CONTAMINANT LEVEL (b) |
|-------------------------|---|----------|---|
| | Maximum Daily Value | | |
| METALS | | | |
| Arsenic (Total) | µg/L | 21 | 50 |
| Barium (Total) | µg/L | 90 | 2,000 |
| Beryllium (Total) | µg/L | 2 | 4 |
| Chromium (Total) | µg/L | 30 | 100 |
| Copper (Total) | µg/L | 29 | 1,300 (c) |
| Lead (Total) | µg/L | 13 | 15 (c) |
| Nickel (Total) | µg/L | 7 | 100 |
| Selenium (Total) | µg/L | 45 | 50 |
| OTHER SUBSTANCES | | | |
| Cyanide (Total) | µg/L | 19 | 200 |
| Nitrate-N - Nitrite-N | mg/L | 0.5/<1.0 | 10 |
| Fluorides | mg/L | 0.3 | 4 |

Notes:

- (a) Constituents presented have been detected in Amoco's treated effluent. Other constituents with federal primary drinking water standards were not detected in the effluent.
- (b) EPA National Drinking Water Regulations in 40 CFR Part 141, except where noted.
- (c) Action levels from 40 CFR 141 Subpart I.





Prepared For



AMOCO OIL COMPANY
WHITING REFINERY
 Whiting, Indiana



THE ADVENT GROUP, INC.
 Rosslyn, Virginia

FIGURE 3-1.
ALTERNATE MIXING
ZONE DELINEATION

97515Task2\Fig3-1.ppt Mar 1998

Figure 3-2
Mixing Zone Shape and Location in Lake Michigan





FIGURE 3-3. CONCEPTUAL COMMUNITY SENSITIVITY



SECTION 4

SECTION 4.0

MIXING ZONE DEMONSTRATION CONCLUSION

Amoco Oil Company, Whiting Refinery has demonstrated that the implementation of a mixing zone in Lake Michigan for treated effluent, particularly through the use of a high-rate multiport diffuser, is protective of the environment. This mixing zone will not be implemented for any bioaccumulative chemicals of concern defined in 327 IAC 2-1.5-6. The information provided in this volume (Volume II Revised) demonstrates that a mixing zone application is appropriate for Outfall 001. In addition, information is provided in this volume and Volume II (submitted August 1994) for consideration by the Commissioner that the mixing zone will not cause harm based on human health, aquatic life, and wildlife criteria. This conclusion is based on the water quality criteria designated to protect the use of Lake Michigan and the assessment of the local biological community. The engineering of the diffuser and resulting dispersion support this conclusion.

The receiving water, Lake Michigan, is designated for use as: a public, industrial, and agricultural water supply; full body contact recreation; and support for a well-balanced aquatic community. The water quality criteria (numeric and whole effluent) presented in 327 IAC 2-1.5-8 are based on protecting the uses of the water. If the criteria are not exceeded in the receiving water, then the use of the water is not impaired and the designated use is maintained. As presented in Table 1-4, the quality of Lake Michigan, as measured at the Whiting intake, does not exceed the water quality criteria for the listed substances. Therefore, the Indiana portion of Lake Michigan does have assimilative capacity for these Table 1-4 substances. Available assimilative capacity is a prerequisite for granting a mixing zone.

Another consideration, before proceeding with a mixing zone demonstration, is to confirm that the effluent quality is equivalent to that established by technology-based limits. That is, a mixing zone cannot be used to attain technology-based permit limits. As presented in Table 1-1, Amoco produces treated effluent that meets the existing technology-based limits. Effluent quality based on historical wastewater treatment plant performance is better

than technology-based limits. Hence, Amoco is not using a mixing zone in place of wastewater treatment to achieve technology-based and existing permit limits. The mixing zone demonstration process for this effluent is appropriate.

The biological community most susceptible with respect to effects of a mixing zone has been identified by the USEPA as the sessile organisms (e.g., benthic community). The benthic community has been found to be poorly developed in the vicinity of the proposed diffuser site due to natural dynamic physical characteristics (e.g., fine sands and turbulence). The portions of the biological community in this area that are also susceptible to the effects of a mixing zone are the drifting water column organisms (e.g., plankton). Plankton are also good candidates for evaluation as they represent primary producers and primary consumers in this area of the lake. Based on literature review and diffuser site field studies, the abundance, diversity, composition, and function of the plankton and benthos biological are typical for a turbulent habitat. In addition, the evaluation of biological communities did not indicate an impact that could be associated with the existing Amoco discharges (presented in Volume II and Attachment 6). The deeper water and engineered structure at the proposed mixing zone will induce immediate and more rapid mixing within an area smaller than the current outfall area, thus providing an additional degree of safety to the receiving waters. As a result, the continued health of the benthic and planktonic community is expected.

Amoco has used a scientifically sound approach to identify and evaluate possible adverse consequences from chemical impacts of its Outfall 001 effluent. Acute toxicity has not been observed in Outfall 001 effluent. Amoco has proposed installation of a new multiport diffuser system where a mixing zone is defined as a ratio of 54:1 within a 50-ft distance. This proposed improvement over the current discharge structure would mean that mixing would occur within a small area (0.39 acre). The mixed effluent meets every applicable standard whether derived to protect human health (e.g., drinking water criteria and standards and Lake Michigan-specific standards) or aquatic life (e.g., water quality criteria).

Therefore, Amoco has demonstrated that a mixing zone for its Outfall 001 effluent is appropriate and meets the requirements of Indiana rules for a mixing zone, as well as the

national guidance of the USEPA. The approaches taken by Amoco, and the key findings, as detailed elsewhere in Volumes I and II, are briefly summarized below:

- Amoco is proposing to install a submerged multiport high-rate diffuser in 28-30 ft of water approximately 3,500 ft from shore to assure rapid and immediate mixing in a small area.
- According to the USEPA CORMIX2 model, a discharge-induced dispersion of 54:1 will be achieved within 50 ft of the diffuser. This CORMIX2 DIMZ dispersion can be directly utilized for calculating acute wasteload allocation values.
- The CORMIX2 model predicts a far-field mixing zone dispersion of 77:1 achieved at 500 ft from the diffuser. However, since the Amoco Outfall 001 discharge is to the open waters of Lake Michigan, the far-field dispersion is reduced to the CORMIX2 DIMZ dispersion (54:1) where discharge-induced mixing ceases (50 ft). The mixing zone dispersion of 54:1 can be directly utilized for calculating acute and chronic wasteload allocation values.
- The proposed diffuser location exhibits a natural, constant turbulence and unstable sandy substrate. This harsh physical setting limits development of the benthic community. Hence, potential aquatic community impacts from effluent may be better detected by focusing also on the plankton as opposed to only on the benthic community. Thus, Amoco's biological field assessments have appropriately focused on the structure and function of the benthos and plankton community.

Based on the findings presented in this report, a mixing zone should be applied to Amoco's NPDES Permit to derive acute and chronic effluent limitations for Outfall 001. Implementation of the mixing zone will continue to protect the designated uses of Lake Michigan. In addition, the mixing zone will not cause harm based on human health, aquatic life, and wildlife. Hence, under Indiana law, Amoco qualifies for a mixing zone.

ATTACHMENTS

1

ATTACHMENT 1

FEDERAL MIXING ZONE GUIDANCES

ATTACHMENT 1

OVERVIEW OF FEDERAL REGULATIONS AND GUIDANCE ON USE OF MIXING ZONES

Federal Regulations and Guidance

Regulatory establishment of mixing zones first occurred in the late 1960s and the early 1970s when thermal pollution from steam-electric power plants was of concern. During the 1970's, following the establishment of discharge limitations based on the Federal Water Pollution Control Act of 1972, requirements and guidelines were issued to implement mixing zones that were environmentally protective. The mixing zone concept was applied more broadly, based on time and exposure assessments, to meet effluent limitations placed on conservative constituents, such as total dissolved solids (TDS). During the 1980s, the definition and allowance of mixing zones were again expanded to include specific constituents for which USEPA had derived receiving water quality criteria. The USEPA ambient water quality criteria presented in the 1986 *Quality Criteria for Water* (or Gold Book) were the foundation for the Indiana Water Quality Criteria. These criteria are based on magnitude (maximum and continuous), duration (acute - one hour or chronic - four days), and frequency (once per three years) statements. This process of integrating time and exposure with concentration was the basic scientific framework for assuring that mixing zones are protective to aquatic life. Part of the rationale for defining the point of application of acute and chronic receiving water criteria using a mixing zone was to allow a small area (where water quality standards do not apply) to exist without causing adverse effects to the overall waterbody. The delineation of a regulatory mixing zone was based on the two areas downstream from an outfall: the Zone of Initial Dilution, outside of which no acute toxicity could occur, and total mixing zone, outside of which no chronic toxicity could occur. The purpose of this mixing zone definition was to minimize the area and time of exposure a wastewater discharge would have on the local biota.

In the 1990s, the USEPA reiterated its policy to allow mixing zones in streams, lakes, estuaries, and oceans for the application of water quality criteria. In the 1992 and 1995 federal Water Quality Standards, 40 CFR 131 Subpart D, and 40 CFR 132 Appendix F,

the applicability of mixing zones is recognized. Mixing zone concepts have been confirmed in various guidance documents such as the 1991 *Technical Support Document for Water Quality-based Toxics Control* (TSD), the 1993 (updated 1996) *Training Manual for NPDES Permit Writers* (TMPW), and the 1993 (updated 1994) *Water Quality Standards Handbook* (WQSH). These guidance documents present revised and updated mixing zone concepts that reflect USEPA's policy of integrating effluent chemical characteristics, whole effluent toxicity, and receiving water bioassessments into the process of establishing water quality-based effluent limits. In addition, revisions were made as more scientific information became available on the relationship between time and exposure of organisms to constituents and the subsequent effects on the organisms and surrounding ecosystem.

The USEPA rules and guidance for mixing zones recognize that states may adopt mixing zones and specify the dimensions. As the water quality standards program elements were clarified by the USEPA, 49 States, including all the states bordering Lake Michigan, have promulgated regulations to demonstrate whether the use of a mixing zone for defining the point of application for a receiving water criterion is appropriate in a discharge permit. The states bordering Lake Michigan allow the use of default mixing zones in the Lake of 10:1 with the demonstration of an alternative mixing zone on a case-by-case basis in accordance with Great Lakes Water Quality Guidance (per preliminarily adopted Illinois and Wisconsin regulations and final Michigan regulations).

General Mixing Zone Hydraulic Characteristics

Individual mixing zones are unique to each effluent discharge and to each environmental setting. The mixing achieved from any effluent discharge can be described from the information listed below:

- Type of effluent discharge structure and configuration;
- Effluent physical characteristics (density, flow rate); and
- Receiving water hydraulic and physical characteristics (depth, velocity, density).

Each effluent plume can be characterized by identifying specific "regions" or areas within the mixing zone, although the location and configuration will differ for each plume. The pertinent regions of a mixing zone are:

- 1) Near-Field Mixing, including:
 - a) Jet Entrainment Zone - Typically within a short distance downstream from the effluent discharge point resulting from initial momentum of the effluent into the receiving water. Dispersion is a function of the outfall characteristics.
 - b) Transition Mixing Zone - A combination of lateral and gravitational spreading and natural ambient diffusion that occurs during the transition from jet entrainment mixing to far-field mixing.
- 2) Far-Field Mixing Zone - Longitudinal, lateral and vertical mixing due to natural receiving water ambient diffusion. Mixing in this area is a function of receiving water characteristics.

Jet Entrainment Zone

The jet entrainment zone is the initial effluent mixing point in the receiving water. It represents the zone in which the maximum reduction in effluent concentration occurs. The size of the jet entrainment zone is directly related to the difference between initial effluent velocity (flow) and the receiving water velocity in the discharge area as well as the initial density difference that exists between the effluent and the receiving water. The rate of dilution is quite rapid in the first few moments after exiting the discharge point. The width of the jet entrainment zone is related to the method of discharge with the average concentration across the plume cross section being about one-half to one-third the maximum centerline concentration. In this zone, designers of an outfall can affect the initial mixing characteristics through manipulation of outfall design variables. Multiport diffusers are designed so that each diffuser port will act as an individual plume for entrainment prior to merging. As presented in the USEPA 1991 TSD, the typical design effluent exit velocity from a diffuser port is around 10 ft/sec. For this velocity, the jet entrainment zone for a diffuser extends to about one diffuser length downstream¹ and the diffuser induced

¹ Lee, J.H. and G.H. Jirka; "Multiport Diffuser as Line Source of Momentum in Shallow Water", Water Resources Research, 1980. Vol. 16, No. 4, pp. 695-708.

dispersion that can be obtained within this distance is on the order of a 50 to 100 times reduction of the effluent concentration. The reduction in effluent concentration based on the ratio of effluent concentration to receiving water concentration, as predicted or measured, will be referred to as the dispersion ratio in this report.

The federal regulatory term "ZID" is analogous to the jet entrainment zone. A typical definition for a ZID is a small area where rapid and immediate mixing occurs.

Transition Mixing Zone

The transition mixing zone has several hydraulic factors acting on the effluent/receiving water mixing regimes. First, the effluent still has momentum that causes turbulent mixing with the receiving water. The plume also undergoes lateral gravitational spreading that occurs due to the density difference that may exist between the effluent and the receiving water. Additionally, the receiving water ambient diffusion forces are working to mix receiving water and effluent together. The overall mixing process continues at a much slower rate in this zone. The transition zone, where the effluent discharge still has influence, slowly transcends into the far-field mixing zone where the receiving water completely dominates the mixing. The end of the transition zone is the end of the near field zone.

Far-Field Mixing Zone

As the turbulent effluent plume travels farther away from the source, the effluent characteristics become less important. Far-field dispersion is totally dependent upon the receiving water ambient diffusion. Eventually, the effluent will become completely mixed laterally and vertically in the receiving water by natural ambient diffusion (far-field dispersive forces). The federal regulatory term of total mixing zone (usually defined in the far-field zone) is typically associated with the chronic toxicity limit (i.e., outside this zone, no chronic toxicity may occur) and is usually geographically limited. The distinction between near-field and far-field is made purely on a hydrodynamic basis. It is unrelated to any regulatory mixing zone definitions that address prescribed water quality standards.

Mixing Zone Specifications

The USEPA guidance documents recognize the use of mixing zones and state numerous mixing zone specifications. A summary of some of the specifications, including the goal of a mixing zone evaluation step and the information to be provided to answer the objective, is presented in Table A1-1. The focus of USEPA guidance includes:

- Determination of the mixing zone boundaries and analysis procedures;
- Minimization of the size of mixing zones;
- Prevention of lethality to passing organisms;
- Prevention of bioaccumulation problems;
- Recommendation of outfall design;
- Designation of critical design periods for water bodies; and,
- Description of discharge induced mixing and far-field mixing modeling techniques.

The 1991 EPA TSD specifies that three independently established mixing zone specifications may apply, which include the following:

1. The jet entrainment zone, which is sized to prevent lethality to passing organisms. Acute criteria are met at the edge of this zone, and outside this zone no acute toxicity should occur to aquatic organisms. This zone is also known as the Zone of Initial Dilution (ZID).
2. A chronic mixing zone (or total mixing zone) is sized to protect the ecology of the waterbody as a whole. Chronic criteria are met at the edge of this zone, and outside this zone no chronic toxicity should occur to aquatic organisms.
3. A health criteria mixing zone is sized to prevent significant human risks. This typically implies that mixing zones not encroach on drinking water intakes nor result in significant health risks to average consumers who might uptake sufficient quantities of fish and shellfish that may be reasonably expected to reside in the affected zone for sufficient exposure periods. These exposure periods would result in a net bioaccumulation of constituents that could subsequently result in a human health risk.

The mixing zone size may be limited by any single specification or all three of these specifications.

The 1991 TSD provides the guidance for assessing and defining mixing zones, the application criteria to mixing zones, and recommendations for outfall design. TSD Section 4, "Exposure and Wasteload Allocation," discusses assessment of mixing zones in receiving waters. In the overview, the EPA divides the transport of treated effluent in a waterbody into two stages:

- First - mixing and dilution as determined by the initial momentum and buoyancy of the discharge. As previously presented in this report, this is called the jet entrainment zone which is analogous to the Zone of Initial Dilution.
- Second - the area in which the effect of initial momentum and buoyancy is overridden and the wastewater is mixed primarily by ambient turbulence. In this report, this is the far-field mixing zone or total mixing zone.

The EPA recommends that regulatory agencies evaluate mixing and outlines methods to evaluate dispersion and set mixing zones in Section 4 of the TSD. Several computer models are recommended for mixing zone analyses. These models were developed to divide the entire mixing region into several zones with distinct behavior (such as individual mixing processes in the near-field and in the far-field). Each model requires some schematizations of the complex and arbitrary ambient and discharge conditions that may prevail at any discharge site. These schematizations are needed to conform to the requirements of the individual models. There are two main groups of zone models commonly used to evaluate mixing: integrated zone models and jet integral models. The integrated zone model, 1992 Cornell Mixing Zone Expert System² CORMIX2, was used to evaluate the mixing between treated effluent discharged through a multiport diffuser and Lake Michigan. Modeling rationale is further discussed in Section 2 of this volume.

² Akar, P.J. and G.H. Jirka 1992. "CORMIX2: An Expert System for Hydrodynamic Mixing Zone Analysis of conventional and Toxic Submerged Multiport Diffuser Discharges", Technical Report, USEPA, ERL, Athens, GA.

The allowable size of a mixing zone is determined on a case-by-case basis, taking into account the critical resource area that needs to be protected and the assimilative capacity of the receiving water. As a mixing zone is used to define the point of application of receiving water criteria, it is necessary to first determine that the receiving water meets the criteria for its designated use. As presented in Table 1-4 (Section 1 of this volume), average Lake Michigan background concentrations are less than the concentrations allowed by the water quality criteria established to protect the use of Lake Michigan. This comparison between background concentrations and water quality standards confirms that the receiving water has available assimilative capacity, and therefore can incorporate a delineated mixing zone.

TABLE A1-1. FEDERAL AND INDIANA MIXING ZONE SPECIFICATIONS

| GOAL | OBJECTIVE | APPROACH | INFORMATION/RESPONSE |
|--|---|--|--|
| Ideally, holistic concepts to determine that a mixing zone is protective. ^{a,d} | Consider all the impacts to the water body and the impacts that the small area of decreased water quality within the mixing zone will have on the surrounding ecosystem and water body uses. ^{a,d} | Use a multistep data collection and analysis procedure. - Identify all ecological and cultural data for upstream and downstream water bodies; collect data on all present and future discharges to the water body; assess relative environmental value and level of protection needed for the water body; allocate environmental impact for a discharge applicant. ^{a,d} | Background water quality conditions. (Federal ^{a,c,d} and Indiana ^f) Present and anticipated use of receiving water. (Indiana ^f) Measured and anticipated effect of discharge on receiving water quality. (Federal ^{a,c,d} and Indiana ^f) Will not cause harm to aquatic life and human health. (Indiana ^{e,f}) |
| Waterbody integrity protected, maintained, and restored. ^{a,b,c,d,e} | Assimilative capacity available. ^{a,c,d,f} | Consider desired uses of water and criteria for use. ^{a,c,d,e} | Background water quality - physical, chemical and biological. (Federal ^{a,c,d} and Indiana ^{f,g}) Present and anticipated uses of receiving water. (Indiana ^f) Measured and anticipated effect of discharge on receiving water quality. (Federal ^{a,c,d} and Indiana ^{e,f,g}) Mixing zone should not be considered a place where effluent is treated, that is technology-based limits achieved. (Federal ^b and Indiana ^f) |

TABLE A1-1. FEDERAL AND INDIANA MIXING ZONE SPECIFICATIONS

| GOAL | OBJECTIVE | APPROACH | INFORMATION/RESPONSE |
|--|---|--|--|
| Waterbody integrity protected, maintained, and restored. ^{a,b,c,d,e} (Continued) | Protect critical areas. ^{a,d,f} | Consider location of mixing zone. ^{a,c,d,f} | <p>Location of mixing zone does not extend to drinking water intake. (Federal^{a,c,d} and Indiana^g)</p> <p>Impact on spawning and nursery areas. (Indiana^g)</p> <p>Size, shape, and location of mixing zone. (Federal^{a,c,d} and Indiana^g)</p> <p>Mixing zone boundaries. (Federal^{a,c,d} and Indiana^g)</p> <p>Mixing zone does not block passage of aquatic life. (Federal^{a,c,d} and Indiana^g)</p> <p>Mixing zone does not promote undesirable aquatic life. (Federal^a and Indiana^g)</p> <p>Substrate characteristics and geomorphology (Indiana^g); impact of mixing zone on sessile organisms. (Federal^{c,d})</p> |
| Waterbody integrity protected, maintained, and restored. ^{a,b,c,d,e} (Continued) | No lethality to passing organisms. ^{a,b,d} | Minimize size of elevated concentration isopleths within the mixing zone. ^{a,b,d} | <p>Degree of discharge induced mixing. (Federal^{a,b,c,d} and Indiana^g)</p> <p>Mixing zone shall be free of substance or combination of substances that are acutely toxic. (Indiana^{a,g})</p> |

TABLE A1-1. FEDERAL AND INDIANA MIXING ZONE SPECIFICATIONS

| GOAL | OBJECTIVE | APPROACH | INFORMATION/RESPONSE |
|--|--|---|--|
| Definable mixing zone extent and magnitude. ^{a,c,d,g} | Define application point for short-term and long-term aquatic criteria, i.e., AAC or TU _a at edge of ZID, CAC or TU _c at the edge of TMZ. ^{a,b,c,d,e,f} | Spatial definitions and achievement rapid intermediate mixing. ^{a,d,e,f} | Mixing zone location, size, shape, boundaries, and dilution ratio. (Federal ^{a,c,d} and Indiana ^g) In lakes, a circle with a specified radius is preferred. (Federal ^d) Manner (outfall design) by which diffusion/dispersion occurs. (Federal ^{a,c,d} and Indiana ^g) Maximize initial dilution. (Federal ^a and Indiana ^{f,g}) Location where discharge-induced mixing ceases in lakes. (Federal ^c and Indiana ^g) Physical, chemical, and biological characteristics of effluent. (Indiana ^{f,g}) |

Federal References:

- (a) USEPA, March 1991, *Technical Support Document for Water Quality-based Toxics Control*, USEPA/505/2-90-001. (TSD).
- (b) USEPA, December 1996, *Training Manual for NPDES Permit Writers*, USEPA 833-B-93-003. (TMPW).
- (c) USEPA, March 1995, "Final Water Quality Guidance for the Great Lakes System", 53 *Federal Register* 15366. (GLI).
- (d) USEPA, September 1993 (updated 1994), *Water Quality Standards Handbook*, Second Edition, USEPA 823-B-93-002. (WQSH).

Indiana References:

- (e) 327 IAC 2-1.5, *Water Quality Standards*.
- (f) 327 IAC 5-2, *Industrial Wastewater NPDES and Pretreatment Programs*.
- (g) 327 IAC 5-2-11.4(b).





2

ATTACHMENT 2

PRELIMINARY DIFFUSER DESIGN

(No change from Volume II, August 1994)



[illegible][illegible]

| | |
|---|---|
| | |
| * | * |
| | |
| | |
| | |
| | |

REFERENCE DRAWINGS

| | |
|---------|--|
| DWG NO. | |
|---------|--|

PRELIMINARY

| | | |
|---|-------|----------|
| PROJ NO. | 64527 | APPN NO. |
| Amoco Oil Company ENGINEERING DEPARTMENT CHICAGO, ILL. | | |
| OUTFALL PLAN, PROFILE AND DIFFUSER | | |

| | | | |
|----------------|-----------|--------|--------|
| DWG.D-7121-SK2 | | P3 | |
| DATE | 8-1-94 | SCALE | NOTED |
| DESIGN | CHMD. SCR | SHEET | 1 OF 1 |
| | | DRAWN | N.F.F. |
| | | APPRO. | SCR |
| DWG.D-7121-SK2 | | P3 | |


3

ATTACHMENT 3

WIND ROSE

(No change from Volume II, August 1994)





4

ATTACHMENT 4

CORMIX2 MODEL OUTPUT

(No change from Volume II, August 1994)



CORMIX2 PREDICTION FILE:

CORNELL MIXING ZONE EXPERT SYSTEM

Subsystem CORMIX2:

Subsystem

version:

Submerged Multiport Diffuser Discharges
CMX2_v.2.10 May_1993

CASE DESCRIPTION

Site name/label: SITE^B
Design case: 0.10mps
FILE NAME: cormix\sim\sitebv3 .cx2
Time of Fortran run: 07/22/94--12:03:32

ENVIRONMENT PARAMETERS (metric units)

Unbounded section
HA = 8.69 HD = 8.69
UA = .100 F = .047 USTAR = .7647E-02
UW = 2.000 UWSTAR = .2198E-02
Uniform density environment
STRCND= U RHOAM = 999.7019

DIFFUSER DISCHARGE PARAMETERS (metric units)

DITYPE=unidirectional_perpendicular
BETYPE=unidirectional_without_fanning
BANK = LEFT DISTB = 1083.70 YB1 = 1070.00 YB2 = 1097.40
LD = 27.40 NOPE = 10 SPAC = 3.04
DO = .152 AO = .018 HO = .50
GAMMA = 90.00 THETA = .00
SIGMA = .00 BETA = 90.00
UO = 3.136 QO = .569 = .5690E+00
RHO0 = 995.6470 DRHO0 = .4055E+01 GP0 = .3978E-01
CO = .1000E+03 CUNITS= PERCENT
IPOLL = 1 KS = .0000E+00 KD = .0000E+00

FLUX VARIABLES - PER UNIT DIFFUSER LENGTH (metric units)

q0 = .2077E-01 m0 = .6512E-01 j0 = .8260E-03 SIGNJ0 = 1.0
Associated 2-d length scales (meters)
lQ=B = .007 lm = 7.38 lm = 6.51
lmp = 99999.00 lbp = 99999.00 la = 99999.00

FLUX VARIABLES - ENTIRE DIFFUSER (metric units)

QO = .5690E+00 MO = .1784E+01 JO = .2263E-01
Associated 3-d length scales (meters)
LQ = .43 LM = 10.26 Lm = 13.36 Lb = 22.63
Lmp = 99999.00 Lbp = 99999.00

NON-DIMENSIONAL PARAMETERS

FR0 = 193.18 FRD0 = 40.32 R = 31.35
(slot) (port/nozzle)

FLOW CLASSIFICATION

2 Flow class (CORMIX2) = MU2 2
2 Applicable layer depth HS = 8.69 2

MIXING ZONE / TOXIC DILUTION / REGION OF INTEREST PARAMETERS

CO = .1000E+03 CUNITS= PERCENT
 NTOX = 0
 NSTD = 0
 REGMZ = 0
 XINT = 1000.00 XMAX = 1000.00

X-Y-Z COORDINATE SYSTEM:

ORIGIN is located at the bottom and the diffuser mid-point:
 1083.70 m from the LEFT bank/shore.

X-axis points downstream, Y-axis points to left, Z-axis points upward.

NSTEP = 20 display intervals per module

BEGIN MOD201: DIFFUSER DISCHARGE MODULE

Profile definitions:

BV = Gaussian 1/e (37%) half-width, in vertical plane normal to trajectory

BH = top-hat half-width, in horizontal plane normal to trajectory

S = hydrodynamic centerline dilution

C = centerline concentration (includes reaction effects, if any)

| X | Y | Z | S | C | BV | BH |
|-----|-----|-----|-----|----------|-----|-------|
| .00 | .00 | .50 | 1.0 | .100E+03 | .01 | 13.70 |

END OF MOD201: DIFFUSER DISCHARGE MODULE

BEGIN MOD271: ACCELERATION ZONE OF UNIDIRECTIONAL CO-FLOWING DIFFUSER

In this laterally contracting zone the diffuser plume becomes VERTICALLY FULLY

MIXED over the entire layer depth (HS = 8.69m).

Full mixing is achieved after a plume distance of about five layer depths from the diffuser.

Profile definitions:

BV = layer depth (vertically mixed)

BH = top-hat half-width, in horizontal plane normal to trajectory

S = hydrodynamic average (bulk) dilution

C = average (bulk) concentration (includes reaction effects, if any)

| X | Y | Z | S | C | BV | BH |
|------|-----|------|------|----------|------|-------|
| .00 | .00 | 8.69 | 1.0 | .100E+03 | 8.69 | 13.70 |
| .69 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 13.35 |
| 1.37 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 13.05 |
| 2.06 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 12.79 |
| 2.74 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 12.56 |
| 3.42 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 12.36 |
| 4.11 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 12.18 |
| 4.80 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 12.03 |
| 5.48 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.89 |
| 6.16 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.76 |
| 6.85 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.65 |

| | | | | | | |
|-------|-----|------|------|----------|------|-------|
| 7.53 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.55 |
| 8.22 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.47 |
| 8.91 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.39 |
| 9.59 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.33 |
| 10.28 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.29 |
| 10.96 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.25 |
| 11.65 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.22 |
| 12.33 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.21 |
| 13.02 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.20 |
| 13.70 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 11.19 |

Cumulative travel time = 87. sec

END OF MOD271: ACCELERATION ZONE OF UNIDIRECTIONAL CO-FLOWING DIFFUSER

 BEGIN MOD251: DIFFUSER PLUME IN CO-FLOW

Phase 1: Vertically mixed, Phase 2: Re-stratified

 Phase 2: The flow has RESTRATIFIED at the beginning of this zone.

This flow region is INSIGNIFICANT in spatial extent and will be by-passed.

END OF MOD251: DIFFUSER PLUME IN CO-FLOW

 ** End of NEAR-FIELD REGION (NFR) **

The initial plume WIDTH values in the next far-field module will be CORRECTED by a factor 1.58 to conserve the mass flux in the far-field! The correction factor is quite large because of the small ambient velocity

relative to the strong mixing characteristics of the discharge!

This indicates localized RECIRCULATION REGIONS and internal hydraulic JUMPS.

 BEGIN MOD241: BUOYANT AMBIENT SPREADING

Profile definitions:

BV = top-hat thickness, measured vertically

BH = top-hat half-width, measured horizontally in y-direction

ZU = upper plume boundary (Z-coordinate)

ZL = lower plume boundary (Z-coordinate)

S = hydrodynamic average (bulk) dilution

C = average (bulk) concentration (includes reaction effects, if any)

Plume Stage 1 (not bank attached):

| X | Y | Z | S | C | BV | BH | ZU | ZL |
|--------------------------|-----|------|-----------|----------|------|--------|------|------|
| 13.70 | .00 | 8.69 | 54.0 | .185E+01 | 8.69 | 17.68 | 8.69 | .00 |
| 63.02 | .00 | 8.69 | 66.3 | .151E+01 | 4.75 | 39.68 | 8.69 | 3.94 |
| 112.33 | .00 | 8.69 | 72.8 | .137E+01 | 3.66 | 56.55 | 8.69 | 5.03 |
| 161.65 | .00 | 8.69 | 77.8 | .129E+01 | 3.11 | 71.15 | 8.69 | 5.58 |
| 210.96 | .00 | 8.69 | 82.2 | .122E+01 | 2.77 | 84.34 | 8.69 | 5.92 |
| 260.27 | .00 | 8.69 | 86.4 | .116E+01 | 2.55 | 96.54 | 8.69 | 6.14 |
| 309.59 | .00 | 8.69 | 90.6 | .110E+01 | 2.39 | 107.98 | 8.69 | 6.30 |
| 358.90 | .00 | 8.69 | 94.9 | .105E+01 | 2.27 | 118.82 | 8.69 | 6.42 |
| 408.22 | .00 | 8.69 | 99.5 | .101E+01 | 2.19 | 129.17 | 8.69 | 6.50 |
| 457.54 | .00 | 8.69 | 104.3 | .959E+00 | 2.13 | 139.09 | 8.69 | 6.56 |
| 506.85 | .00 | 8.69 | 109.4 | .914E+00 | 2.09 | 148.66 | 8.69 | 6.60 |
| 556.16 | .00 | 8.69 | 115.0 | .870E+00 | 2.07 | 157.91 | 8.69 | 6.62 |
| 605.48 | .00 | 8.69 | 120.9 | .827E+00 | 2.06 | 166.88 | 8.69 | 6.63 |
| 654.79 | .00 | 8.69 | 127.2 | .786E+00 | 2.06 | 175.61 | 8.69 | 6.63 |
| 704.11 | .00 | 8.69 | 134.0 | .746E+00 | 2.07 | 184.11 | 8.69 | 6.62 |
| 753.42 | .00 | 8.69 | 141.3 | .708E+00 | 2.09 | 192.42 | 8.69 | 6.60 |
| 802.74 | .00 | 8.69 | 149.1 | .671E+00 | 2.11 | 200.53 | 8.69 | 6.58 |
| 852.05 | .00 | 8.69 | 157.3 | .636E+00 | 2.15 | 208.49 | 8.69 | 6.54 |
| 901.37 | .00 | 8.69 | 166.1 | .602E+00 | 2.19 | 216.29 | 8.69 | 6.50 |
| 950.68 | .00 | 8.69 | 175.5 | .570E+00 | 2.23 | 223.94 | 8.69 | 6.46 |
| 1000.00 | .00 | 8.69 | 185.4 | .539E+00 | 2.28 | 231.47 | 8.69 | 6.41 |
| Cumulative travel time = | | | 9950. sec | | | | | |

Simulation limit based on maximum specified distance = 1000.00 m.
This is the REGION OF INTEREST limitation.

END OF MOD241: BUOYANT AMBIENT SPREADING

CORMIX2: Submerged Multiport Diffuser Discharges End of Prediction File

5

ATTACHMENT 5

SOUTH END OF LAKE MICHIGAN BIBLIOGRAPHY

ATTACHMENT 5
SOUTH END OF LAKE MICHIGAN BIBLIOGRAPHY

- Adamkus, Valdas (1985): Restoring the Great Lakes. EPA Journal 11(Mar), 2-4. [EUTROPHICATION, GREAT LAKES, PHOSPHORUS, POLLUTION, RESTORATION, WATER COLUMN]
- The ADVENT Group, Inc. (1989): Comments on the Proposed Indiana Water Quality Standards, prepared for the Indiana Steel Industry Advisory Commission Regulatory Policy Committee. 167 Pages. [RIVER, HABITAT WATER QUALITY STANDARDS, STREAMS, MIXING ZONES]
- Allan, R.J.; Ball, A.J. (1990): An overview of toxic contaminants in water and sediments of the Great Lakes. Water Pollut. Res. J. Can. 25, 387-505. (GREAT LAKES, SEDIMENT, TOXICS, WATER COLUMN]
- American Fishing Tackle Manufacturers Association and Michigan Charter Boat Association (1990).
- Anan, J.D.; Flecker, A.S. (1993): Biodiversity Conservation in Running Waters. BioScience 43, 32-42. [ECOSYSTEM]
- Andresen, N.A., and M.L. Tuchman. 1991. Anomalous Diatom Populations in Lakes Michigan and Huron in 1983. J. Great Lakes Res. 17(1):144-149.
- Anon. (1989): Something's fishy in Lake Michigan. Journal of Environmental Health 52(Sep/Oct), 74+. [FISH, Health, LAKE MICHIGAN, POLLUTION, TOXICS]
- Anon. (1989): Will Great Lakes fish like warmer waters? Environment 31(Apr), 24. [FISH, GREAT LAKES]
- Anon. (1989): Celebrate the Great Lakes. In: State of the Great Lakes Annual Report 1988-1989. 48. [GREAT LAKES, HUMAN USE, RESTORATION]
- Anon. (1990): Siliceous Microfossil Succession in Lake Michigan. Limnology and Oceanography 35, 959-967. [LAKE MICHIGAN, SEDIMENT, TRENDS]
- Anon. (1990): Managing water quality on the Great Lakes. Public Works 121(Jan), 104+. [GREAT LAKES, MANAGEMENT, WATER QUALITY]
- Bailey, R.C., K.E. Day, R.H. Norris, and T.B. Reynoldson. 1995. Macroinvertebrate Community Structure and Sediment Bioassay Results from Nearshore Areas of North American Great Lakes. J. Great Lakes Res. 21(1):42-52.
- Balcer, Mary D.; Korda, Nancy L.; Dodson, Stanley I; (): Zooplankton of the Great Lakes -A Guide to the Identification and Ecology of the Common Crustacean Species. Pages. The University of Wisconsin Press. [GREAT LAKES, PLANKTON]
- Baldwin, N.; Saalseld, R.; Ross, M.; Buettner, H. (1979): Commercial Fish Production in the Great Lakes: 1867-1977. Great Lakes Fishery Commission Tech. Rep #3., Ann Arbor, MI. [FISH, GREAT LAKES, HUMAN USE]

- Barton, David R. (1989): Some problems affecting the assessment of Great Lakes water quality using benthic invertebrates. *Journal of Great Lakes Research* 611-622. [BENTHOS, GREAT LAKES, INDICATOR, SEDIMENT, WILDLIFE]
- Barton, David R. Distribution of some common Benthic Invertebrates in Nearshore Lake Erie, with Emphasis on Depth and Type of Substrate. 1988. *J. Great Lakes Res.* 14(1):34-43.
- Becker, George C. (1976): Environmental Status of the Lake Michigan Region. Volume 17. Inland Fishes of the Lake Michigan Drainage Basin. Argonne National Laboratory, Environmental Control Technology and Earth Sciences. Argonne, IL (ANL/ES-40 Vol.17) [FISH, LAKE MICHIGAN]
- Behmanu, Birch (1991): Aiming for Zero Discharge in the Great Lakes. *Altern. Perspec. Soc. Technol. Environ.* 18, 7-9. [GREAT LAKES, HABITAT, LOADINGS, PROGRAM, TOXICS, WATER COLUMN, WILDLIFE]
- Bertram, P.E.; Reynoldson, Th. (1991): Developing Ecosystem Objectives for the Great Lakes: Policy, Progress and Public Participation. *Hydrobiologia*. [ECOSYSTEM, GREAT LAKES]
- Bertram, P.E.; Reynoldson, Th. (1992): Developing Ecosystem Objectives for the Great Lakes: Policy, Progress and Public Participation. *Journal of Aquatic Ecosystem Health* 1, 89-95. [ECOSYSTEM, GREAT LAKES]
- Bertram, Paul E. (1993): Total Phosphorus and Dissolved Oxygen Trends in the Central Basin of Lake Erie, 1970-1991. *Journal of Great Lakes Research* 19, 224-236. [EUTROPHICATION, LAKE ERIE, WATER COLUMN]
- Bimber, D.L.; Perrone, M. Jr; Noguchi, L.S.; Jude D.J.: Field Distribution and Entrainment of Fish Larvae and Eggs at the Donald C. Cook Nuclear Power Plant, Southeastern Lake Michigan, 1973-1979. Special Report No. 105 of the Great Lakes Research Division. University of Michigan. [FISH, LAKE MICHIGAN]
- Black, John (1990): Impact of Toxic Chemicals on Great Lakes Biota. In: Great Lakes Monograph No.3. Contemporary and Emerging Issues in the Great Lakes. Proceedings from a Colloquium Between The University at Buffalo and the University of Toronto April 12, 1989. (Eds: Bankeri, Lyune S; Flint, R. Warren) Great Lakes Program. State University of New York, New York, Buffalo, New York, 37-39. [AVIAN SPECIES, FISH, GREAT LAKES, TOXICS, WILDLIFE]
- Booth, J.S. 1994. Wave Climate and Nearshore Lakebed Response, Illinois Beach State Park, Lake Michigan. *J. Great Lakes Res.* 20(1): 163-178.
- Born, Stephen M.; Sonzogno, William C. (1992): Integrated Environmental Management: Strengthening the Conceptualization. in press. [MANAGEMENT]
- Botts, L (1985): Thinking Ecologically in Lakes Protection. *EPA Journal* 11, 13-14. [GREAT LAKES, POLLUTION, WASTE DISPOSAL, WATER COLUMN]
- Botts, L.; Krushelnicki, B. (1987): Great Lakes: An Environmental Atlas and Resource Book. Environmental Protection Agency, Chicago, IL Great lakes National Program Office. 50 pages. (EPA/90 519-871002, ISBN-0462-15 189-5) [ECOSYSTEM, EUTROPHIC, FISH, GREAT

LAKES, GROUNDWATER, LAND USE, MANAGEMENT, POLLUTION, TOXICS, WATER COLUMN]

- Botts, Paul (1991): A ton of prevention. New approach could hold key to Great Lakes' future. The Great Lakes Reporter 8 (March/April), 14. [GREAT LAKES, POLLUTION, PROGRAM]
- Bowden, R.J., et. al.: Lake Michigan Intensive Survey, 1976-1977. Management Report. U.S. EPA: August 1981. 56 pp.
- Bowden, R.J., et al. (1981). Michigan Intensive Survey 1976-77. Management Report. US EPA, August, 56 pp.
- Boyce, F. (1974): Some Aspects of Great Lakes Physics of Importance to Biological and Chemical Processes. Journal of the Fisheries Research Board of Canada 31, 689-730. [ECOSYSTEM, GREAT LAKES]
- Braden, John B.; Larson, Robert S.; Herricks, Edwin W. (1991): Impact Targets Versus Discharge Standards in Agricultural Pollution Management, American Journal of Agricultural Economics 73 (May), 388-397. [EUTROPHIC, GREAT LAKES, MANAGEMENT, NUTRIENTS, POLLUTION, WATER COLUMN]
- Branstrator, Donn K.; Lehman, John T. (1991): Invertebrate predation in Lake Michigan: Regulation of *Bosmina longirostris* by *Leptodora kindtii*. Limnology and Oceanography 36, 483-495. [LAKE MICHIGAN, POPULATION, WILDLIFE]
- Brazo, Dr. Dan C. (): Biological Parameters of Chinook Salmon in Southern Lake Michigan, 1991. Indiana Department of Natural Resources, Division of Fish and Wildlife. Pages.
- Burt, M.; McKee, P.M.; Hart, D.R., Kauss, P.B. (1991): Effects of pollution on benthic invertebrate communities of the St Marys River, 1985. In: Environmental Assessment and Habitat Evaluation of the Upper Great Lakes Connecting Channels. Eds: Munawar, M; Edsall, T), 6341. [BENTHOS, HABITAT, POLLUTION, ST MARYS RIVER, TOXICS] 1991.
- Camanzo, Joseph; Rice, Clifford P.; Jude, David J.; Rossman, Ronald (1987): Organic priority pollutants in nearshore fish from 14 Lake Michigan tributaries and embayments, 1983. Journal of Great Lakes Research 13, 296-309. [DDT, FISH, LAKE MICHIGAN, PCB, PESTICIDE, POLLUTION, TOXICS]
- Canada-Ontario (1990): Second Report of Canada Under the 1987 Protocol to the 1978 Great Lakes Water Quality Agreement Issues Overview and Technical Summary., Toronto Ontario. 82 (overview) 180 (summary) pages. [GREAT LAKES, WATER COLUMN]
- Carrick, H.J., and G.L. Fahnenstiel. 1990. Planktonic Protozoa in Lakes Huron and Michigan: Seasonal Abundance and Composition of Ciliates and Dinoflagellates. J. Great Lakes Res. 16(2):319-329.
- Chang, W.Y.B. and R. Rossmann. 1988. Changes in the abundance of blue-green algae related to nutrient loadings in the nearshore of Lake Michigan. Hydrobiologia 157:271-278.

Christensen, E.R., Goetz, R.H. (1987: Historical fluxes of particle-bound pollutants from deconvolved sedimentary records. *Environmental Science and Technology* 21, 1088-1090. [LAKE MICHIGAN, LEAD, POLLUTION, SEDIMENT, TOXICS, TRENDS]

Christensen, Erik R., Kien, Richard J. (1991): "Unmixing" of Cs, Pb, Zn, and Cd Records in Lake Sediments. *Environmental Science and Technology* 25, 1627-1637. [ATMOSPHERE, LAKE MICHIGAN, LEAD, SEDIMENT, TOXICS]

Chrastowski, M.J., T.A. Thompson, and C.B. Trask. 1994. Coastal Geomorphology and Littoral Cell Divisions along the Illinois-Indiana Coast of Lake Michigan. *J. Great Lakes Res.* 20(1):27-43.

The City of Chicago; Department of Water; Bureau of Water Operations; Division of Water Purification; Water Quality Surveillance Section; Illinois Environmental Protection Agency; Bureau of Water, Division of Water Pollution Control, Planning Section; Northern Monitoring and Assessment Unit (1993): Lake Michigan Water Quality Report January through December 1989-1991.

Colborn, Theodora E. (1990): Defining and Measuring Ecosystem Health. In: *Great Lakes: Great Legacy?* Conservation Foundation for Research on Public Policy, Canada, 15-30. [ECOSYSTEM, GREAT LAKES, HEALTH, HUMAN HEALTH, WILDLIFE]

Colborn, Theodora E. (1990): Fish, Wildlife, and Habitat In: *Great Lakes: Great Legacy?* Conservation Foundation/Inst for Research on Public Policy, Canada, 131-163. [ECOSYSTEM, FISH, GREAT LAKES, HABITAT, POLLUTION, POPULATION, WILDLIFE]

Colborn, Theodora E. (1990): Legacies and Challenges: Air and Climate. In: *Great Lakes: Great Legacy?* Conservation Foundation/Inst for Research on Public Policy, Canada, 113-130. [ATMOSPHERE, ECOSYSTEM, GREAT LAKES, POLLUTION]

Colborn, Theodora E. (1990): Legacies and Challenges: Water. In: *Great Lakes: Great Legacy?* Conservation Foundation/Inst for Research on Public Policy, Canada, 75-112. [ECOSYSTEM, GREAT LAKES, GROUNDWATER, WATER COLUMN]

Colborn, Theodore E. (1990): Legacies and Challenges: Land. In: *Great Lakes: Great Legacy?* Conservation Foundation/Inst for Research on Public Policy, Canada, 314-342. [ECOSYSTEM, GREAT LAKES, LAND USE, POLLUTION, WASTE DISPOSAL]

Colborn, T.E.; Davidson, A.; Greeve, S.N.; Hodge, R.A.; Jackson, C.I.; Liroff R.A. (1990): *Great Lakes, Great Legacy?* The Conservation Foundation, Institute for Research on Public Policy, Washington, DC and Ottawa, Ontario. 174 pages. [GREAT LAKES]

Contaminant Warnings, Troubled Fishery Hobble Michigan Charter Business. News Release of January 10, 1990., Barington, L. [FISH, GREAT LAKES, HUMAN USE, RECREATION, TOXICS]

Council of Great Lakes Research Managers (1990(?)): *Great Lakes 2000: Building a Vision.* Summary Report of the Workshop of the Council of Great Lakes Research Managers on Futures. 22 pages. [ECOSYSTEM, GREAT LAKES; INDICATOR, MANAGEMENT]

- Council of Great Lakes Research Managers (1991): A Proposed Framework for Developing Indicators of Ecosystem Health for the Great Lakes Region. Report to the International Joint Commission., Windsor, Ontario. 50 pages. [ECOSYSTEM, GREAT LAKES, HEALTH, INDICATOR]
- Davenport, R., and A. Species. 1991. Acute Phototoxicity of Harbor and Tributary Sediments from Lower Lake Michigan. J. Great Lakes Res. 17(1):51-56.
- Dawson, C.; Lichtkoppler, F.; Pistis, C. (1989): The Charter Fishing Industry in the Great Lakes. North American Journal of Fisheries Management 9, 493-499. [FISH, GREAT LAKES, HUMAN USE]
- Dawson, C.; Brown, T. (1990): The Demand for Great Lakes Sportfishing: Some Future Marketing Implications. In: Proceedings of the National Outdoor Recreation Trends Symposium m. Vol. II. (Eds: O'Leary, J.; Fesenmaier, D.; Brown, T.; Stynes, D.; Driver, B.) Department of Recreation and Park Administration, Indiana University, Bloomington, IN, 528-536. [FISH, GREAT LAKES, HUMAN USES]
- Dawson, C.; Voiland, M. (1990): The Great Lakes Charter Fishing Industry in the 1990's. In: 1990 National Outdoor Recreation Trends Symposium m., Indianapolis, IN, March 29-31, 1990. New York Sea Grant Program, Oswego, NY, 19. [FISH, HUMAN USE]
- Day, K.E., B.J. Dutka, K.K. Kwan, N. Batista, T.B. Reynoldson, and J.L. Metcalf-Smith. 1995. Correlations Between Solid-Phase Microbial Screening Assays, Whole-Sediment Toxicity Test with Macroinvertebrates and *In Situ* Benthic Community Structure. J. Great Lakes Res. 21(2): 192-206.
- Department of the Army, U.S. Army Corps of Engineers, Chicago District (1974): Wastewater Management Study for Chicago - South End of Lake Michigan Area. Summary Report. 155 Pages. [LAKE MICHIGAN, WATER QUALITY]
- DePinto, Joseph V.; Young, Thomas C.; McIlroy, Lyn M. (1986): Great Lakes Water Quality Improvement Environmental Science and Technology 20(Aug), 752-759. [EUTROPHICATION, GREAT LAKES, PHOSPHATE, WATER COLUMN]
- Dickie, Lloyd M.; Bandurski, Bruce L. (1990): Integrity and Surprise in the Great Lakes Basin Ecosystem: Implications for Theory and Testing. In: An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times (Great Lakes Fishery Comm 90-4). Int Joint Commission, Washington, DC, 105-119. [ECOSYSTEM, GREAT LAKES, HEALTH, INDICATOR]
- Dixon, D.G., Hodson, P.V., Klaveramp, J. (1985). The Role of Biochemical Indicators in the Assessment of Ecosystem Health - Their Development and Validation. National Research Council of Canada: Report No. 24371. 119 pp. [ECOSYSTEM HEALTH, INDICATOR]
- Dobson, H.F.H. (1981): Trophic Conditions and Trends in the Laurentian Great Lakes: UNIWHO. Water Quality Bulletin 6, 146-160. [EUTROPHICATION, TRENDS, WATER COLUMN]
- Dochoda, Margaret A. (1989): Preventing Ballast Water Introductions in the Great Lakes. Focus 14, 15-17. [EXOTIC SPECIES, GREAT LAKES]

Dochoda; Margaret Ross (1991): Meeting the Challenge of Exotics in the Great Lakes: the Role of an International Commission Canadian Journal of Fisheries and Aquatic Sciences 48, 171-176. [EXOTIC SPECIES, GREAT LAKES, MANAGEMENT]

Door, John, A.; Jude, David J. (19__): SCUBA Assessment of Abundance, Spawning, and Behavior of Fishes in Southeastern Lake Michigan Near the Donald C. Cook Nuclear Plant, 1975-1978.

Eadie, B.J., Robbins, J.A.: (198~. The Role of Particulate Matter in the Movement of Contaminants in the Great Lakes. In, Sources and Fates of Aquatic Pollutants, from Advances in Chemistry Series No. 216, Editors: Hites, R.A., Eisenreich. [GREAT LAKES, TOXICS, WATER COLUMN]

Eck, G.; Wells, L. (1987): Recent Changes in Lake Michigan's Fish Community and Their Probable Causes, With Emphasis on the Role of Alewife (*MoM pseudoharengus*). Canadian Journal of Fisheries and Aquatic Sciences 44 (Supplement 2), 53-60. [FISH, LAKE MICHIGAN]

Ecosystem Objectives Committee (1990): Final Report of the Ecosystem Objectives Committee to the Great Lakes Science Advisory Board. International Joint Commission, Windsor, ON., 1-53. [AVIAN SPECIES, ECOSYSTEM, FISH, GREAT LAKES, HEALTH, INDICATOR, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, LAKE SUPERIOR, NEAR SHORE, POPULATION, TOXICS, WATER COLUMN, WILDLIFE]

Edsall, T.A., G.W. Kennedy, and W.H. Horns. 1966. Potential Spawning Habitat for Lake Trout on Julian's Reef, Lake Michigan. J. Great Lakes Res. 22(1):83-88.

Edsall, T.A., C.L. Brown, G.W. Kennedy, and T.P. Poe. 1992. Lake Trout Spawning Habitat in the Six Fathom Bank-Yankee Reef Lake Trout Sanctuary, Lake Huron. J. Great Lakes Res. 19(1):70-90.

Edwards, C.J.; Ryder, R.A. (1990): Biological Surrogates of Mesotrophic Ecosystem Health in the Laurentian Great Lakes. Report to the Great Lakes Science Advisory Board., Windsor, Ontario. 78 pages. [BENTHOS, ECOSYSTEM, EUTROPHICATION, EXOTIC SPECIES, FISH, GREAT LAKES, HABITAT, HEALTH, INDICATOR, NUTRIENTS, POLLUTION, TOXICS, WATER COLUMN, WILDLIFE]

Edwards, C.J.; Regier, H.A. (1990): An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times. Great Lakes Fishery Commission Special Publication 90-4, Ann Arbor, MI. [ECOSYSTEM, GREAT LAKES]

Edwards, Clayton J.; Ryder, Richard A.; Marshall, Terry R. (1990): Using lake trout as a surrogate of ecosystem health for oligotrophic waters of the Great Lakes. Journal of Great Lakes Research 16, 591-608. [ECOSYSTEM, FISH, GREAT LAKES, HEALTH, INDICATOR]

El-Shaarawi, A.H.; Esterby, S.R., Kunt, K.W. (1983): A Statistical Evaluation of Trends in Water Quality of the Niagara River Journal of Great Lakes Research 9(2), 234-240. [TRENDS, WATER COLUMN]

Emery, L. 1985): Review of Fish Species Introduced into the Great Lakes. 1819-1974. Great Lakes Fishery Commission Technical Report No. 45. Great Lakes Fishery Commission, Ann Arbor, MI. [EXOTIC SPECIES, FISH]

- Endicott, Richardson, and Kandt (1992). Michtox, A Mass Balance and Bioaccumulation Model for Toxic Chemicals in Lake Michigan. Environmental Research Lab, Office of Research and Development,. U.S. EPA, Duluth, MN. [LAKE MICHIGAN, TOXICS]
- Eshenroder, Randy L. et al. (1991): Lake Michigan: an Ecosystem Approach for Remediation of Critical Pollutants and Management of Fish Communities. In: Great Lakes Fishery Commission Special Publication 91-2. 64. [ECOSYSTEM, FISH, LAKE MICHIGAN, MANAGEMENT, RESTORATION, TOXICS]
- Evans, D.O.; Henderson, B.A.; Bax, N.J.; Marshall, T.R.; Oglesby, R.T.; Christie, W.J. (1987): Concepts and Methods of Community Ecology Applied to Freshwater Fisheries Management. Canadian Journal of Fisheries and Aquatic Sciences 44: (Supplement 2), 448-470. [FISH]
- Evans, David O.; Warren, Glenn J.; Cairns, Victor W. (1990): Assessment and management of fish community health in the Great Lakes synthesis and recommendations. Journal of Great Lakes Research 16, 639-669. [ECOSYSTEM, FISH, GREAT LAKES, HEALTH, TOXICS]
- Evans, Marlene S.; Sell, Daniel W.; and Page, Donna I. (1982): Special Report Number 89, Great Lakes Research Division, The University of Michigan: Zooplankton Studies in 1977 and 1978 at the Donald C. Cook Nuclear Power Plant: Comparisons of Preoperational (1971-1974) and Operational (1975-1978) Population Characteristics.
- Evans, Marlene S.; Jude, David J. (1986): Recent Shifts in *Daphnia* Community Structure in Southeastern Lake Michigan: A comparison of the Inshore and Offshore Regions. Limnology and Oceanography 31(1), 56-67. [FISH, LAKE MICHIGAN]
- Evans, M.S.; Warren, G.J., Page, D.I.; Flath, L.F.: Zooplankton Studies at the Donald C. Cook Nuclear Power Plant: 1979-1982 Investigations, Including Preoperational (1971-1974) and Operational (1957-1982) Comparisons. Special Report No. 111 of the Great Lakes Research Division. University of Michigan. [PLANKTON, GREAT LAKES]
- Evans, M.S.; Sell, D.W., Page, D.I.: Zooplankton Studies in 1977 and 1978 at the Donald C. Cook Nuclear Power Plant: Comparisons of Preoperational (1971-1974) and Operational (1975-1978) Population Characteristics. Special Report No. 89 of the Great Lakes Research Division. University of Michigan. [PLANKTON, GREAT LAKES]
- Evans, M.S.; McNaught, D.C. (1988): The effects of toxic substances on zooplankton populations: A Great Lakes perspective. In: Toxic Contaminants and Ecosystem Health: A Great Lakes Focus. (Ed: Evans, M.S.) John Wiley and Sons, New York, NY, 5346. (CONTRIB-472, EPA/600/d- 891241 Grant EPA-R-812468) [GREAT LAKES, PLANKTON, POPULATION, TOXICS]
- Evans, M.S. (1985): The morphology of *Daphnia pulicaria*, a species newly dominating the offshore southeastern Lake Michigan summer *Daphnia* community. Trans. Amer. Micor. Soc. 104(3): 223-231.
- Evans, M.S. (1986): Lake Huron rotifer and crustacean zooplankton, April-July, 1980. J. Great Lakes Research. 6(4): 275-289.

- Evans, M.S., B.E. Hawkins and D.W. Sell (1980): Seasonal fluctuation of zooplankton assemblages in the nearshore area of southeastern Lake Michigan. *J. Great Lakes Research*. 6(4): 275-289.
- Evans, M.S. (1983): Crustacean and rotifer zooplankton of Lake Huron. 1980. Factors affecting community structure with an evaluation of water quality status. University of Michigan. Great Lakes Research Division, Special Report 97.
- Fahnenstiel, Gary L.; Carrick, Hunter J. (1991): Physiological Characteristics and Food-web dynamics of *Synechococcus* in Lakes Huron and Michigan. *Limnology and Oceanography* 36, 219-234. [LAKE HURON, LAKE MICHIGAN, WILDLIFE]
- Fahnenstiel, Gary L., and D. Scavia. 1987. Dynamics of Lake Michigan Phytoplankton: The Deep Chlorophyll Layer. *J. Great Lakes Res.* 13(3):285-295.
- Fairchild, D.J., and J.H. McCormick. 1996. Effects of Temperature on Hatching and Development of Ruffe (*Gymnocephalus cernuus*). *J. Great Lakes Res.*
- Fenner, Kenneth A.; Davenport, Thomas E. (1988): Lake Michigan Toxic Pollution Control/Reduction Strategy. In: AWRA The Great Lakes: Living with North America's Inland Waters Sym. Milwaukee, WI Nov 6-11. 221-226. [BENEFICIAL USES, GREAT LAKES, HUMAN HEALTH, LAKE MICHIGAN, MANAGEMENT, POLLUTION, RESTORATION, TOXICS, WATER COLUMN]
- Federal Water Pollution Control Administration, Washington, D.C. (1966): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Proceedings of Conference (Technical Session), January 4-5, 1966. Volume 1. (PB-230 534)
- Federal Water Pollution Control Administration, Washington, D.C. (February 2, 1966): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Conclusions of Technical Session. Held at Chicago, Illinois on February 2, 1966. (PB-230 729)
- Federal Water Pollution Control Administration, Washington, D.C. (September 21, 1967): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Proceedings of Conference, Second Session, held at Chicago, Illinois on September 11, 1967. Volume 1. (PB-230 728)
- Federal Water Pollution Control Administration, Washington, D.C. (1967): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Progress Evaluation Meeting held at Chicago, Illinois on March 15, 1967. Volume 1. (PB-230 540)
- Federal Water Pollution Control Administration, Washington, D.C. (1967): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Progress Evaluation Meeting held at Chicago, Illinois on March 15, 1967. Volume III. (PB-230 542)
- Federal Water Pollution Control Administration, Washington, D.C. (March 1968): Pollution Of Lake Michigan And Its Tributary Basin. Proceedings of Conference held at Chicago, Illinois on

January 31, February 1-2, February 5-7, 1968. Executive Session, March 7, 8 and 12, 1968. Volume II. (PB-230 478)

Federal Water Pollution Control Administration, Washington, D.C. (December 12, 1968): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries, Illinois-Indiana. Proceedings of Conference, Session (2nd) held at Chicago, Illinois, on December 11-12, 1968. Volume 1. (PB-230 555)

Federal Water Pollution Control Administration, Washington, D.C. (February 2, 1968): Pollution Of Lake Michigan And Its Tributary Basin. Proceedings of Conference held at Chicago, Illinois on January 31, February 1-2, February 5-7, 1968. Executive Session, March 7, 8 and 12, 1968. Volume III. (PB-230 479)

Federal Water Pollution Control Administration, Washington, D.C. (March 1968): Pollution Of Lake Michigan And Its Tributary Basin. Proceedings of Conference held at Chicago, Illinois, on January 31, February 1-2, February 5-8, 1968. Executive Session, March 7, 8 and 12, 1968. Volume I. (PB-230 477)

Fitchko, J. (1985): Health of Aquatic Communities Task Force. Literature Review of the Effects of Persistent Toxic Substances on Great Lakes Biota. Report to the Great Lakes Science Advisory Board., Windsor, Ontario. 356 pages. [BIOTA, ECOSYSTEM, FISH, GREAT LAKES, HUMAN HEALTH, LEAD, PESTICIDE, POLLUTION, TOXICS, WASTE DISPOSAL, WATER COLUMN]

Fitchko, J. (1986): Health of Aquatic Communities Task Force. Literature Review of the Effects of Persistent Toxic Substances on Great Lakes Biota. Report to the Great Lakes Science Advisory board., Windsor, Ontario. 256 pages. [BIOTA, ECOSYSTEM, FISH, GREAT LAKES, HUMAN HEALTH, LEAD, PESTICIDE, POLLUTION, TOXICS, WASTE DISPOSAL, WATER COLUMN]

Flint, R.W. (1987): Use of Biological Controls for Managing Great Lakes Disturbances. Journal of Great Lakes Research 13, 93-95. [GREAT LAKES, MANAGEMENT]

Fontaine III, Thomas D.; Lesht, Barry M. (1987): Contaminant management strategies for the Great Lakes: optimal solutions under uncertain conditions. Journal of Great Lakes 'Lurch 13, 178-192. [EUTROPHICATION, GREAT LAKES, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, LAKE ONTARIO, LAKE SUPERIOR, MANAGEMENT, PHOSPHORUS, WATER COLUMN]

Fontaine III, Thomas D.; Stewart, D. J. (1990): An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times. (Series Eds: Edgds, CJ; Regier, HA.) Great Lakes fishery Commission Seal Publication 90-4, Ann Arbor, MI. 153-168 pages. [ECOSYSTEM, GREAT LAKES]

Fontaine III, Thomas D.; Stewart, Donald J. (1990): Trophic Dynamics and ecosystem integrity in the Great Lakes: past, present, and possibilities. In: An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times. Proceedings of a 1988 Workshop Supported by the Great Lakes Fishery Commission and the Science Advisory Board of the International Joint Commission Great Lakes Fishery Commission Seal Publication 90-4. (Eds: Edwards, CJ; Regier, Henry A.) Great Lakes Fishery Commission, Ann Arbor, MI, 153-167. [ECOSYSTEM, FISH, GREAT LAKES, LAKE MICHIGAN, TRENDS, WATER COLUMN]

Foster, D.S., and D.W. Folger. 1994. The Geologic Framework of Southern Lake Michigan. *J. Great Lakes Res.* 20(1):44-60.

Fox, Glenn A. (1993): What Have Biomarkers Told Us About the Effects of Contaminants on the Health of Fish-Eating Birds in the Great Lakes? The Theory and a Literature Review. *J. Great Lakes Res.* 19(4), Pages 722-736. [TOXICS, GREAT LAKES]

Fox, R. and M. Tuchman (Eds.). 1996. The Assessment and Remediation of Contaminated Sediments (ARCS) Program. *J. Great Lakes Res.* 33(3):1-669.

France, Robert L. (1990): Theoretical framework for developing and operationalizing an index of zoobenthos community integrity application to biomonitoring with zoobenthos communities in the Great Lakes. In: *An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times. Proceedings of a 1988 Workshop Supported by the Great Lakes Fishery Commission and the Science Advisory Board of the International Joint Commission. Great Lakes Fishery Commission Special Publication 90-4.* (Eds: Edwards, C.J.; Regier, Henry, A.) Great Lakes Fishery Commission, Ann Arbor, MI, 169-193. [BENTHOS, GREAT LAKES, INDICATOR, PROGRAM, WILDLIFE]

Gannon, J.E., (1971) Two counting cells for the enumeration of zooplankton micro-crustacea. *Trans. Am. Microsc. Soc.* 90: 486-490.

Gannon, J.E., (1975) Horizontal distribution of crustacean zooplankton along a cross-lake transect in Lake Michigan. *J. Great Lakes Research.* 1(1): 79-91.

Gannon, J.E., (1981) Changes in zooplankton populations of Lakes Erie and Ontario. In R.K. Cap and V.R. Frederick, *Proc. of Conference on Changes in the Biota of Lakes Erie and Ontario.* Bull. Buffalo Soc. Nat. Soc. 25(4): 21-39.

Gannon, J.E., R.S. Stemberger. (1978) Zooplankton (especially crustaceans and rotifers) as indicators of water quality. *Trans. Amer. Microsc. Soc.* 97 (1): 16-35.

Gannon, J.E., Bricker, F.J., and Bricker, K.S. (1982) Zooplankton Community Composition in Nearshore Waters of Southern Lake Michigan. EPA-905/3-82/001. 132 pp.

Gannon, J.E., Bricker, K.S., and Bricker, F.J. (1982b) Zooplankton Community Composition in Green Bay, Lake Michigan. EPA-905/3-82/002.

Gilbertson, Michael et al. (1990): Commentary: New Strategies for Great Lakes Toxicology. *Journal of Great Lakes Research* 16, 625-627. [FISH, GREAT LAKES, TOXICS, WILDLIFE]

Goudy, Greg (1986): Water Quality and Pollution Control in Michigan: Surface Water Quality Division, Environmental Protection Bureau, Michigan Department of Natural Resources. [Water Quality, Toxics, Pollution, Chlorides]

Government of Canada, Government of the Province of Ontario (1990): Second Report of Canada Under the 1987 Protocol to the 1978 Great Lakes Water Quality Agreement. Technical Summary. 180 pages. [ATMOSPHERE, AVIAN SPECIES, ECOSYSTEM, EUTROPHICATION, EXOTIC SPECIES, FISH, GREAT LAKES, GROUNDWATER, HEALTH, HUMAN HEALTH, LAKE ERIE, LAKE ONTARIO, LAKE SUPERIOR, LEAD, LOADINGS, MANAGEMENT, MERCURY, NITRATE, PCB, PESTICIDE, PHOSPHORUS, POLLUTION, PROGRAM,

RESTORATION, SEDIMENT, TOXICS, TRENDS, WASTE DISPOSAL, WATER COLUMN, WETLAND, WILDLIFE]

Great Lakes Science Advisory Board (1987): 1987 Report to the International Joint Commission. 78 pages. [ATMOSPHERE, ECOSYSTEM, GREAT LAKES, GROUNDWATER, MANAGEMENT, SEDIMENT, TOXICS]

Great Lakes Science Advisory Board (1991): 1991 Report to the International Joint Commission. 126 pages. [ATMOSPHERE, AVIAN SPECIES, DEFORMITIES, ECOSYSTEM, FISH, GREAT LAKES, GROUNDWATER, HABITAT, HUMAN HEALTH, INDICATOR, LOADINGS, MAMMALIAN SPECIES, MANAGEMENT, TOXICS, TUMOR, WETLAND, WILDLIFE]

Great Lakes Science Advisory Board (1993). Report to the International Joint Commission. Windsor, Ontario. 62 pp. [ECOSYSTEM, GREAT LAKES, HUMAN HEALTH, TOXICS, WATER COLUMN]

Great Lakes Water Quality Board (1977): Great Lakes Water Quality Fifth Annual Report, Appendix B, Annual Report of the Surveillance Subcommittee to the Implementation Committee Great Lakes Water Quality Board, June 1977. [WHOLE LAKE PROBLEMS, LOCAL AREA PROBLEMS]

Great Lakes Water Quality Board (1982): Appendix E: Great Lakes Water Quality Status Report on the Persistent Toxic Pollutants in the Lake Ontario Basin, Presented to the Great Lakes Water Quality Board by the Implementation Committee. Appendix E: Status Report on Organic and Heavy Metal Contaminants in the Lakes Erie, Michigan, Huron and Superior Basins. Reprinted in one volume., Windsor, Ontario. 468 pages. ((Lake Ontario volume originally printed 1976; Lakes Erie, Michigan, Huron and Superior volume originally printed 1978.)) [LAKE ERIE, LAKE HURON, LAKE MICHIGAN, LAKE ONTARIO, LAKE SUPERIOR, WATER COLUMN]

Great Lakes Water Quality Board (1987): Report on Great Lakes Water Quality., Windsor, Ontario. 236 pages. [ATMOSPHERE, AVIAN SPECIES, BENTHOS, DDT, DEFORMITIES, DIOXIN, ECOSYSTEM, EUTROPHICATION, FISH, GREAT LAKES, HABITAT, HEALTH, HUMAN HEALTH, INDICATOR, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, LAKE ONTARIO, LAKE SUPERIOR, LEAD, LOADINGS, MAMMALIAN SPECIES, MANAGEMENT, MERCURY, ORGANOCHLORINE, PCB, PESTICIDE, PHOSPHORUS, POLLUTION, PROGRAM; RESTORATION, SEDIMENT, TOXICS, TUMORS, WASTE DISPOSAL, WATER COLUMN]

Great Lakes Water Quality Board (): 1987 Report on Great Lakes Water Quality: Appendix B, Great Lakes Surveillance: Volume III. Report to the International Joint Commission. [GREAT LAKES, WATER QUALITY]

Great Lakes Water Quality Board (1989): 1987 Report on Great Lakes Water Quality: Appendix B, Great Lakes Surveillance: Volume I. Report to the International Joint Commission. [GREAT LAKES, WATER QUALITY]

Great Lakes Water Quality Board (1989): 1989 Report on Great Lakes Water Quality., Windsor, Ontario. 128 pages. [AVIAN SPECIES, EUTROPHICATION, EXOTIC SPECIES, FISH, GREAT LAKES, HABITAT, HUMAN USE, SEDIMENT, TOXICS, WATER COLUMN]

Great Lakes Water Quality Board (1991): Cleaning Up Our Great Lakes, A Report on Toxic Substances in the Great Lakes Basin Ecosystem. 1991 Report on Great Lakes Water Quality to the International Joint Commission, Windsor, Ontario. 47 pages. [ECOSYSTEM, GREAT LAKES, RESTORATION, TOXICS]

Green, Roger H.; Bailey, Robert C.; Hinch, Scott G.; Metcalfe, Janice L.; Young, Vicki H. (1989): Use of freshwater mussels (bivalvia: unionidae) to monitor the nearshore environment of lakes. Journal of Great Lakes Research 15,635-644. [BENTHOS, GREAT LAKES, INDICATOR, NEAR SHORE, SEDIMENT, WILDLIFE]

Groark, Corinne M. (1992): The Great Lakes: Saving a Fresh Source. Environ. Prot. 3, 12-18. [EUTROPHICATION, GREAT LAKES, NUTRIENTS, POLLUTION, RESTORATION, TRENDS, WATER COLUMN]

Hair, Jay D. (1989): Don't blame the messenger. National Wildlife 27(Oct/Nov), 30. [FISH, LAKE MICHIGAN, POLLUTION, TOXICS]

Harris, H.J.; Sager, P.E.; Richman, S.; Harris, V.A.; Yarbrough, C.J. (1987): Coupling ecosystem science with management: A Great Lakes perspective from Green Bay, Lake Michigan, US & Environmental Management 11, 619-625. [ECOSYSTEM, GREAT LAKES, GREEN BAY, LAKE MICHIGAN, MANAGEMENT]

Harris, Hallett J.; Sager, P.E.; Regier, H.A.; Francis, G.R. (1990): Ecotoxicology and Ecosystem Integrity: the Great Lakes Examined. Environmental Science and Technology 24, 598-603. [ECOSYSTEM, GREAT LAKES, POLLUTION, TOXICS, WATER COLUMN]

Harris, W.E. (1992): Analyses, Risks, and Authoritative Misinformation. Analytical Chemistry 64, 665-671. [RISK ASSESSMENT]

Harris, H.J.; Wenger, R.B.; Harris, V.A.; DeVault, D.S. (1993): A Method for Assessing Environmental Risk: A Case Study of Green Bay, Lake Michigan. Environmental Management in press. [GREEN BAY, LAKE MICHIGAN, RISK ASSESSMENT]

Hartig, John H.: (1993). A survey of fish-community and habitat goals/objectives/targets and status in Great Lakes Areas of Concern. Great Lakes Fishery Commission, Ann Arbor, MI. 95 pages. [FISH, GREAT LAKES, HABITAT, RESTORATION]

Hellawell, J.M. (1986): Biological Indicators of Freshwater Pollution and Environmental Management. Elsevier Applied Science Publishers, New York, NY. [INDICATOR, MANAGEMENT, POLLUTION, TOXICS, WATER COLUMN]

Herdendorf, Charles E. (1982). Large Lakes of the World, Center for Lake Erie Area Research, Ohio Sea Grant Program, The Ohio State University, Reprint OHSU-RS-008.

Herdendorf, Charles E. (1984); Inventory of the Morphometric and Limnologic Characteristics of the Large Lakes of the World. Clear Technical Report No. 286. United States Geological Survey, Office of International Hydrology, International Hydrological Program, United Nations Educational, Scientific, and Cultural Organization, The Ohio State University Center for Lake Erie Area Research, Columbus, OH.

- Heufelder, George R.; Schneeberger, Philip J.; Madenjian, Charles P.; Rutecki, Thomas L.; Mansfield, Pamela J.; Auer, Nancy A.; Noguchi, George E. (1981): Special Report Number 86 Great Lakes Research Division, The University of Michigan: Adult, Juvenile, and Larval Fish Populations in the Vicinity of the J.H. Campbell Power Plant, Eastern Lake Michigan, 1977-1980.
- Heufelder, G.R.; Jude, D.J.; and Tesar, F.J. (1982): Effects of Upwelling on Local Abundance and Distribution of Larval Alewife (*Alosa pseudoharengus*) in Eastern Lake Michigan, Volume 39, Number 11, pgs. 1531-1537.
- Holey, M.E., R.W. Rybicki, G.W. Eck, E.H. Brown Jr., J.E. Marsden, D.S. Lavis, M.L. Toney, T.N. Trudeau, and R.M. Horrall. 1995. Progress Toward Lake Trout Restoration in Lake Michigan. J. Great Lakes Res. 21(Supplement 1):128-151.
- Hunsaker, C.T.; Carpenter, D.E. (1990): Environmental Monitoring and Assessment Program: Ecological Indicators. U.S. Environmental Protection Agency, Office of Research and Development, Research Triangle Park, NC. [INDICATOR, PROGRAM]
- Illinois Environmental Protection Agency (): Lake Michigan Water Quality Report 1985. 174 Pages. [GREAT LAKES, LAKE MICHIGAN, WATER QUALITY, TOXICS, PLANKTON, CHLORIDE]
- Illinois Environmental Protection Agency (1988): Lake Michigan Water Quality Report 1986. 128 Pages. (IEPA/WPC/88-015). [GREAT LAKES, LAKE MICHIGAN, WATER QUALITY, TOXICS, PLANKTON, CHLORIDE]
- Illinois State Environmental Protection Agency, Springfield, Div. of Water Pollution Control (1988): Lake Michigan Water Quality Report, 1986. 140 pages. Section 305(b) Report (EPA/WPC/88-015) [EUTROPHICATION, FISH, HUMAN USE, LAKE MICHIGAN, POLLUTION, TOXICS, WASTE DISPOSAL, WATER COLUMN]
- Illinois Environmental Protection Agency (1992): Illinois Water Quality Report 1990-1991. Section 305 (b) Report. 405 pages. [EUTROPHICATION, FISH, HABITAT, HUMAN HEALTH, HUMAN USE, SEDIMENT, TOXICS, WATER COLUMN, WETLAND]
- Illinois Environmental Protection Agency, Bureau of Water, Division of Water Pollution Control (1993): Lake Michigan Water Quality Report 1989 - 1991. 135 Pages. (IEPA/WPC/93-065) [HEALTH, FISH, GREAT LAKES, HUMAN HEALTH, LAKE MICHIGAN, LEAD, PCB, PESTICIDE, PLANKTON, POLLUTION, RECREATION, REGULATION WATER QUALITY, WATER QUALITY STANDARDS]
- Illinois Environmental Protection Agency, Bureau of Water (1993): Water Quality in Illinois (1990-1991). 9 Pages. (IEPA/WPC/92-224). [WATER QUALITY, GREAT LAKES, RIVERS, STREAMS, FISH, SEDIMENT, TOXICS]
- Indiana Department of Environmental Management (1991): The Remedial Action Plan for the Indiana Harbor Canal, The Grand Calumet River, and the Nearshore Lake Michigan - Stage One. 84 Pages. [LAKE MICHIGAN, WATER QUALITY]
- Indiana State Board of Health, Division of Water Pollution Control (): Physical & Chemical Characteristics of the Indiana Portion of Lake Michigan 1980-1981. Prepared for the Indiana

- Environmental Management Board, Indiana Stream Pollution Control Board. 76 Pages. [GREAT LAKES, LAKE MICHIGAN, WATER QUALITY, CHLORIDES]
- International Joint Commission (1982): A Review of the Pollution Abatement Programs Relating to the Petroleum Refinery in the Great Lakes Basin. [REFINERY, POLLUTION ABATEMENT, CANADA, US, EFFLUENT LIMITS]
- International Joint Commission (1983): An Inventory of Chemical Substances Identified in the Great Lakes Ecosystem. Vol. 1-6. International Joint Commission, Great Lakes Water Quality Board, Windsor, Ontario. [ECOSYSTEM, GREAT LAKES, TOXICS]
- International Joint Commission Surveillance Work Group (1985): Guidance on Characterization of Toxic Substances Problems in Areas of Concern in the Great Lakes Basin (1985). [TOXICS, TOXICS PROBLEMS IN THE GREAT LAKES]
- International Joint Commission (1986): Great Lakes International Surveillance Plan (2 Vols)., Windsor, Ontario. [GREAT LAKES]
- International Joint Commission (1986): Report of the Aquatic Ecosystem Objectives Committee, 1985 Annual Report Great Lakes Science Advisory Board Report to the International Joint Commission. [ECOSYSTEM]
- International Joint Commission, Great Lakes Regional Office. (1988). Report on Modeling the Loading-Concentration Relationship for Critical Pollutants in the Great Lakes, Prepared by the Task Force on Chemical Loadings of the Toxic Substances Committee, October. [GREAT LAKES, TOXICS, LOADINGS]
- International Joint Commission (1989): Fifth Biennial Report on Great Lakes Water Quality Part II Under the Great Lakes Water Quality Agreement of 1978 to the Governments of the United States and Canada and the State and Provincial Governments of the Great Lakes Basin. 57 pages. [EXOTIC SPECIES, FISH, GREAT LAKES, HUMAN HEALTH, LAKE SUPERIOR, PROGRAM, TOXICS, WATER COLUMN]
- International Joint Commission (1989): 1989 Report on Great Lakes Water Quality. Great Lakes Water Quality Board. [WATER COLUMN]
- International Joint Commission, United States and Canada (1990): Fifth Biennial Report on Great Lakes Water Quality. International Joint Commission, Washington, DC. (ISBN 1-895085-03-09) [GREAT LAKES, WATER COLUMN]
- International Joint Commission and Great Lakes Fishery Commission (1990); Exotic Species and the Shipping Industry: The Great Lakes-St. Lawrence Ecosystem at Risk. A special report to the Governments of the United States and Canada. 77 pages. [ECOSYSTEM, EXOTIC SPECIES, GREAT LAKES]
- International Joint Commission, Virtual Elimination Task Force (1991): Persistent Toxic Substances: Virtually Eliminating Inputs to the Great Lakes. Interim report., Windsor, Ontario. 42 pages. [GREAT LAKES, LOADINGS, TOXICS, WATER COLUMN]
- International Joint Commission (1992): Sixth Biennial Report on Great Lakes Water Quality Under the Great Lakes Water Quality Agreement of 1978 to the Governments of the United States and

Canada and the State and Provincial Governments of the Great Lakes Basin. 60 pages. [ECOSYSTEM, GREAT LAKES, LAKE SUPERIOR, PROGRAM; RESTORATION; TOXICS, WATER COLUMN]

International Joint Commission: Seventh Biennial Report on Great Lakes Water Quality. [WATER QUALITY, GREAT LAKES]

International Joint Commission (1993). Great Lakes Science Advisory Board. Report to the International Joint Commission.

International Joint Commission (1994): Bibliography of Reports Issued Under the Boundary Waters Treaty of 1909 and Great Lakes Water Quality Agreements of 1972 and 1978, and the Protocol Amending the 1978 Agreement.

International Joint Commission Reference Group; International Reference Group on Great Lakes Pollution (From Land Use Activities) Trophic Characterization of the US and Canadian Nearshore Zones of the Great Lakes. [TROPIC LEVELS, TROPIC STATUS, NEARSHORE ZONES, CHLOROPHYLL, PHOSPHOROUS, EUTROPHICATION]

International Joint Commission. Proceedings of the Roundtable on Contaminant-caused Reproductive Effects in Salmonids. [REPRODUCTIVE EFFECTS, SALMON, SALMONIDS, TROUT, CHLORINATED ORGANICS]

Jackson, M.B., E.M. Vandermeer, and L.S. Heintsch. 1990. Attached Filamentous Algae of Northern Lake Superior: Field Ecology and Biomonitoring Potential During 1983. J. Great Lakes Res. 16(1):158-168.

Jacobson, Joseph L.; Jacobson, Sandra W. (1993): A 4-Year Follow-up Study of Children Born to Consumers of Lake Michigan Fish. J. Great Lakes Res. 19(4), Pages 776-783. [GREAT LAKES, FISH, HEALTH]

Janssen, John; and Quinn, John. (19__): Chapter 17 - Biota of the Naturally Rocky Area of Southwestern Lake Michigan with Emphasis on Potential Fish Prey.

Johnson, M.G., O.C. McNeil, and S.E. George. 1987. Benthic Macroinvertebrate Associations in Relation to Environmental Factors in Georgian Bay. J. Great Lakes Res. 13(3):310-327.

Journal of Great Lakes Research. 1982. Ecology of Filamentous Algae. J. Great Lakes Res. 8(1):1-237.

Jude, David J: Entrainment of Fish Larvae and Eggs on the Great Lakes, With Special Reference to the D.C. Cook Nuclear Plant, Southeastern Lake Michigan. [FISH, PLANKTON, LAKE MICHIGAN]

Jude, D.J.; Klinger, S.A.; Enk, M.D. (1981): First Evidence of Natural Reproduction by Planted Lake Trout in Lake Michigan. Journal of Great Lakes Research 7, 57-61. [FISH, LAKE MICHIGAN, REPRODUCTION]

Jude, David J.; and Tesar, Frank J. (1985): Recent Changes in the Inshore Forage Fish of Lake Michigan. Canadian Journal of Fisheries and Aquatic Sciences, Volume 42, Number 6, Pp. 1154-1157. [FISH, LAKE MICHIGAN]

Jude, D.J.; Heang T.T.; Heufelder, G.R.; et.al. : Adult, Juvenile and Larval Fish Populations in the Vicinity of the J.H. Campbell Power Plant, Eastern Lake Michigan, 1977-1980. Special Report No. 86 of the Great Lakes Research Division. University of Michigan.

Jude, David J.; Reider, Robert H.; Smith, Gerald R. (1992): Establishment of Gobiidae in the Great Lakes Basin. *Canadian Journal of Fisheries and Aquatic Sciences* 49(2), 416-421. [EXOTIC SPECIES, GREAT LAKES]

Jude, D.J. (1992): Evidence for Natural Reproduction by Stocked Walleyes in the Saginaw River Tributary System, Michigan. *North American Journal of Fisheries Management* 12:386-395. [FISH, GREAT LAKES]

Jude, David J.; Pappas, Janice (1992): Fish Utilization of Great Lakes Coastal Wetlands. *Journal of Great Lakes Research* 18, 651-672. [FISH, GREAT LAKES, HABITATS WETLAND]

Jude, D.J.; Leach, J. (1993): The Great Lakes Fisheries. Chap. 22. In: *North American Fisheries Management Textbook of American Fisheries Society*. (Eds: Kohler,C; Hubert,W), Bethesda, MD. [FISH, GREAT LAKES]

Keeler, Gerald J.; Pacyna, Jezef M.; Bidleman, Terry F.; Nriagu, Jerome O. (1993): Identification of Sources Contributing to the Contamination of the Great Waters by Toxic Compounds. 145 pages. [LOADINGS, TOXICS]

Kelly, J.R.; Harwell, M.A. (1989): Indicators of ecosystem response and recovery. In: *Ecotoxicology: Problems and Approaches*. (Eds: Levin, S.A.; Harwell ,M.A.; Kelly, J.R., Kimball, K.D.) Springer Veriag, New York, NY, 9-40. [ECOSYSTEM, INDICATOR, TRENDS]

Kenaga, D.E., Creal, W.S., and Basch, R.E.: *Limnology of Michigan's Nearshore Waters of Lake Michigan*. U.S. EPA: 100 pp. EPA 905/3-83-003.

Kielty, T.J.; Landrum, P.F. (1990): Population-Specific Toxicity Responses by the Freshwater Oligochaete *Stylocrilius heringianus*, in *Natural Lake Michigan Sediments*. *Environmental Toxicology and Chemistry* 9, 1147-1154. [BENTHOS, LAKE MICHIGAN, SEDIMENT]

Kitchell, J.F.; Evans, M.S.; Scavia, D.; Crowder, L.B. (1988): Regulation of water quality in Lake Michigan: Report of the Food Web Workshop. *Journal of Great Lakes Research* 14, 109-114. [EUTROPHICATION, LAKE MICHIGAN, PROGRAM, WATER COLUMN]

Koonce, Joseph F. (1990): Commentary on Fish Community Health: Monitoring and Assessment in Large Lakes. *Journal of Great Lakes Research* 16, 631-634. [ECOSYSTEM, FISH, GREAT LAKES, HEALTH]

Kratt, C.E. (1993): Changes in the Fish Community of Lower Green Bay, Lake Michigan. In: *IAGLR Conference, Green Bay, Wisconsin, June 1993*. [FISH, GREEN BAY]

Krueger, C.C.; May, B. (1991): Ecological and Genetic Effects of Salmonid Introductions in North America. *Canadian Journal of Fisheries and Aquatic Sciences* 44 (Suppl. 1), 66-77. [FISH]

- Lauritsen, D.D., S.C. Mozley, and D.S. White. 1985. Distribution of Oligochaetes in Lake Michigan and Comments on Their Use as Indices of Pollution. *J. Great Lakes Res.* 11(1):67-76.
- Lavrentyev, P.J., W.S. Gardner, J.F. Cavaletto, and J.R. Beaver. 1995. Effects of the Zebra Mussel (*Dreissena polymorpha* Pallas) on Protozoa and Phytoplankton from Saginaw Bay, Lake Huron. *J. Great Lakes Res.* 21(4):545-557.
- Leatherland, John F. (1993): Field Observations on Reproductive and Development Dysfunction in Introduced and Native Salmonids from the Great Lakes. *J. Great Lakes Res.* 19(4), Pages 737-751. [GREAT LAKES, TOXICS]
- Lee, D.; Eedford, K.; Yen, C. (1993): Storm and Entrainment Effects on Tributary Sediment Loads. *J. Hydraulic Engrg.* 119(12). [LOADINGS, SEDIMENT]
- Leonard, D.; Manam, R. (1988): Reassessing Estimates of Great Lakes Consumptive Use and Impacts. In: *The Great Lakes: Living with North America's Inland Waters.* (Ed: Kickcox, D) American Water Resources Association Tech. Pub TPS48-3, Bethesda, MD, 33-44. [GREAT LAKES, HUMAN USE]
- Lesht, B.M. and N. Hawley. 1987. Near-Bottom Currents and Suspended Sediment Concentration in Southeastern Lake Michigan. *J. Great Lakes Res.* 13(3):375-386.
- Lesht, B.M.: Michigan Eutrophication Model: Calibration, Sensitivity, and 5-Year Hindcast Analysis. U.S. EPA/Argonne National Laboratory: September 1984. 55 pp.
- Lesht, B.M., and Rockwell, D.C.: The State of the Middle Great Lakes: Results of the 1983 Water Quality Survey of Lakes Erie, Huron, and Michigan. U.S. EPA August 1985, 171 pp. (ANL/ER-84-3).
- Lesht, B.M.; Fontaine, T.D. III; Dolan, D.M. (1991): Great Lakes Total Phosphorus Model: Post Audit and Regionalized Sensitivity Analysis. *Journal of Great Lakes Research* 17, 3-17. [EUTROPHICATION, GREAT LAKES, PHOSPHORUS, WATER COLUMN]
- Likens, G.E., ED. (1972): Nutrients and Eutrophication: The Limiting Nutrient Controversy Proceedings of the Symposium on Nutrients and Eutrophication W.K. Kellogg Biological Station, Michigan State U. 11 and 12 February 1971. American Society of Limnology and Oceanography, Inc.
- Locke, A; Reid, D.M.; Sprules, W.G.; Carlton, I.T.; van Leeuwen, J.C. (1991): Effectiveness, of Mid-Ocean Exchange in Controlling Freshwater and Coastal Zooplankton in Ballast Water. Can. Tech. Rep. Fish. Aquat Sci. No. 1822. [PLANKTON]
- Lorenz, R.C., M.E. Monaco, and C.E. Herdendorf. 1991. Minimum Light Requirements for Substrate Colonization by *Cladophora glomerata*. *J. Great Lakes Res.* 17(4):536-542.
- Loucks, O.L. (1982): Concern for Acidic Deposition in the Great Lakes Region Chap. 2. In: *Acid Precipitation: Effects on the Ecological Systems.* 21-41. (ISBN-0-250-10509, EPA/600/D-89/239 Grant R-8094 12). [ATMOSPHERE, GREAT LAKES, POLLUTION, WATER COLUMN]

- Lowe, R.L., and R.W. Pillsbury. 1995. Shifts in Benthic algal Community Structure and Function Following the Appearance of Zebra Mussels (*Dreissena polymorpha*) in Saginaw Bay, Lake Huron. J. Great Lakes Res. 21(4):558-566.
- LTI, Limno-Tech, Inc. (1984): Field Methodology and Results for Indiana Harbor and Two Nearshore Areas of Lake Michigan. Limno-Tech, Inc. Prepared for U.S. Army Engineer District, Detroit. Delivery Order 0008. 67 pp.
- LTI, Limno-Tech, Inc. (1993): Great Lakes Environmental Assessment. Prepared for: The National Council of the Paper Industry for Air and Stream Improvement (NCASI). [SEDIMENTS, FISH, TOXICS, GREAT LAKES, LAKE MICHIGAN, HEALTH, HABITAT]
- Lyons, J.; Bedford, K.; Yen, C.; Lee, D.; Mark, D. (1988): Determination of Suspended Concentrations from Multiple Day Landsat and AVHRR data. Journal of Remote Sensing of the Environment 24,364-373. [SEDIMENT]
- Mac, Michael; Gilbertson, Michael (Eds.) (1990): Great Lakes Science Advisory Board's Biological Effects Subcommittee of the Ecological Committee. Report to the International Joint Commission. Proceedings of the Roundtable on Contaminant-Caused Reproductive Problems in Salmonids., Windsor, Ontario. 45 pages. [DEFORMITIES, FISH, GREAT LAKES, LAKE ERIE, LAKE MICHIGAN, LAKE ONTARIO]
- Mac, Michael J.; Edsall, Carol C. (1991): Environmental Contamination and the Reproductive Success of Lake Trout in the Great Lakes an Epidemiological Approach. Journal of Toxicology and Environmental Health 33, 375-394. [EPIDEMIOLOGY, FISH, GREAT LAKES, PCB, POPULATION, REPRODUCTION, TOXICS]
- Mac, Michael J.; Schwartz, Ted R.; Edsall, Carol C.; Frank, Anthony M. (1993): Polychlorinated Biphenyls in Great Lakes Lake Trout and Their Eggs: Relations to Survival and Congener Composition 1979-1988. J. Great Lakes Res. 19(4), Pages 752-765. [FISH, GREAT LAKES]
- Mackay, D.; Paterson, S. (1981): Calculating Fugacity. Environmental Science and Technology 15, 1006-1014. [ECOSYSTEM]
- Mackay, Donald (1990): Modeling pathways for toxic chemicals. In: Great Lakes Monograph No.3. Contemporary and Emerging Issues in the Great Lakes. Proceedings from a Colloquium Between The University at Buffalo and the University of Toronto April 12, 1989. (Eds: Bankert, Lynne S; Flint, R Warren) Great Lakes Program. State University of New York, Buffalo, New York, 33-35. [LAKE ONTARIO, PCB, TOXICS]
- Madenjian, C.P.; Jude, D.J. (1985): Comparison of Sleds Versus Plankton Nets for Sampling Fish Larvae and Eggs. Hydrobiologia 124, Pages 275-281. [FISH, GREAT LAKES]
- Magnuson, John J. (1992): A Sense of Beginning the Laurentian Great Lakes in the Process of Rehabilitation. Restor. Manag. Notes 10, 29-32. [ECOSYSTEM, GREAT LAKES, RESTORATION]
- Maguire, L. (1988): Decision analysis: An integrated approach to ecosystem exploitation and rehabilitation. In: Rehabilitating Damaged Ecosystems. (Ed: Cairns, Jr, J.) CRC Press, Boca Raton, FL, 105-122. [ECOSYSTEM; PROGRAM]

Makarewicz, J.C. (1987). Phytoplankton and Zooplankton Composition, Abundance, and Distribution: Lake Erie, Lake Huron, and Lake Michigan-1983. Vol. 1: Interpretive Report. GLNPO Report 87-05. USEPA: July 1987, 280 p. (EPA-905/3-84-006). [AQUATIC LIFE: FISH STUDIES AND OTHER BIOTA]

- Makarewicz, J.C. (1987): Phytoplankton and Zooplankton in Lakes Erie, Huron and Michigan: 1984. Volume 1, Interpretive Report, Final rept 1984-1985. Environmental Protection Agency, Chicago, IL. Great Lakes National Program Office. 295 pages. (EPA/905/348/001, GLPNO-88/03 Grant EPA-R-005772) [EUTROPHICATION, FISH, GREAT LAKES, INDICATOR, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, NUTRIENTS, OPEN WATER, PLANKTON; POLLUTION, TRENDS, WATER COLUMN]
- Makarewicz, J.C. (1987): Phytoplankton Composition, Abundance, and Distribution: Nearshore Lake Ontario and Oswego River and Harbor. J. Great Lakes Res. 13(1):56-64.
- Makarewicz, J.C.; Bertram, P.E.; Lewis, T. (1989): Phytoplankton and Zooplankton in Lakes Erie, Huron, and Michigan: 1985. Volume 1. Interpretive Report. Final Rept. Environmental Protection Agency, Chicago, IL Great Lakes National Program Office. 272 pages. (EPA/905/3-90/003, GLNPO- 01/91) [ECOSYSTEM; EUTROPHICATION, GREAT LAKES, INDICATOR, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, PLANKTON, POLLUTION, WATER COLUMN]
- Makarewicz, Joseph C.; Bertram, Paul (1991): A lakewide comparison study of phytoplankton biomass and its species composition in Lake Huron, 1971 to 1985. Journal of Great Lakes Research 17, 553- 564. [LAKE HURON, OPEN WATER, PLANKTON, TRENDS, WILDLIFE]
- Makarewicz, Joseph C. (1991): Photosynthetic parameters as indicators of ecosystem health. Journal of Great Lakes Research 17, 333-343. [INDICATOR, LAKE ONTARIO]
- Makarewicz, Joseph C. (1991): Feasibility of Shoreside Monitoring of the Great Lakes. J. Great Lakes Res. 17(3):344-360.
- Makarewicz, Joseph C. (1993): Phytoplankton Biomass and Species Composition In Lake Erie, 1970 to 1987. Journal of Great Lakes Research 19, 258-272. [EUTROPHICATION, LAKE ERIE, PLANKTON, WATER COLUMN]
- Makarewicz, Joseph C.; Bertram, Paul. 1995. A Decade of Predatory Control of Zooplankton Species of Composition of Lake Michigan. J. Great Lakes Res. 21(4):620-640.
- Makarewicz, Joseph C.; Bertram, Paul. 1997. Changes in phytoplankton size-class abundance and species composition coinciding with changes in the zooplankton community of Lake Michigan 1983-1992. Draft.
- Mandrak, Nicholas E. (1989): Potential invasion of the Great Lakes by fish species associated with climatic warming. Journal of Great Lakes Research 15, 306-316. [FISH, GREAT LAKES]
- Manny; B.A.; Fahnenstiel, G.L.; Gardner, W.S. (1987): Acid Rain Stimulation of Lake Michigan.
- Marsden, J.E., J.J. Casselman, T.A. Edsall, R.F. Elliott, J. D. Fitzsimons, W.H. Horns, B.A. Manny, S.C. McAughey, P.G. Sly, and B.L. Swanson. 1995. Lake Trout Spawning Habitat in the Great Lakes - A Review of Current Knowledge. J. Great Lakes Res. 21(Supplement 1):487-497.
- Marti, Edwin A.; Armstrong, David E. (1990): Polychlorinated biphenyls in Lake Michigan tributaries. Journal of Great Lakes Research 16, 396-405. [LAKE MICHIGAN, LOADINGS, PCB, POLLUTION, TOXICS, WATER COLUMN]

- Masalek, J. (1990): Evaluation of Pollutant Loads from urban Nonpoint Sources. Water Science and Technology 22, 23-30. [GREAT LAKES, LOADINGS, POLLUTION]
- Mansfield, P.J.; Jude, D.J.; Michaud, D.T.; Brazo, D.C.; Gulvas, J. (1983): Distribution and Abundance of Larval Burbot and Deepwater Sculpin in Lake Michigan. Transactions of the American Fisheries Society 112, Pages 162-172. [FISH, LAKE MICHIGAN]
- Mansfield, P.J.; Jude, D.J. (1986): Alewife (*Alosa pseudoharengus*) survival during the first growth season in southeastern Lake Michigan. Reprinted from Canadian Journal of Fisheries and Aquatic Sciences. Vol. 43, No. 7, pp 1318-1326. [FISH, LAKE MICHIGAN]
- Marshall, T.R. et al. (1987): Using the Lake Trout as an Indicator of Ecosystem Health: Application of the Dichotomous Key. (Great Lakes fishery Commission Report 49.) Ontario Ministry of Natural Resources, Canada. 41 pages. [ECOSYSTEM, FISH, GREAT LAKES, HABITAT, HEALTH, INDICATOR]
- Mass Balance Workshop Steering Committee (1991): Proceedings of the Mass Balance Workshop. Report to the Surveillance Subcommittee to the Great Lakes Water Quality Board. 91 pages. [GREAT LAKES, LAKE ONTARIO, MANAGEMENT, TOXICS]
- May, R.M. (1981): Patterns in Multi-Species Communities. In: Theoretical Ecology: Principles and Applications. 2nd ed. (Ed: May, RM) Blackwell Scientific Publications, Oxford. [ECOSYSTEM]
- McComas, Steve: LakeSmarts - The First Lake Maintenance Handbook. [FISH, SEDIMENTS, GREAT LAKES]
- McComish, Thomas S.; Shroyer, Steven M. (1993): Characteristics of the Near - Shore Non-Salmonine Fish Community in Indiana Waters of Lake Michigan with Emphasis on Yellow Perch. Project Performance Report for 1992, Federal Aid Project F-18-R, Segment 5, Indiana Department of Natural Resources, Division of Fish and Wildlife. Pages.
- Metropolitan Water Reclamation District of Greater Chicago (1982-86): Research and Development Report 93-2 of the Greater Chicago Water Reclamation District for Southwestern Lake Michigan. [WATER QUALITY, SEDIMENT QUALITY, BENTHIC INVERTEBRATES]
- Metropolitan Water Reclamation District of Greater Chicago, Research and Development Department: Report on Lake Michigan Water Quality - Clean Water Quarterly: January Through March 1993. [LAKE MICHIGAN, WATER QUALITY]
- Metropolitan Water Reclamation District of Greater Chicago, Research and Development Department: Report on Lake Michigan Water Quality - Clean Water Quarterly: April Through June 1993. [LAKE MICHIGAN, WATER QUALITY]
- Metropolitan Water Reclamation District of Greater Chicago, Research and Development Department: Report on Lake Michigan Water Quality - Clean Water Quarterly: July Through September 1993. [LAKE MICHIGAN, WATER QUALITY]
- Michigan Department of Natural Resources, Surface Water Quality Division (1986): Water Quality and Pollution Control in Michigan. Michigan 305(b) Report: Volume 9: Water Years 1984 and

1985. 132 Pages. [WATER QUALITY, LAKE MICHIGAN, GREAT LAKES, TOXICS, RIVERS, AQUATIC LIFE, FISH, HEALTH]
- Michigan Department of Natural Resources, Office of the Great Lakes (1986): State of the Great Lakes: Annual Report for 1986. 40 Pages. [GREAT LAKES, LAKE MICHIGAN, SEDIMENTS, FISH, TOXICS]
- Michigan Department of Natural Resources (1988): State of the Great Lakes 1978-1988. 36 pages. [GREAT LAKES, HUMAN USE, TRENDS]
- Michigan Department of Natural Resources, Office of the Great Lakes: State of the Great Lakes 1988-1989. 48 Pages. [GREAT LAKES, LAKE MICHIGAN]
- Michigan Department of Natural Resources, Office of the Great Lakes: Great Lakes Connections: State of the Great Lakes 1990-1991. 47 Pages. [GREAT LAKES, LAKE MICHIGAN, HUMAN HEALTH, FISH]
- Michigan Department of Natural Resources (1990): Water Quality and Pollution Control in Michigan 1990 Report. Section 305(b) Report. 274 pages. [AVIAN SPECIES, EUTROPHICATION, FISH, HABITAT, HUMAN HEALTH, HUMAN USE, PLANKTON, SEDIMENT, TOXICS, WATER COLUMN, WETLAND]
- Michigan Department of Natural Resources, Surface Water Quality Division (1992): Water Quality and Pollution Control in Michigan: 1992 Report. Michigan 305(b) Report: Volume 12. Lansing, MI. 351 Pages. [WATER QUALITY, LAKE MICHIGAN, GREAT LAKES, TOXICS, RIVERS, SEDIMENTS, AQUATIC LIFE, FISH, HEALTH]
- Michigan Department of Natural Resources, Office of the Great Lakes (1993): State of the Great Lakes: 1993 Annual Report. 47 Pages. [GREAT LAKES, LAKE MICHIGAN, SEDIMENTS, FISH, TOXICS, HABITAT, CHLORINE]
- Miller, M.A., and M.E. Holey. 1992. Diets of Lake Trout Inhabiting Nearshore and Offshore Lake Michigan Environments. J. Great Lakes Res. 18(1):51-60.
- Mills, Edward L.; Leach, Joseph H.; Carlton, James T.; Secor, Carol L. (1993): Exotic Species in the Great Lakes: A History of Biotic Crimes and Anthropogenic Introductions. Journal of Great Lakes Research 19, 1-54. [ECOSYSTEM, EXOTIC SPECIES, GREAT LAKES, TRENDS]
- Mills, Edward L.; Leach, Joseph H.; Secor, Carol L.; Carlton, James T. (1993): What's Next? The Prediction and Management of Exotic Species in the Great Lakes (Report of the 1991 Workshop). Great Lakes Fishery Commission, Ann Arbor, MI. 22 pages. [EXOTIC SPECIES]
- Milwaukee Metropolitan Sewerage District: Water Quality and Biological Data for Near Shore Lake Michigan - Information Provided to The ADVENT Group, Inc. on March 30, 1994. Jones Island Wastewater Treatment Plant. [LAKE MICHIGAN, WATER QUALITY]
- Mlot, Christine (1989): Great Lakes fish and the greenhouse effect. BioScience 39(Mar), 145. [ATMOSPHERE, FISH, GREAT LAKES]

- Moll, R. A.; Rossmann, R., Bares, J.A.; Horvath, F.J. (1991): Historical Trends of Chlorides in the Great Lakes. In: Deicing Chemicals and the Environment (Ed: D'Itri, FM) Lewis Publishers, Chelsea, MI, 303-322. [GREAT LAKES, TOXICS]
- Morehead, N.R., Robbins, J.A.; Mudroch, A. (1991): Anthropogenic Alteration of Carbon, Nitrogen, and Biogenic Silica Deposition in Lake George (St Mary's River) Since 1820. In: 34 Annual Meeting of the International Association for Great Lakes Research, Buffalo, NY, June 2-6. [SEDIMENT, ST MARYS RIVER]
- Mortimer, Clifford H.; Csanady, Gabriel T. (1975): Environmental Status of the Lake Michigan Region. Volume 2. Physical Limnology of Lake Michigan; Part 1. Physical Characteristics of Lake Michigan and its Responses to Applied Forces; Part 2. Diffusion and Dispersion. Argonne National Laboratory, Argonne, Illinois. [Hydrology, Wind Currents, Buoyancy, Seasonal Cycles]
- Munawar, M.; Munawar, I.F. (1982): Toxicity Studies on Natural Phytoplankton Assemblages by Means of Fractionation Bioassays. Can. Fish. Aquat. Sci. Tech. Rep. No. 1152. [PLANKTON]
- Munawar, M; Wong, PTS; Rhee, GY (1988): Effects of Contaminants on Algae: An Overview. In: Toxic Contamination in Large Lakes. Volume I: Chronic Effects of Toxic Contaminants in Large Lakes. Lewis Publishers, Chelsea, MI, 113-160. [GREAT LAKES, LAKE ONTARIO, LAKE SUPERIOR, PLANKTON, POLLUTION, TOXICS, WATER COLUMN]
- Munawar, M.; Wiese, T. (1989): Is the "microbial loop" an early warning indicator of anthropogenic stress? *Hydrobiologia* 188-189, 163-174. [GREAT LAKES, INDICATOR]
- Munawar, M. et al. (1989): Probing Ecosystem Health: a Multi-Disciplinary and Multi-Trophic Assay Strategy. *Hydrobiologia* 188-189, 93-116. [ECOSYSTEM, EUTROPHICATION, GREAT LAKES, HEALTH, NUTRIENTS, PLANKTON, SEDIMENT, TOXICS, WATER COLUMN]
- Munkittrick, Kelly R., Dixon, D. George (1989): A Holistic Approach to Ecosystem Health Assessment Using Fish Population Characteristics. *Hydrobiologia* 188-189, 123-135. [ECOSYSTEM, FISH, HEALTH, INDICATOR, POPULATION]
- Munkittrick, K.R.; Dixon, D.G. (1989): Use of White Sucker (*Catostomus commerson*) Populations to Assess the Health of Aquatic Ecosystems Exposed to Low-Level Contaminant Stress. *Canadian Journal of Fisheries and Aquatic Sciences* 46, 1455-1462. [ECOSYSTEM, FISH, HABITAT, INDICATOR]
- Nalepa, t. F. and M. A. Quigley. 1987. Distribution of Photosynthetic Pigments in Nearshore Sediments of Lake Michigan. *J. Great Lakes Res.* 13(1):37-42.
- The Nature Conservancy (1994): The Conservation of Biological Diversity in the Great Lakes Ecosystem: Issues and Opportunities. The Nature Conservancy, Great Lakes Program. 118 Pages. [GREAT LAKES, AQUATIC LIFE, BIOLOGICAL DIVERSITY]
- Nepszy, S.J.; Leach, J.H. (1973): First Records of the Chinese Mitten Crab, *Eriocheir sinensis* (Crustacea: Brachyrra) from North America. *Journal of the Fisheries Research Board of Canada* 30, 1909-1910. [EXOTIC SPECIES]
- Nepszy, Stephen J. et al. (1988): Parasites of Fishes in the Canadian Waters of the Great Lakes. (Great Lakes fishery Commission Technical Report 51.). 112 pages. [FISH, GREAT LAKES]

NOAA, U.S. National Marine Pollution Program Office (1980): Report of Great Lakes Region Conference on Marine Pollution Problems Held at Traverse City Michigan, on June 9-11, 1980. Prepared for the Federal Coordinating Council for Science, Engineering, and Technology, Washington, DC. 73 Pages. (NTIS # PB82 106295) [TOXICS, GREAT LAKES, TOXICS, SEDIMENTS, HUMAN HEALTH]

Ohio EPA, Division of Water Quality, Planning and Assessment, Ecological Assessment Section: A Preliminary Assessment of Ohio's Lake Erie Estuarine Fish Communities. 27 Pages. [FISH, GREAT LAKES, RIVER]

Ohio EPA, Division of Water Quality, Planning and Assessment, Ecological Assessment Section (1990): Ohio Water Resource Inventory, Executive Summary and Volume 1. 174 Pages. [FISH, GREAT LAKES, RIVER, STREAMS, BIOASSAY, AQUATIC LIFE, WATER QUALITY STANDARDS, HEALTH, HABITAT, TOXICS]

Ohio EPA, Division of Water Quality, Planning and Assessment, Ecological Assessment Section (1990): Compendium of Biological Results From Ohio Rivers, Streams, and Lakes: 1989 Edition. 176 Pages. [FISH, GREAT LAKES, RIVER, STREAMS, HABITAT]

Perrone, Michael Jr.; Schneeberger, Philip J.; Jude, David J. (1983): Distribution of Larval Yellow Perch (*Perca Flavescens*) in Nearshore Waters of Southeastern Lake Michigan. J. Great Lakes Res. 9(4), Pages 517-522. [FISH, LAKE MICHIGAN]

Phytoplankton Growth. Journal of Great Lakes Research 13, 218-223. [ATMOSPHERE, ECOSYSTEM, LAKE MICHIGAN, POLLUTION, WATER COLUMN]

Polls, I.; Sedita, S.J.; Zenz, D.R.; Lue-Hing, C. (1993): Research and Development Department - Report No. 93-2: A Comparison of the Water and Sediment Quality and Benthic Invertebrates in the Grand Calumet River, the Indiana Harbor Canal, Indiana Harbor, Southwestern Lake Michigan, and the Calumet River During 1982 and 1986. Metropolitan Water Reclamation District of Greater Chicago. [WATER QUALITY, SEDIMENT, BENTHIC]

Pontaseh, K.W.; Smith, E.P.; Cairns, Jr., J. (1989): Diversity indices, community comparison indices and canonical discriminant analysis: Interpreting the results of multispecies toxicity tests. Water Resources 23, 1229-1238. [INDICATOR, TOXICS]

Poulton, K.J., K.J. Simpson, D.R. Barton, and K.R. Lum. 1988. Trace Metals and Benthic Invertebrates in Sediments of Nearshore Lake Ontario at Hamilton Harbor. J. Great Lakes Res. 14(1):52-65.

Predation and Weather on Long-Term Water Quality Trends in Lake Michigan. Canadian Journal of Fisheries and Aquatic Sciences 43, 435-443. [FISH, LAKE MICHIGAN, TRENDS]

Pringle, C.M.; White, D.S.; Rice, C.P.; Tuchman, M.L. (1981): The Biological Effects of Chloride and Sulfite with Special Emphasis on the Laurentian Great Lakes. Publ. No. 20. Great Lakes Research Div. University of Michigan, Ann Arbor. 51 pages. [GREAT LAKES, POLLUTION]

Project Management Team, Functional Group 2 (1989): Living With the Lakes: Challenges and Opportunities. Annex B: Environmental Features, Processes and Impacts - An Ecosystem

Perspective on the Great Lakes-St Lawrence River System:, Burlington, Ontario and Chicago, Illinois. 169 pages. [ECOSYSTEM, GREAT LAKES, MANAGEMENT]

Project Management Team; Functional Group 5 (1989): Living With the Lakes: Challenges and Opportunities. Annex D: The Great Lakes Ecosystem Perspective - Implications for Water Levels Management, Burlington, Ontario and Chicago, Illinois. 79 pages. [ECOSYSTEM, GREAT LAKES, MANAGEMENT]

Public Health Service, Washington, D.C. (March 2, 1965): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan and Their Tributaries. Proceedings Of Conference held at Chicago, Illinois on March 2-9, 1965. Volume 1. (PB-230 544)

Public Health Service, Washington, D.C. (March 3, 1965): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Proceedings of Conference held at Chicago, Illinois on March 2-9, 1965. Volume 2. (PB-230 545)

Public Health Service, Washington, D.C. (March 4, 1965): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Proceedings of Conference held at Chicago, Illinois on March 2-9, 1965. Volume 3. (PB-230 546)

Public Health Service, Washington, D.C. (March 5, 1965): Pollution Of The Interstate Waters Of The Grand Calumet River, Little Calumet River, Calumet River, Wolf Lake, Lake Michigan And Their Tributaries. Proceedings of Conference held at Chicago, Illinois on March 2-9, 1965. Volume 4. (PB-230 547)

Quinn, John P.; Janssen, John. (1989): Crayfish Competition in Southwestern Lake Michigan: A Predator Mediated Bottleneck. Journal of Freshwater Ecology, Volume 5, Number 1. [PLANKTON, LAKE MICHIGAN, BENTHIC]

Rabe, Barry G.; Zimmerman, Janet B. (1992): Cross-Media Environmental Integration in the Great Lakes Basin. Environ Law 22, 253-289. [GREAT LAKES, MANAGEMENT, POLLUTION]

Rakoczy, G.P.; Rogers, R.D. (1987): Sportfishing Catch and Effort from the Michigan Waters of Lakes Michigan, Huron, and Erie, and their Important Tributary Streams, April 1, 1986-March 31, 1987. Michigan Department of Natural Resources, Fisheries Division Fisheries Technical Report Number 87-6A. [FISH, HUMAN USE, LAKE ERIE, LAKE HURON, LAKE MICHIGAN]

Rathke, David E.; and McRae, Gil (1989): 1987 Report on Great Lakes Water Quality, Appendix B Great Lakes Surveillance, Volume I.

Rathke, David E.; and McRae, Gil (1989): 1987 Report on Great Lakes Water Quality, Appendix B Great Lakes Surveillance, Volume II.

Rathke, David E.; and McRae, Gil (1989): 1987 Report on Great Lakes Water Quality, Appendix B Great Lakes Surveillance, Volume III.

Reed, P., Evans, R.L. (1981): Acute Toxicity of Chlorides, Sulfates, and Total Dissolved Solids to Some Fishers in Illinois. 50 p. Illinois State Water Survey, Office of Publications Services, Illinois Department of Energy and Natural Resources.

Richardson, W.L.; Paul, J.F. (1988): Historical Synopsis of Great Lakes Water Quality Research and Management and Future Directions. In: Protection of River Basins, Lakes, and Estuaries, Section 2, Protection and Management of Water Quality in Lakes and Estuaries. 83-97. (EPA/600/D-89/230,ERLN-1114) [DDT, EUTROPHICATION, GREAT LAKES, LAKE MICHIGAN, PCB, PLANKTON, POLLUTION, SEDIMENT, TOXICS, TRENDS, WATER COLUMN]

Robbins, J.A.; Morehead, N.R.; Mudroch, A. (1992): History of Contamination of Lake George and its Impact on Biogenic Silica Production from 1750-1986. In: Annual Meeting of the American Society of Limnology and Oceanography, Santa Fe, MN, February 9-14. [TOXICS]

Robertson, A. (1984): The Present Status of Research on the Zooplankton and Zoobenthos of the Great Lakes. Journal of Great Lakes Research 10, 156-163. [BENTHOS, GREAT LAKES, PLANKTON]

Rockwell, D.C. et al. (1980) Lake Michigan Intensive Study, 1976-1977. USEPA: December, 186 pp. (EPA-905/4-80-003-A) [LAKE STUDIES]

Rockwell, D.C.; Salisbury, D.K.; Lesht, B.M. (1989): Water Quality in the Middle Great Lakes: Results of the 1985 U.S. EPA (Environmental Protection Agency) Survey of Lake Erie, Huron, and Michigan: Final Report - Environmental Protection Agency, Chicago, IL Great Lakes National Program Office. 270 pages. (EPA/905/6-89/001,GLNPO-4) [EUTROPHICATION, GREAT LAKES, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, NITRATE, PHOSPHORUS, POLLUTION, WATER COLUMN]

Rodgers, P.W.; Salisbury, D.K. (1981): Water Quality Modeling of Lake Michigan and Consideration of the Anomalous Ice Cover of 1976-1977. Journal of Great Lakes Research 7, 467-480. [LAKE MICHIGAN, WATER COLUMN]

- Rodgers, Paul W.; Dilks, David W.; Samson, P. (1991). An integrated Model of Atmospheric and Aquatic Chemical Fate Useful for Guiding Regulatory Decisions: A Proposal. In: Long Range Transport of Pesticides. Kurtz, David A. (ed). Lewis Publishers, Chelsea, MI. [ATMOSPHERE, TOXICS]
- Romano, R.R.; McIntosh, A.W.; Kessler, W.V. et.al. (1977): Trace Metal Discharges of the Grand Calumet River. J. Great Lakes Res. October 1977. Internat. Assoc. Great Lakes Res. 3(1-2):144-147. [LAKE MICHIGAN]
- Rossmann, R. (1980): Soluble Element Concentrations and Complexations in Southeastern Lake Michigan: Journal of Great Lakes Research 6, 47-53. [LAKE MICHIGAN]
- Rossmann, R.: Trace Metal Concentrations in the Offshore Waters of Lakes Erie and Michigan. Special Report No. 108. Great Lakes Research Division: November 1984, 190 pp. (NTIS PB-85-199396-AS).
- Rossmann, Ronald; Chang, William Y. B.; Bowers, James A.; Feldt, Laurie; Barres, James: Southeastern Nearshore Lake Michigan: Impact of the Donald C. Cook Nuclear Plant. University of Michigan, Great Lakes Research Division, Publication 22.
- Rossmann, Ronald; Barres, James (1988): Trace Element Concentration in Near-Surface Waters of the Great Lakes and Methods of Collection, Storage, and Analysis. Journal of Great Lakes Research 14, 188-204. [GREAT LAKES, LAKE ERIE, LAKE HURON, LAKE MICHIGAN, LAKE ONTARIO, LAKE SUPERIOR, LEAD, MERCURY, TOXICS, WATER COLUMN]
- Rowan, David J.; Rasmussen, Joseph B. (1992): Why don't Great Lakes fish reflect environmental concentrations of organic contaminants? - An analysis of between-lake variability in the ecological partitioning of PCBs and DDT. Journal of Great Lakes Research 18, 724-741. [DDT, ECOSYSTEM; FISH, GREAT LAKES, PCB, TOXICS]
- Ryder, R.A.; Edwards, C.J. (Eds.) (1985): A Conceptual Approach for the Application of Biological Indicators of Ecosystem Quality in the Great Lakes Basin Report to the Great Lakes Science Advisory Board of the International Joint Commission., Windsor, ON. 169 pages. [ECOSYSTEM, GREAT LAKES, INDICATOR]
- Ryder, Richard A.; Kerr, Steve R. (1990): Aquatic harmonic communities: surrogates of ecosystem integrity. In: An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times. Proceedings of a 1988 Workshop Supported by the Great Lakes Fishery Commission and the Science Advisory Board of the International Joint Commission. Great Lakes Fishery Commission Seal Publication 90-4. (Eds: Edwards, C.J.; Regier, Henry, A) Great Lakes Fishery Commission, Ann Arbor, MI, 239-255. [ECOSYSTEM; GREAT LAKES, INDICATOR, WILDLIFE]
- Ryder, R.A. (1990): Ecosystem health, a human perception: definition, detection, and the dichotomous key. Journal of Great Lakes Research 16, 619-624. [ECOSYSTEM, GREAT LAKES, HEALTH, INDICATOR]
- Samples, K.; Bishop, R. (1981): The Lake Michigan Angler: A Wisconsin Profile. University of Wisconsin Sea Grant Institute Pub. WIS-SG-81-423., Madison, WI. 59 pages. [FISH, HUMAN USE, LAKE MICHIGAN]

- Scavia, D., and G.L. Fahnenstiel. 1987. Dynamics of Lake Michigan Phytoplankton: Mechanisms Controlling Epilimnetic Communities. *J. Great Lakes Res.* 13(2):103-120.
- Scavia, Donald et al. (1988): Dynamics of Lake Michigan Plankton: a Model Evaluation of Nutrient Loading, Competition, and Predation. *Canadian Journal of Fisheries and Aquatic Sciences* 45, 165-177.[EUTROPHICATION, LAKE MICHIGAN, PLANKTON, TRENDS, WATER COLUMN]
- Scavin, D.; Fahnenstiel, G.; Evans, M.; Jude, D.; Lehman, J. (1986): Influence of Salmonine Predation and Weather on Long-Term Water Quality Trends in Lake Michigan. *Canadian Journal of Fisheries and Aquatic Sciences* 43, 435-443.[FISH, LAKE MICHIGAN, TRENDS]
- Schelske, Claire, L.; Stoermer, Eugene F. (1971): Eutrophication, Silica Depletion, and Predicted Changes in Algal Quality in Lake Michigan. [EUTROPHICATION, SILICA, PHYTOPLANKTON]
- Schelske, C.L.; Feldt, L.E.; Simmons, M.S. (1980): Phytoplankton and Physical Chemical Conditions in Selected Rivers and the Coastal Zone of Lake Michigan, 1972 Publ. No 19. *Great Lakes Res. Div., Univ. of Michigan, Ann Arbor.* 162 pages. [LAKE MICHIGAN, PLANKTON]
- Schelske, C.L.; Stoermer, E.F.; Gannon, J.E. and Simmons, M.S. (1976): Biological, chemical and physical relationships in the Straits of Mackinaw. University of Michigan, Great Lakes Research Div. Spec. Rept. 60, 267 pages.
- Schelske, C.L.; Feldt, L.E.; Simmons, M.S.; and Stoermer, E.F. (1974): Storm induced relationships among chemical conditions and phytoplankton in Saginaw Bay and Western Lake Huron. *Proc. 17th Conf. Great Lakes Res.*, pp. 78-91. International Association Great Lakes Research.
- Schelske, C.L.; Moll, R.A.; Berry, T.; Stoermer, E.F. (1985): Limnological Characteristics of Northern Lake Michigan, 1976. Spec. Rep. No. 95. Great Lakes Research Division, Univ. of Michigan, Ann Arbor. 245 pages. [LAKE MICHIGAN]
- Schelske, C.L.; Stoermer, E.F.; and Feldt, L.E. (1971): Nutrients, phytoplankton productivity, and species composition as influenced by upwelling in Lake Michigan. *Proc. 14th Conference. Great Lakes Research, International Association Great Lakes Research.* pp.102-113.
- Schelske, C.L.; Feldt, L.E.; Santiago, M.A. and Stoermer, E.F.; (1972): Nutrient enrichment and its effect on phytoplankton and species composition in Lake Superior. *Proc. 15th Conf. Great Lakes Res., Int. Assoc. Great Lakes Res.*, pp. 149-165.
- Schelske, C.L.; and Stoermer, E.F.; (1972): Phosphorus, silica and eutrophication in Lake Michigan. In G.E. Likens (ed.). *Nutrients and Eutrophication: The Limiting-nutrient Controversy. Special Symposium. Vol. 1, ASLO*, pp. 157-171.
- Schelske, C.L.; Stoermer, E.F.; Fahnenstiel, G.L.; Haibach, M. (1986): Phosphorus Enrichment Silica Utilization, and Biogeochemical Silica Depletion in the Great Lakes. *Canadian Journal of Fisheries and Aquatic Sciences* 43, 407-415. (EPA/600/J-86/522 Grants EPA-R406294, NSF-OCE82-16588) [EUTROPHICATION, GREAT LAKES, LAKE ERIE, LAKE ONTARIO, PHOSPHORUS, WATER COLUMN]
- Schelske, Claire L. (1991): Historical Nutrient Enrichment of Lake Ontario: Paleolimnological Evidence *Canadian Journal of Fisheries and Aquatic Sciences* 48, 1529-1538.

[EUTROPHICATION, LAKE ONTARIO, LOADINGS, NUTRIENTS, PHOSPHORUS, SEDIMENT, TRENDS, WATER COLUMN]

Schierow, L.J.; Chesters, G. (1988): Evaluation of the Great Lakes Near Shore Index. *Water Research* 22, 269-277. [EUTROPHICATION, GREAT LAKES, MANAGEMENT, POLLUTION, WATER COLUMN]

Schindler, D.W. (1987): Detecting ecosystem responses to anthropogenic stress. *Can. J. Fish: Aquat. Sci.* 44(Suppl 1), 6-25.[ECOSYSTEM]

Schloesser, D.W., T.B. Reynoldson, and B.A. Manny. 1995. Oligochaete Fauna of Western Lake Erie 1961 and 1982: Signs of Sediment Quality Recovery. *J. Great Lakes Res.* 21(3):294-306.

Schneider, J.C.; Leach, J.H. (1979): Walleye Stocks in the Great Lakes 1800-1975: Fluctuations and Possible Causes. Technical Report No. 31. Great Lakes Fishery Commission, Ann Arbor, MI.[FISH] *Research* 22, 269-277. [EUTROPHICATION, GREAT LAKES, MANAGEMENT, POLLUTION, WATER COLUMN]

Schneider, J.C. et al. (1991): Walleye Rehabilitation in Lake Michigan, 1969-1989. In: Great Lakes Fishery Commission Special Publication 91-1. 23-61.[FISH, LAKE MICHIGAN, MANAGEMENT, POPULATION, RESTORATION, TRENDS, WATER COLUMN]

Science Applications International Corporation (1993): Revised Lake Michigan Lakewide Management Plan for Toxic Pollutants (Draft). 225 Pages. U.S. EPA Region V, Chicago IL. (EPA Contract # 68-C8-0066, W.A. No. C-4-98(O). [LAKE MICHIGAN]

Sediment Concentrations from Multiple Day Landsat and AVHRR data. *Journal of Remote Sensing of the Environment* 24, 364-373. [SEDIMENT]

Selgey, J.H., R.L. Eshenroder, C.C. Krueger, J.E. Marsden, and R.L. Pycha (Eds.). 1995. International Conference on Restoration of Lake Trout in the Laurentian Great Lakes. *J. Great Lakes Res. Special Edition. Volume 21, Supplement 1.*

Serafin, Rafal (1990): Rehabilitating Great Lakes Integrity in Times of Surprise. In: *An Ecosystem approach to the Integrity of the Great Lakes in Turbulent Times* (Great Lakes Fishery Comm 90-4). 45-67.[ECOSYSTEM, GREAT LAKES, RESTORATION]

Sheath, R.G. (1987). Invasions into the Laurentian Great Lakes by Marine Algae. *Arch. Hydrobiol. Beih. rgebn. Limnol.* 25, 165-186.[EXOTIC SPECIES, GREAT LAKES]

Simmers, J.W.; Lee, C.R.; Brandon, D.L.; Tatem, H.E.; Skogerboe, J.G. (1991): Information Summary, Area of Concern: Grand Calumet River, Indiana. 203 Pages. Miscellaneous Paper EL-91-10. USAE Waterways Experiment Station, Environmental Laboratory, Vicksburg, MS. [TOXICS, SEDIMENTS, GREAT LAKES, WATER QUALITY CRITERIA]

Sly, P.G. 1988. Interstitial Water Quality of Lake Trout Spawning Habitat. *J. Great Lakes Res.* 14(3):301-315.

Smith, S.H. (1972): Factors in Ecologic Succession in Oligotrophic Fish Communities of the Laurentian Great Lakes. *Journal of the Fisheries Research Board of Canada* 29, 717-730.[FISH; GREAT LAKES]

Sonzogni, W .L.; Rodgers, P.W.; Richardson, W. L; Monteith, T. J. (1982). Chloride Pollution of the Great Lakes. *Journal of the Water Pollution Control Federation*. 55(5), 513-521. [GREAT LAKES, POLLUTION]

Sonzogni, W.C.; Robertson, A.; Beeton, A.M. (1983): Great Lakes Management: Ecological Factors. *Environmental Management* 7, 531-542.[GREAT LAKES, MANAGEMENT]

Sonzogni, William C; Heidtke, Thomas M (1986): Water Quality Management for the Great Lakes. *Journal of Water Resources Planning and Management* 1 12(Jan), 48-63. [GREAT LAKES, MANAGEMENT, POLLUTION, WATER COLUMN]

Sonzogni, W.C.; Canale, R.P.; Lam, DCL.; Lick, W.; Mackay, D. (1987): Large Lake Models'- Uses, Abuses, and Future. *Journal of Great Lakes Research* 13, 387-396. (Environmental Research, Lab - Duluth, Grosse Ile, MI. Large Lakes Research Station). [EUTROPHICATION, GREAT LAKES, POLLUTION, TOXICS, WATER COLUMN]

Sprules, W. Gary; Riessen, Howard P.; Jin, Edward H. (1990): Dynamics of the Bythotrephes invasion of the St Lawrence Great Lakes. *Journal of Great Lakes Research* 16, 346-351. [EXOTIC SPECIES, GREAT LAKES]

Stanley, J.G.; Peoples, R.A. Jr; Mcann, J.A. (1991): U.S. Federal Policies, Legislation, and Responsibilities Related to Importation of Exotic Fishes and Other Aquatic Organisms. *Canadian Journal of Fisheries and Aquatic Sciences* 45 (Suppl 1), 162-166.[EXOTIC SPECIES]

Stearns, Forest; Hole, Francis, D.; Klopatek, Jeffery (1974): Environmental Status of the Lake Michigan Region. Volume 9. Soils of the Lake Michigan Drainage Basin-An Overview. Argonne National Laboratory, Argonne, Illinois.

Stearns, Forest; Hole, Lindsley, Diane (1977): Environmental Status of the Lake Michigan Region. Volume 11. Natural Areas of the Lake Michigan Drainage Basin and Endangered or Threatened Plant and Animal Species. Argonne National Laboratory, Argonne, Illinois

- Steedman, Robert J.; Regier, Henry A. (1990): Ecological bases for an understanding of ecosystem integrity in the Great Lakes basin. In: *An Ecosystem Approach to the Integrity of the Great Lakes in Turbulent Times*. Proceedings of a 1988. Workshop Supported by the Great Lakes Fishery Commission and the Science Advisory Board of the International Joint Commission. Great Lakes Fishery Commission Special Publication 90-4. (Eds: Edwards, C.J.; Regier, Henry, A.) Great Lakes Fishery Commission, Ann Arbor, MI, 257-270.[ECOSYSTEM, GREAT LAKES, HUMAN USE]
- Stemberger, R.S., and M. S. Evans. (1984): Rotifer Composition and Abundance in Lake Ontario During IFYGL. National Environmental Research Center.
- Stemberger, R.S., and M. S. Evans. (1984): Rotifer seasonal succession and copepod predation in Lake Michigan. *J. Great Lakes Res.* 10(4): 417-428.
- Stoermer, E.F., and Ladewski, T.B. (1975): Apparent optimal temperatures for the occurrence of some common phytoplankton species in southern Lake Michigan. *Great Lakes Res. Div., Univ. Michigan Publ.* 18, 49 p.
- Stoermer, Eugene F.; and Yang, J.J. (1970): Distribution and relative abundance of dominant plankton diatoms. *Univ. Michigan, Great Lakes Res. Div., Pub. No.* 16. 64 p.
- Stoermer, Eugene F.; Conley, Daniel J.; Schelske, Claire L. (1983): Early eutrophication in the lower Great Lakes: new evidence from biogenic silica in sediments. *Science* 222(21 Oct), 320-322.[EUTROPHICATION, GREAT LAKES, SEDIMENT, WATER COLUMN]
- Stoermer, Eugene F.; Stevenson, R.J. (1979): Green Bay phytoplankton, composition, abundance and distribution. EPA-905/3-79-002.
- Stoermer, E.F., Tuckman, M.L. (1979): Phytoplankton Assemblages of the Near-Shore Zone of Southern Lake Michigan. USEPA, November, 99 pp. (EPA 905/2-87-002). [AQUATIC LIFE: FISH STUDIES AND OTHER BIOTA]
- Stoermer, E.F. (1978): Phytoplankton Assemblages as indicators of water quality in the Laurentian Great Lakes. *Trans. Amer. Micros. Soc.* 97 (1): 2-16.
- Stoermer, E.F., et al (1975): Phytoplankton Composition and Abundance in Lake Ontario During IFYGL. National Environmental Research Center.
- Stoermer, E.F., and Theriot, E. (1985): Phytoplankton distribution in Saginaw Bay. *J. Great Lakes Res.* 11 (2): 132-142.
- Stoermer, E.F., and Kopczynska, E. (1967a): Phytoplankton populations in the extreme southern basin of Lake Michigan, 1962-1963. *Proc. 10th Conf. Great Lakes Res., Int. Assoc. Great Lakes Res.* pp. 88-106.
- Stoermer, E.F., and Kopczynska, E. (1967b): Phytoplankton populations in the extreme southern basin of Lake Michigan, 1962-1963, pp. 19-40. In J.C. Ayers and D.C. Chandler. *Studies on the environment and eutrophication of Lake Michigan*. Univ. Michigan, Great Lakes Res. Div., Spec. Rep. No. 30.

Stoermer, E.F., Schelske, C.L., Santiago, M.A. and Feldt, L.E. (1972): Spring phytoplankton abundance and productivity in Grand Traverse Bay, Lake Michigan, 1970. 15th Conf. Great Lakes Res. 1972: 181-191. Intern. Assoc. Great Lakes Res.

Strachan, WM.J. (1988): Test systems and exposure in the aquatic Environment Ambio 17, 394-397.[ECOSYSTEM, GREAT LAKES, RISK ASSESSMENT]

Sullivan, R.A.C., Baise, M., Sonzogni, W.C. (1981): Environmental Quality Maps for the U.S. Great Lakes Basin. USEPA, June, 98 pp. (EPA 905/4-79-028. [GREAT LAKES BASIN]

Task Force on Chemical Loadings of the Toxic Substances Committee (1988): Report on Modeling the Loading-Concentration Relationship for Critical Pollutants in the Great Lakes. Report to the Great Lakes Water Quality Board., Windsor, Ontario. 275 pages. [GREAT LAKES, LOADINGS, MANAGEMENT, PCB, POLLUTION, TOXICS, WATER COLUMN]

Thomann, Robert V.; Mueller, John A. (1987). Principles of Surface Water Quality Modeling and Control. Harper and Row, Publishers, New York. 644 pages. [GREAT LAKES]

Tin, Heang, T.; and Jude, David, J. (1983): Distribution and Growth of Larval Rainbow Smelt in Eastern Lake Michigan, 1978-1981.

Tisue, Thomas; Edgington, David N.; Seils, Charles A. (1988): Sulfate Reduction in Sediment Interstitial Fluids in Lakes Michigan and Erie. Journal of Great Lakes Research 14, 14-22. [EUTROPHICATION, LAKE ERIE, LAKE MICHIGAN, NUTRIENTS, TRENDS]

Torrey, Marguerite S. (1976): Environmental Status of the Lake Michigan. Chemistry of Lake Michigan Argonne National Laboratory, Argonne, Illinois. ANL/ES-40 Volume 3. [Conventional Pollutants, Nutrients, Data Review, Criteria]

The University of Michigan, Great Lakes Research Division (1979): Phytoplankton Assemblages of the Nearshore Zone of Southern Lake Michigan. 88 Pages. Prepared for U.S. EPA Great Lakes National Program Office, Chicago, IL. (Grant No.- R005337-001, NTIS # PB81-106387). [PLANKTON, LAKE MICHIGAN]

The University of Michigan, Great Lakes and Marine Waters Center. (1984): Field Distribution and Entrainment of Fish Larvae and Eggs at the Donald C. Cook Nuclear Power Plant, Southeastern Lake Michigan, 1973-1979. Special Report No. 105 of the Great Lakes Research Division. 320 Pages. [FISH, LAKE MICHIGAN]

The University of Michigan, Great Lakes and Marine Waters Center. (1985): Zooplankton Studies at the Donald C. Cook Nuclear Plant: 1979-1982 Investigations, Including Preoperational (1971-1974) and Operational (1975-1982) Comparisons. Special Report No. 111 of the Great Lakes Research Division. 236 Pages. [PLANKTON, LAKE MICHIGAN]

U.S. Army Corps. of Engineers (1986): Indiana Harbor Combined Disposal Facility and Maintenance Dredging, Lake Co., IN Draft EIS, February. [SEDIMENT, WASTE DISPOSAL]

U.S. Army Corps of Engineers, et. al., A Joint Federal/State 5-Year Strategy (1992-1997), Protecting the Great Lakes - Our Environmental Goals and How We Plan to Achieve Them. April 1992 DRAFT.

U.S. Fish and Wildlife Service, - IL, IN, MI, MN, NY, OH, PA, WI, and Chippewa/Ottawa Treaty Fishery Management Authority. A Joint Federal/State 5-Year Strategy (1992-1997): Protecting The Great Lakes - Our Environmental Goals and How We Plan to Achieve Them (April 1992 DRAFT).

U.S. Department of Health, Education, and Welfare, Technical Committee on Water Quality (1970): Water Quality in the Calumet Area. Conference on Pollution of Lower Lake Michigan, Calumet River, Grand Calumet River, Little Calumet River, and Wolf Lake, Illinois and Indiana. 131 Pages. (NTIS # PB245377). [LAKE MICHIGAN, RIVERS, INDUSTRIAL DISCHARGE, WATER QUALITY]

U.S. EPA, Office of Water Regulations and Standards (1983): Technical Guidance Manual for Performing Waste Load Allocations. Book II - Streams and Rivers: Chapter 1 - BOD/DO. (EPA D-337)(Contract No. 68-01-5918).

U.S. EPA, Office of Water Regulations and Standards (1983): Technical Guidance Manual for Performing Waste Load Allocations. Book IV - Lakes and Impoundments: Chapter 2 Nutrient/Eutrophication Impacts. 179 Pages. (EPA 440/4-84-019)

U.S. EPA, Office of Water (1983): Technical Support Manual: Waterbody Surveys and Assessments for Conducting Use Attainability Analysis. 220 Pages. Washington D.C. [CHEMICAL, PHYSICAL, BIOLOGICAL, HABITAT, RIVERS, STREAMS]

U.S. EPA, Office of Water (1983): Technical Support Manual: Waterbody Surveys and Assessments for Conducting Use Attainability Analysis - Volume II: Estuarine Systems. 185 Pages. Washington D.C. [CHEMICAL, PHYSICAL, FISH, PLANKTON, BENTHOS, AQUATIC LIFE]

U.S. EPA, Office of Water (1984): Technical Support Manual: Waterbody Surveys and Assessments for Conducting Use Attainability Analysis - Volume III: Lake Systems. 196 Pages. Washington D.C. [CHEMICAL, PHYSICAL, FISH, PLANKTON, BENTHOS, AQUATIC LIFE]

U.S. EPA, Office of Water Regulations and Standards (1984): Technical Guidance Manual for Performing Waste Load Allocations. Book II - Streams and Rivers: Chapter 3 - Toxic Substances. 404 Pages. (EPA 440/4-84-022)

U.S. EPA, Office of Public Affairs (1985): The Great Lakes. EPA Journal, Vol. 11 No.2, March 1985. 32 Pages. [GREAT LAKES, TOXICS, SEDIMENTS]

U.S. EPA, Office of Regulation and Standards Monitoring and Data Support Division (1986): Technical Guidance Manual for Performing Waste Load Allocations. Book IV - Lakes, Reservoirs and Impoundments: Chapter 3 - Toxic Substances Impact. 80 Pages. (EPA 440/4-87-002), Washington D.C.

U.S. EPA, Office of Water Regulations and Standards (1986): Technical Guidance Manual for Performing Waste Load Allocations. Book VI - Design Conditions: Chapter 1 - Stream Design Flow for Steady State Modeling. 59 Pages. (EPA 440/4-86 014)

U.S. EPA, Chicago, IL Great Lakes National Program Office (1988): Five Year Program Strategy for the Great Lakes National Program Office, FY1989-1993. 94 pages. (EPA/905/9-89/001,

GLNPO 89/1) [EUTROPHICATION, FISH, GREAT LAKES, MANAGEMENT, PROGRAM, SEDIMENT, TOXICS, WATER COLUMN]

U.S. EPA, Great Lakes National Program Office (1988): Phytoplankton and Zooplankton in Lakes Erie, Huron, and Michigan: 1984. 275 Pages. (EPA 905/3-88-001, GLNPO 03-88). Chicago, IL. [PLANKTON, GREAT LAKES, LAKE MICHIGAN]

U.S. EPA, Office of Water Regulations and Standards, Criteria and Standards Division (1988): Ambient Water Quality Criteria for Chloride.

U.S. EPA, Chicago, IL Great Lakes National Program Office (1989): U. S. Progress in Implementing the Great Lakes Water Quality Agreement: Annex Reports to the International Joint Commission, 1988. Final rept 89 pages. (EPA/905/9-89/006, GLNPO-05/89) [ATMOSPHERE, EUTROPHICATION, GREAT LAKES, GREEN BAY, GROUNDWATER, PHOSPHORUS, POLLUTION, SEDIMENT, TOXICS, WATER COLUMN]

U.S. EPA, Great Lakes National Program Office (1989): Phytoplankton and Zooplankton in Lakes Erie, Huron, and Michigan: 1985. 252 Pages. (EPA 905/3-90-003, GLNPO 01-91). Chicago, IL. [PLANKTON, GREAT LAKES, LAKE MICHIGAN]

U.S. EPA, Office of Water (1990): Technical Guidance Manual for Performing Waste Load Allocations. Book III - Estuaries: Part 1 - Estuaries and Waste Load Allocation Models. 65 Pages. (EPA 823-R-92-002), Washington D.C.

U.S. EPA, Office of Water (1990): Technical Guidance Manual for Performing Waste Load Allocations. Book III - Estuaries: Part 2 - Application of Estuarine Waste Load Allocation Models. 137 Pages. (EPA 823-R-92-003), Washington D.C.

U.S. EPA (1991): Development of Index of Biotic Integrity Expectations for the Ecoregions of Indiana, 1. Central Corn Belt Plain.

U.S. EPA, Region V (1991): Development of Index of Biotic Integrity Expectations for the Ecoregions of Indiana - I. Central Corn Belt Plan. 93 Pages. (EPA 905/9-91/025). [WATER QUALITY, FISH]

U.S. EPA, Environmental Research Laboratory, Office of Research and Development (1992): MICHTOX: A Mass Balance and Bioaccumulation Model for Toxic Chemicals in Lake Michigan. First Draft, July 4, 1992. [BIOACCUMULATION, LAKE MICHIGAN]

U.S. EPA (1992): Exposure and Effects of Airborne Contamination for the Great Waters Program Report. 201 pages. [ATMOSPHERE, TOXICS]

U.S. EPA, Office of Water (1992): Technical Guidance Manual for Performing Waste Load Allocations. Book III - Estuaries: Part 3 - Use of Mixing Zone Models in Estuarine Waste Load Allocations. 41 Pages. (EPA 823-R-92-004)

U.S. EPA, Office of Water (1992): Technical Guidance Manual for Performing Waste Load Allocations. Book III - Estuaries: Part 4 - Critical Review of Coastal Embayment and Estuarine Waste Load Allocation Modeling. 69 Pages. (EPA 823-R-92-005)

- U.S. EPA. (1993): Revised Draft Lake Michigan Lakewide Management Plan for Toxic Pollutants. [LAKE MICHIGAN, MANAGEMENT]
- U.S. EPA, Great Lakes National Program Office (1993): Assessment and Remediation of Contaminated Sediments (ARCS) Program - Biological and Chemical Assessment of Contaminated Great Lakes Sediment. 351 Pages. (EPA-905-R93-006). Chicago, IL. [SEDIMENTS, GREAT LAKES, BENTHOS]
- U.S. EPA, Office of Water, Water Quality Standards Branch (1993): Water Quality Standards Handbook, Second Edition. 646 Pages. (EPA 823-B-93-002). Washington D.C. [WATER QUALITY, STANDARDS, USE ATTAINABILITY, WATER QUALITY CRITERIA]
- U.S. EPA, Office of Water, Office of Science and Technology (1993): Water Quality Standards Academy: Basic Course: Participant Manual. 530 Pages. [WATER QUALITY, USE ATTAINABILITY, RISK ASSESSMENT, HEALTH, SEDIMENTS, AQUATIC LIFE]
- U.S. Fish and Wildlife. 1966. Final Fish and Wildlife Coordination Act Report for the Indiana Harbor and Ship Canal Maintenance Dredging Disposal Project at East Chicago In Lake Country, Indiana. Prepared for U.S. Army Engineer District, Chicago. 117 pp.
- Vallentyne, John R., Beeton, Alfred M. (1988): The 'Ecosystem' Approach to Managing Human Uses and Abuses of Natural Resources in the Great Lakes Basin. Environmental Conservation 15, 58-62.[ECOSYSTEM, GREAT LAKES, MANAGEMENT, WATER COLUMN]
- Virtual Elimination Task Force of the International Joint Commission (1991): Persistent Toxic Substances: Virtually Eliminating Inputs to the Great Lakes. 42 pages. [AVIAN SPECIES, DDT, DEFORMITIES, DIOXIN, FISH, GREAT LAKES, HEALTH HUMAN HEALTH, LEAD, MAMMALIAN SPECIES, MERCURY, ORGANOCHLORINE, PCB, PESTICIDE, POLLUTION, POPULATION, PROGRAM; TOXICS, WILDLIFE]
- Voldner, E.C.; Alvo, M. (1989): Estimation of Sulphur and Nitrogen Wet Deposition to the Great Lakes. Environmental Science and Technology 23, 1223-1232. [ATMOSPHERE, GREAT LAKES]
- Voldner, E.C.; Smith, L. (1991): Production, Usage, and Atmospheric Emissions of 14 Priority Toxic Chemicals. Appendix 2 of the Proceedings of the Workshop on Great Lakes Atmospheric Deposition, October 29-31, 1986. Report to the Great Lakes Water Quality, Great Lakes Science Advisory and the International Air Quality Advisory Boards of the International Joint Commission., Windsor, Ontario. 100 pages. [ATMOSPHERE, GREAT LAKES, LOADINGS, TOXICS]
- Voldner, Eva C.; Shannon, Jack D. (1992): Deposition of S and NOx Nitrogen to the Great Lakes Estimated With A Regional Deposition Model. Environmental Science and Technology (26 May), 970-978. [ATMOSPHERE, GREAT LAKES, POLLUTION, WATER COLUMN]
- Wall, Gregory J. et. al. (1989): Pollution Control in the Great Lakes Basin: an International Effort J Soil & Water Conservation 44, 12-15. [EUTROPHICATION, GREAT LAKES, MANAGEMENT, PHOSPHORUS, POLLUTION, RESTORATION, TOXICS, WATER COLUMN]

Warwick, W.F.; Casey, C.A. (1982): Sampling Chironomid Communities in Lakes National Water Resources Institute (NWRI) Publication No. W&NR 82-02, NHRI., Saskatoon, Waskatchewan. [BENTHOS, WATER COLUMN]

The Water Quality Board (1991): Cleaning up in the future. In: Cleaning up Our Great Lakes. A Report From the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 34-36. [GREAT LAKES, PROGRAM, RESTORATION, TRENDS]

The Water Quality Board (1991): Current Approach to Cleaning up the Lakes. In: Cleaning up Our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 31-33. [GREAT LAKES, PROGRAM, RESTORATION]

The Water Quality Board (1991): Exposure to and Effects of Toxic Substances. In: Cleaning Up Our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 22-26. [AVIAN SPECIES, DEFORMITIES, FISH, GREAT LAKES, HUMAN HEALTH, MAMMALIAN SPECIES, TOXICS, TRENDS, WILDLIFE]

The Water Quality Board (1991): Long term goals. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 45. [ECOSYSTEM, GREAT LAKES, HUMAN USE, TRENDS]

The Water Quality Board (1991): Polluted areas. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 21. [GREAT LAKES, POLLUTION, TOXICS, WATER COLUMN]

The Water Quality Board (1991): Sources of pollution. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 17-20. [ATMOSPHERE, GREAT LAKES, LOADINGS, POLLUTION, SEDIMENT, TOXICS, WASTE DISPOSAL, WATER COLUMN]

The Water Quality Board (1991): Toxic Substances in the Great Lakes. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the international Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 14-16. [DDT, DIOXIN, GREAT LAKES, LEAD, MERCURY; ORGANOCHLORINE, PCB, PESTICIDE, TOXICS, WATER COLUMN]

The Water Quality Board (1991): Trends in Pollution Discharges and Levels. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 29-30. [GREAT LAKES, LOADINGS, PCB, POLLUTION, TOXICS, TRENDS, WATER COLUMN]

The Water Quality Board (1991): What has been done to clean up the lakes. In: Cleaning up our Great Lakes. A Report from the Water Quality Board to the International Joint Commission on Toxic Substances in The Great Lakes Basin Ecosystem. 27-28. [GREAT LAKES, MANAGEMENT, POLLUTION]

Water Quality and Pollution Control in Michigan: 1990 Report. Michigan 305(b) Report: Volume 11. Lansing, MI. 274 Pages. [WATER QUALITY, LAKE MICHIGAN, GREAT LAKES, TOXICS, RIVERS, SEDIMENTS, AQUATIC LIFE, FISH, HEALTH]

Wells, L.;McLin, A.L. (1973): Lake Michigan: Man's Effects on Native Fish Stocks and Other Biota.Great Lakes Fish. Comm. Tech. Rep. 20., Ann Arbor, MI.[FISH, LAKE MICHIGAN]

Whyte, Robert S.; Hartig, John H.; Hopkins, Gordon J. (1990): Decreasing Chloride Trends Observed at Lake Erie Municipal Water Intakes. Journal of Great Lakes Research 16, 233-[LAKE ERIE, LOADINGS, POLLUTION, TRENDS, WATER COLUMN]

Winnell, M.H. and D.J. Jude. 1987. Benthic Community Structure and Composition Among Rocky Habitats in the Great Lakes and Keuka Lake, New York. J. Great Lakes Res. 13(1):3-17.

Wisconsin Department of Natural Resources (1990): Wisconsin Water Quality Assessment Report to Congress 1990. Section 305(b) Report. 172 pages.[EUTROPHICATION, EXOTIC SPECIES, FISH, HABITAT, HUMAN HEALTH, WATER COLUMN, WETLAND]

Wisconsin Department of Natural Resources (1992): Wisconsin Water Quality Assessment Report to Congress 1992. 244 Pages. (PUBL-WR254-92-REV) [GREAT LAKES, FISH, STREAMS, RIVERS, TOXICS, HUMAN HEALTH, SEDIMENTS, WATER QUALITY, AQUATIC LIFE, TOXICITY TESTING]

Wyte, R.S., J. H. Hartig, and G.J. Hopkins. 1990. Decreasing Chloride Trends Observed at Lake Erie Municipal Water Intakes. 16(2):233-240.

Zimmerman, A.R.B., and R.M. Owen. 1990. A Quantitative Model of the Dispersal of Detrital Inputs and Minor Compositional Components in Lake Michigan Sediments. J. Great Lakes Res. 16(3):444-456.

6

ATTACHMENT 6

LAKE MICHIGAN BIOMONITORING PROGRAM DATABASE AND SUMMARY REPORT



Lake Michigan Biomonitoring Program Database and Summary Report

Attachment 6 Volume II (Revised)

Prepared for:

**Amoco Petroleum Products Refining Business Group
Whiting Business Unit
Whiting, Indiana**

Prepared by:

**Schafer & Associates
Golden, CO
and**

**The ADVENT Group, Inc.
Brentwood, TN**

March 24, 1998

TABLE OF CONTENTS

| | |
|---|-----|
| 1.0 Introduction | 1.. |
| 2.0 Study Sites | 1.. |
| 2.1 Sample Site Selection | 2.. |
| 2.2 Physical Description of General Study Area | 2 |
| 3.0 Sediment | 3.. |
| 3.1 Sediment Collection Methods | 3.. |
| 3.2 Sediment Results | 5.. |
| 4.0 Benthos | 5.. |
| 4.1 Collection Methods | 5.. |
| 4.2 Benthos Results | 6.. |
| 5.0 Phytoplankton | 7.. |
| 5.1 Collection Methods | 7.. |
| 5.2 Phytoplankton Results | 7.. |
| 6.0 Zooplankton | 9.. |
| 6.1 Zooplankton Collection Methods | 9.. |
| 6.2 Zooplankton Results | 10 |
| 7.0 Chlorophyll a | 11 |
| 7.1 Chlorophyll a Collection Methods | 11 |
| 7.2 Chlorophyll a Results | 11 |
| 8.0 Water Chemistry | 11 |
| 8.1 Water Chemistry Collection Methods | 11 |
| 8.2 Water Chemistry Results | 11 |
| 9.0 <i>In-situ</i> Water Quality | 12 |
| 9.1 <i>In-situ</i> Water Quality Collection Methods | 12 |
| 9.2 <i>In-situ</i> Water Quality Results | 12 |
| 10.0 References | 13 |

LIST OF FIGURES

- 2-1 Calumet and Indiana Harbors, NOAA Chart 14929
- 3-1 Amoco Sediment Sampling Characterization Configuration
- 3-2a Percent Gravel in Sediment
- 3-2b Percent Sand in Sediment
- 3-2c Percent Silt in Sediment
- 3-2d Percent Clay in Sediment
- 4-1 Amoco Benthos and Sampling Sediment Configuration
- 4-2 Benthos Richness
- 4-3 Benthos Density
- 4-4 Benthos Diversity
- 5-1 Diatom Richness
- 5-2 Phytoplankton Density
- 5-3 Phytoplankton Diatom Diversity
- 5-4 Phytoplankton Distribution
- 5-5 1997 Phytoplankton Standing Crop
- 6-1 Zooplankton Richness
- 6-2 Zooplankton Density
- 7-1 Chlorophyll *a* Concentrations

LIST OF TABLES

- 1-1 Amoco NPDES Permit Reapplication Biomonitoring Support Sampling Schedule
- 4-1 Lake Michigan Benthos Summary
- 5-1 Lake Michigan Phytoplankton Summary
- 6-1 Lake Michigan Zooplankton Summary
- 7-1 Chlorophyll *a* Determination (mg/M³)
- 8-1 Lake Michigan Water Chemistry Constituents
- 9-1 *In-Situ* Water Quality Summary

APPENDICES

Appendix A Sediment Core Data

Appendix B Biological Data

Appendix C Chemical Data

1.0 INTRODUCTION

Monitoring of near-shore Lake Michigan was continued following submittal to IDEM of the NPDES Permit Renewal Application for Amoco Oil Company in August 1994. Subsequent lake studies near Amoco's proposed multi-port diffuser were conducted to document lake characteristics and provide ecological data in support of a more complete description of existing ecological conditions. Physical, chemical, and biological samples were collected and analyzed from an area proposed as the site for the NPDES multiport diffuser. This monitoring program also provides data to address application requirements recently implemented with the adoption of the Great Lakes Initiative.

The monitoring program was designed to meet the following objectives:

1. Provide new information supplemental to the Permit Renewal Application (ADVENT 1994) with respect to characteristics of Lake Michigan at the proposed location of the multiport diffuser.
2. Document the natural variability of physical, chemical, and biological attributes of southern Lake Michigan at the location of the proposed multiport diffuser.
3. Support and augment the findings presented in Volume II NPDES Permit Renewal Application Mixing Zone Demonstration (ADVENT 1994).

2.0 STUDY SITES

Two study sites were chosen to represent Lake Michigan in the region of the proposed diffuser. Site S3500 was included in Attachment 5 Bioassessment Data Summary of Volume II (ADVENT 1994) and was retained as a monitoring study site. Site C3501 was established to investigate spatial variation in physical, chemical, and biological characteristics for southern Lake Michigan in the proposed diffuser area. A general description for each study site is given below and shown on Figure 2-1.

- S3500: Located approximately 3,500 feet from Amoco Outfall 001 along a magnetically corrected compass heading of approximately 39° at Longitude W87° 28.093' and Latitude N41° 40.976'. The S3500 site area is shown on Sheet 29 of National Oceanic and Atmospheric Administration (NOAA) Recreational Chart 14926 (January 20, 1990). Geographical Positioning System (GPS) coordinates shows the distance to be 0.27 nautical miles (1,640 feet) from the Amoco intake buoy.
- C3501: Located approximately 3,500 feet from Amoco Outfall 001 along a magnetically corrected compass heading of bearing of approximately 18° at Longitude W87° 28.349' and Latitude N41° 41.149'. Sites C3501 and S3500 are separated by a distance of approximately 1,500 feet along a bearing of 311.5 from magnetic North. The site C3500 area is shown on Sheet 29 of NOAA Recreational Map 14926 (January 20, 1990).

Positioning at the sites was accomplished by visual sightings on numerous landmarks for monitoring activities during May 1995. The coordinate position for site S3500 was established using GPS during November 1995. The coordinate position for site C3501 was established

using GPS during October 1996. Measured total depth at both S3500 and C3501 were consistently between 28-30 feet.

2.1 Sample Site Selection

The locations of study sites S3500 and C3501 were selected because they met the following objectives:

- Represent a realistic location in Lake Michigan selected for installation of the proposed multiport diffuser.
- Representative of physical, chemical, and biological characteristics of the near-shore area for southern Lake Michigan west of Indiana Harbor Ship Canal.
- Are not influenced by existing discharges to or intakes from Lake Michigan.

The study site locations were selected following a study of the area, including (1) an intensive sonar survey to record bottom topography, (2) a diver-assisted visual survey to evaluate substrate homogeneity, and (3) evaluation of diver-collected sediment samples for visual inspection for homogeneity. Two study locations were identified specifically to expand the spatial scale of the data to better represent a large area of Lake Michigan.

2.2 Physical Description of General Study Area

Physical characteristics of the study site can be influenced by lake-wide patterns as well as shoreline related effects. Lake-wide currents, seasonal wind patterns, thermal convection and Coriolis forces that influence the deeper open waters of southern Lake Michigan also contribute to the physical conditions at C3501 and S3500. However, in the near shore zone (up to one mile from shore) the influence from localized storms in combination with shallow waters often greatly affect physical conditions in the study area because of the relative close proximity to the shoreline. For example, localized storms and wind currents may induce highly variable currents and turbulence in the shallow near-shore waters but have negligible effect on deeper lake-wide currents or stratification, which are influenced more by seasonal wind and storm patterns. Shoreline currents mainly follow the direction of the wind, and in the case of localized wind blowing toward the shore, the lake water will deflect to follow the shore contour (Saunders *et al.* 1976). Sites C3501 and S3500 are approximately 3,500 feet from shore in 28-30 feet of water. This region is in close proximity to the shoreline and reflects best a flooded beach. Winds and shoreline currents are likely more pronounced at the study site than for the outer near shore zone of southern Lake Michigan.

Winds and currents at the study area typically result in wave turbulence to the lake bottom and promote complete mixing throughout the water column at sites C3501 and S3500. The study site bottom is flat, with sediment dominated by small grain sand and some silt that is easily disturbed and re-suspended into the water column. Sediment material suspended in the water column have resulted in underwater visibility problems and low Secchi disk depths following periods of moderate to strong local winds. Stratification of the water column or formation of a thermocline is short lived, if present. Measurements at the study sites even during calm periods have shown uniform temperature, conductivity and dissolved oxygen profiles indicating complete mixing of the water column.

The trophic status of southern Lake Michigan has been classified as mesotrophic (Great Lakes Water Quality Board, 1977). This trophic status is intermediate between oligotrophic (clear water, low nutrient concentration, low biological productivity) and eutrophic (nutrient rich, highly productive). Measured densities and community composition for phytoplankton, zooplankton, chlorophyll *a* concentration, and water chemistry parameters from the water column at the study sites are consistent with the mesotrophic trophic status.

The benthos assemblage (organisms living on and in the sediments) is poorly developed. The uniform, sandy bottom composition and constant disturbance at the sediment surface from currents and wave action create an unstable and harsh habitat. The benthos includes midge larvae (Chironomidae), worms (Oligochaeta), snails (Mollusca), and small clams (Pelecypoda). The exotic Zebra mussel (*Dreissena polymorpha*) has been infrequently collected when the sample contains a piece of gravel or buried wood debris. The benthic organisms are subjected to continuous habitat disruption and abrasion from the bottom material and typically show a patchy distribution with low density and species richness. Ripples on the surface of the sediment that conform to the direction and velocity of induced wave action or currents are a characteristic feature of the bottom surface.

3.0 SEDIMENT

3.1 Sediment Collection Methods

Starting in November 1995, sediment samples at S3500 and C3501 were hand collected by a self-contained underwater breathing apparatus (SCUBA) diver using a coring device made of 2.5-inch-diameter by 8-inch-length (5 cm X 20 cm) polyvinyl chloride (PVC) pipe. The use of the coring device minimized loss of sampled material and maximized sampling efficiency. All samples were collected as 4-inch cores and capped underwater prior to extrusion from the bottom material.

A sampling grid was configured using depth contours and specifications for the proposed multiport diffuser mixing zone. The grid approach optimized sample collection for a maximum spatial area. The grid configuration used a benchmark point "B-0" that represented the longitudinal center of the 90-foot-long diffuser. Two 750-foot-long transects (B+ and B-) were established at right angles to the longitudinal axis of the diffuser, and a third (D+) as an extension of the diffuser axis (Figure 3-1). Sediment sample points were selected at 0, 25, 75, 125, 250, 500, and 750 feet from the center point of the diffuser (zero position being common to all three transects). Four additional 75-foot-long transects (A+, A-, C+, and C-) were established from each end of the proposed diffuser location and perpendicular to the diffuser axis. Sediment sample points were selected at 0, 25, and 75 feet from the diffuser along these four transects (site D+25 being common to zero position of the A+ and A- transects). A total of 28 sample positions were configured. Figure 3-1 shows, as an inset, the general location of S3500, the overall configuration of the sampling position matrix, and detailed sampling positions surrounding the proposed diffuser location.

For sediments, an extensive sediment characterization was conducted at S3500 during November 1995 when all 28 sample positions were used for sediment collection and analyses. A total of 72 sediment samples were collected at S3500 to evaluate sediment composition variation on three spatial scales: 0-6 inches apart, 3-6 feet apart and 25 feet apart, or greater.

Sediment samples collected to evaluate variation at 2 inches distance (5 cm) consisted of three replicate cores taken adjacent (i.e., PVC pipe touching) to each other. These adjacent cores were identified as replicates A, B, and C. Samples collected to evaluate variation on a scale of 3-6 feet apart (1.8 meters) consisted of three replicate cores (separated by approximately 3 feet each) taken at arm-length distance in random directions from the adjacent samples. These samples were identified as replicates D, E, and F. Four of 28 sample positions (A-25, B0, C+25 and B+750) were selected for collecting replicates A through F. Two replicate sediment samples collected approximately 1 meter apart were obtained at all 24 remaining sample positions shown in Figure 3-1. These samples were used to evaluate composition variability at 25 feet or greater distance, and to maximize spatial sampling for sediment composition analyses.

Statistical tests were used to independently determine significance for differences among the four intensively samples sites based on replicates A, B, and C (adjacent samples) and based on replicates D, E, and F (3-6 foot samples). Results of *t*-tests for statistical differences in mean percent composition of sand, silt, clay, and gravel between the 0-2 inch samples and the 3-6 feet samples showed the following:

1. No statistical differences were found among four sampling positions for mean percent composition of sand, silt, clay, and gravel based on sediment samples representing 6 square inches (98 cm²) from each sample location.
2. No statistical differences were found among four sampling positions for mean percent composition of sand, silt, clay, and gravel based on samples representing approximately 6 square feet (0.55 m²) from each sample location.
3. No statistical differences were observed in mean percent composition of sand, silt, clay, and gravel between samples representing 6 square inches (replicates A, B, and C) and samples representing 6 square feet (replicates D, E, and F) from four identical sample locations.
4. Sample data for replicates A through F collected from sites A-25, B0, C+25, and B+750 may be combined to represent an area of approximately 7.5×10^4 square feet to further refine the particle size composition characteristics for the sample site.

Differences in mean percent composition between the area represented by the 7.5×10^4 square foot area (24 sediment samples) and the remaining sample positions at S3500 (48 sediment samples) were evaluated using the statistical *t*-test for each of sand, silt, and clay and Wilcoxon's Rank Sum non-parametric test for gravel. Statistical test results showed no significant differences in mean percent composition for each of the particle size categories.

Based on the above findings, a description for the sediment composition was generated using the entire suite of sediment samples collected 3-6 feet apart from sites A-25, B0, C+25, and B+750, and all samples from the B- and B+ transect (34 sediment samples). Sediment samples collected from the D+ transect were not analyzed, and thus, not used to characterize the sediment composition at S3500.

The sediment survey indicated the number of sediment samples that could be reduced without loss of information due to the relative homogeneity of the sediment. However, a large spatial

area was needed to adequately characterize the benthos community assemblage. During June 1996, sediment was collected from S3500 at 75, 125, 250, 500, and 750 feet along the B+, B-, and D transects and sites A0, B0, and C0 for a total of 18 sample positions. This configuration of sites resulted in a sampling area of approximately 12.9 acres (5.2 ha) spanning a distance of 1,500 feet. This same sampling scheme of 18 sample positions was repeated at C3501 and S3500 during October 1996 and April 1997.

Sediments material from each position was completely mixed and analyzed using ASTM Method D421 (sieve method for particles 75 microns (μ) diameter and larger) and ASTM Method D422-63 (hydrometer method for silts and clays). Size determinations were based on the Wentworth-Krumbein-Udden size classification for sediment grains.

3.2 Sediment Results

Sediments from the sample sites can be described as fine-grained sand with silts that exhibit an even spatial distribution. Analyses indicated that sand-sized particles (4.74 millimeters [mm] to 0.75 mm diameter) were the dominant component of the lake bottom material. Sand particles accounted for a mean composition of 76.3 percent with an observed range from 49.1 percent to 91.0 percent. Silt particles (0.074 mm to 0.005 mm diameter) were the next most common particle size and accounted for a mean of 21.2 percent composition with a range from 7.4 to 50.3 percent. Clay particles (less than 0.005 mm diameter) were a minor component of the sediment and contributed a mean of 2.3 percent composition and ranged from less than one to 4.8 percent. Gravel-sized particles occurred intermittently and were observed in 50 of 122 sediment samples. Gravel exhibited a mean composition of less than 1 (0.25) percent, with a maximum in one sample of 11.4 percent. Depending upon the size of the gravel, a single particle could account for up to 11.4 percent composition. Figures 3-2a through 3-2d show the composition data, including the mean percent abundance value and upper and lower 95 percent confidence limits for each particle size category. The percent composition data for each sediment sample is presented in Appendix A.

Changes in overall sediment composition among the November 1995, June and October 1996, and April 1997 sampling periods were not observed for either S3500 or C3501. Spatial trends in sediment composition were not observed among the 18 sampling positions at S3500 or C3501, as well as general trends between the study sites. The sediment information supports a characterization of the study area as a large flat zone of unconsolidated sand (76%) and silt (21%) conducive to disturbed surface materials and rippled surface topography with little to no slope in 28-30 feet of water.

4.0 BENTHOS

4.1 Collection Methods

Benthos collection methods were the same as for sediment described above. Additional core samples were collected for benthos analysis from S3500 during November 1995 at positions B+75, B-75, B+250, B-250, B+750, D+75, and D+500 for macroinvertebrate analyses. These positions were selected to give a good spatial representation of the sampling area. To maximize sampling efficiency, core samples collected during June 1996, October 1996, and April 1997 and used for sediment analyses were first evaluated for benthic organisms.

The November 1995 sampling scheme was altered to include 18 sediment sample positions (Figure 4-1) in subsequent sampling periods to verify the 1995 results that indicated a highly variable and patchy distribution for the benthos. Benthic macroinvertebrate core samples were obtained from all 18 sampling positions during June 1996, which further expanded the spatial range of the benthos samples. The June 1996 benthos samples showed a highly variable and patchy distribution of benthos organisms existed at S3500. Many of the June 1996 benthos samples contained one or zero organisms, and extrapolation of low density to commonly used units, such as number of organisms per meter, would be inappropriate and likely inaccurate. To better account for the variation in patchiness for the benthos, two sediment core samples were collected approximately 1 meter apart from each of the 18 sample positions and used for benthos evaluation during October 1996 and April 1997. This sampling scheme of 36 benthos samples was conducted at C3501 and S3500. All samples were transferred from the core device to sample storage containers and preserved with up to 10 milliliters (mL) of weak (3 percent) formalin solution prior to shipment for analysis.

4.2 Benthos Results

Benthos analyses consistently indicated an assemblage of low richness, density, and diversity with a patchy spatial distribution. A total of 169 benthos core samples were analyzed. The most abundant organisms were oligochaetes (Oligochaeta) followed by snails (Gastropoda), then fingernail clams and zebra mussels (Pelycepod), and aquatic flies (Chironomidae). Leeches (Hirudinae), flatworms (Turbellaria) and amphipod crustaceans (Amphipoda) were occasionally observed. Oligochaetes accounted for 40.1 percent and snails accounted for 30.2 percent of the total organisms. Appendix B presents a taxonomic listing of observed organisms with richness, density, and measures of diversity for each benthos sample.

Organism richness was variable, but reflected an assemblage with generally low richness for benthos. Twenty-four of 169 samples had zero or one taxon present. A maximum richness of 10 taxa was recorded with a mean richness value of 3.5 taxa (Figure 4-2). The mean richness value is likely lower than actually present because many of the tubificid oligochaetes and aquatic flies were immature and identification to genus level was not possible. The maximum richness value of 10 taxa is still within a range that indicates low to moderate richness for benthos. Mature or large specimens of soft-bodied organisms, such as the oligochaetes and chironomids, were reported by the taxonomist to be rare. It is speculated that abrasion by the shifting sandy substrate resulting from wave disturbance may destroy larger soft-bodied organisms. Hard-bodied organisms, such as snails, clams, and amphipods that may be protected more from abrasion by shifting sands were observed in all sizes. The spatial relationship for richness indicated a patchy distribution with respect to the sampling grid.

Benthos density was highly variable among the samples. Benthos density was calculated as the number of organisms per cubic decimeter (organisms/dM³) because it best reflects the size of the core sample (10 centimeters [cm] deep X 6.5 cm diameter). Mean benthos density was 50 organisms/dM³ and ranged from zero to 344 organisms/dM³. Figure 4-3 depicts the mean density and the array of density values for the benthos samples. Five benthos samples, each containing an abundance of very small fingernail clams, exhibited a density in excess of 200 organisms/dM³. The spatial relationship for organism density indicated a patchy distribution with respect to the sampling grid.

Benthos assemblage diversity values indicated little diversity. Simpson's diversity values range from 1.0 for no diversity to 0.0 for maximum diversity. Simpson's Diversity values determined for each of the benthos samples ranged from 1.0 for samples with zero or one taxon present (no diversity) to 0.15 for the sample with 10 taxa. Mean Simpson's Diversity was 0.64. Shannon-Weiner Diversity values ranged from 0.0 for samples with zero organisms or one taxon present to 2.04 for the sample with 10 taxa. The mean Shannon-Weiner Diversity value was also 0.64. Simpson's Diversity values may provide a more meaningful range of density values for the benthos samples because calculation of Shannon-Weiner Diversity for assemblages that contained less than 10 taxa can be unreliable. Figure 4-4 shows the array of Simpson's Diversity values for the benthos samples.

The benthos community at C3501 and S3500 is highly variable and patchy with respect to spatial and temporal measures. With the exception of an overall increase in the total abundance of clams and snails observed during April 1997, large changes in overall benthos structure have not been observed for either S3500 or C3501. All data from November 1995 through April 1997 shows a patchy spatial distribution for benthos richness and benthos abundance during all sampling periods.

5.0 PHYTOPLANKTON

5.1 Collection Methods

A depth-integrated composite of the water column collected at position "B0" was used to obtain grab samples for phytoplankton analyses. The composite water sample was retained in a large bucket into which water was pumped from a submersible pump attached to a hose that was slowly lowered and raised from the water surface to 0.5 M above the bottom. The compositing bucket contained sufficient volume for grab samples consisting of a 1.0-liter (L) plastic bottle for phytoplankton, two 1.0-L amber plastic bottles for chlorophyll *a* analyses, and a full set of water chemistry sample bottles. The water column was again composited for replicate samples.

Three replicate phytoplankton grab samples were collected at S3500 during the May 1995, June 1996, October 1996, and April 1997 sampling periods. Three replicate phytoplankton grab samples were retained from C3501 during May 1995, October 1996, and April 1997. All samples were immediately preserved with weak Lugol's solution and properly stored until shipment for analysis.

5.2 Phytoplankton Results

The phytoplankton was moderately diverse and exhibited cell density values typical for oligotrophic to mildly mesotrophic lake conditions. Seven major groups of algae were represented and include the diatoms (Bacillariophyta), and the green algae (Chlorophyta), blue-green algae (Cyanophyta), yellow-green algae (Chrysophyta), euglenoids (Euglenophyta), dinoflagellates (Pyrrhophyta), and cryptomonads (Cryptophyta). Diatoms were the most common group, which accounted for a mean of 45 percent and range of 24 to 55 percent of total cell abundance. Among the soft algae groups (non-diatom taxa), yellow-green algae were the next most abundant with a mean of 27 percent of total cell abundance followed by a mean of 14 percent for green algae, and a mean of 8 percent for dinoflagellates. The blue-green were represented by 8 different taxa but accounted for a mean of 1.0 percent with a maximum of 5

percent of total cell abundance. A taxonomic listing for the soft algae and diatoms is presented in Appendix B. Table 5-1 presents values for minimum, maximum, and mean richness; cell density and diversity for the soft algae and diatoms; and total percent contribution for each of the major algae groups.

Richness for the soft algae ranged from 7 to 15 taxa with a mean of 10 taxa from a total of 35 taxa identified. The yellow-green algae *Dinobryon sociale* variety *americum*, the green algae complex *Chlorella/Chlorococcum humicola* and *Chlamydomonas* sp., and the dinoflagellate *Chroomonas nordstedtii* were the most abundant soft algae forms that demonstrated seasonal succession in the lake. *Dinobryon* and *Chlorella/Chlorococcum* were more abundant during spring and *Chlamydomonas* and *Chroomonas* tended to be more abundant during fall sampling periods.

Richness for the diatoms ranged from 26 to 55 taxa with a mean of 44 taxa from a total of 141 taxa identified. Diatom taxa commonly encountered include *Asterionella formosa*, *Diatoma tenuis* and the variety *elongatum*, several varieties of *Fragilaria capucina* and *Fragilaria construens*, species of the genus *Nitzschia*, *Stephanodiscus*, and *Cyclotella*. Many of the diatom taxa identified represent forms that typically occur as periphyton (attached to surfaces) that successfully persist in the water column as "tychoplankton" after detachment due to physical disturbance. Reports from project SCUBA divers of turbulence from wave action at the sediment surface, and the persistence of ripples on the lake bottom at the sampling locations attest to a constant resuspension of tychoplankton into the water column. Sediment material was always rippled and project SCUBA divers reported a shifting of surface sediment material from wave action during even the most calm sampling periods. Abundant tychoplanktonic forms observed in the samples include species from the genera *Diatoma*, *Fragilaria* and *Nitzschia*, *Synedra* and *Navicula*. Figure 5-1 shows the richness data and mean richness value for the diatom assemblage.

Total phytoplankton density ranged from 292 to 1,239 cells per milliliter (cells/mL) with a mean of 688 cells/mL. Diatoms accounted for a mean of 44.1 percent and exhibited a range of 26.3 to 55.3 percent of the total cell abundance. Figure 5-2 shows the soft algae, diatom, and total density values.

Diversity for the soft algae was moderate to low. Simpson's Diversity value ranged from 0.82 to a value of 0.19 on a scale of 1.0 for no diversity to zero for maximum diversity. The mean Simpson's Diversity value was 0.34. Shannon-Weiner Diversity values ranged from a low of 0.48 to 1.9 on a scale of zero for no diversity to a maximum of 2.71 for the highest richness observed (15 taxa) for the soft algae. It is common to focus more on the diatom assemblage diversity since this is typically the major component of the phytoplankton. The diatom assemblage exhibited much higher diversity values because of greater richness values and the large number of taxa with similar abundance. The diatom assemblage mean value for Simpson's Diversity was 0.10 with a range of 0.17 depicting the lowest diversity to 0.07 for the highest diversity. Shannon-Weiner Diversity values for the diatom assemblage ranged from 2.29 to 3.12 with a mean value of 2.83. The diatom assemblage diversity values are representative of moderate to high diversity for the number of taxa observed. Figure 5-3 depicts the Shannon-Weiner Diversity data and mean value for the diatom assemblage.

Expected seasonal patterns common to deeper waters were generally observed during the sampling period. A general successional pattern for stratified lakes show phytoplankton

numbers to increase in spring due to nutrient replenishment from spring overturn, warmer temperatures, and longer daylight hours. Diatoms tend to dominate the spring assemblage. The total phytoplankton standing crop decreases during summer but can show a relative increase for blue-green algae in late summer until fall overturn. The fall period is characterized by a second pulse in diatom biomass before a general decrease in total phytoplankton standing crop during the winter ice season. During winter dominant forms generally include chryptomonads, mobile chrysophytes, and diatoms.

The distribution of mean phytoplankton density at the sampling locations for the major algae groups by sampling period is shown in Figure 5-4. With the exception of April 1997, the phytoplankton reflected the expected seasonal biomass pattern. Phytoplankton standing crop, especially for the diatoms, is generally higher in spring and fall than during summer. Diatoms showed the highest mean density with peaks during May of 1995 (spring) and October 1996 (fall). A typical shift from *Asterionella formosa*, species of *Diatoma*, and some centric diatoms (*Cyclotella* and *Stephanodiscus* species) during spring, to some centric diatoms and *Fragilaria* species showing dominance during the fall was observed. The high standing crop of chrysophytes (yellow-green algae) common to the winter months a residual high population could be reflected in the May 1995 and June 1996 spring samples. Lower chrysophyte abundance was present in the October 1996 fall sample. Total phytoplankton biomass was low in the April 1997 spring sample. The relative contribution of the chrysophytes to the phytoplankton assemblage in April 1997 was nearly identical to the May 1995 spring collection. Green algae showed a general increase in mean cell density during the warmer sampling periods of June 1996 and October 1996. It is possible the spring maxima may have occurred prior to the April 28, 1997 sampling period. However, in the nearshore and turbulent environment of the sampling locations a typical spring maxima and summer reduction in standing crop may have been masked by localized storm conditions. Subsequent sampling of the phytoplankton at the study sites during late spring and summer of 1997 revealed a general increase in total standing crop from a mean of 390 cells/mL on April 28, 1997 through the first week of August followed by a decline in phytoplankton standing crop by early September 1997 to levels similar to April 1997 (Figure 5-5).

6.0 ZOOPLANKTON

6.1 Zooplankton Collection Methods

Zooplankton samples were collected from the "B0" position of the sampling grid by vertical net tow. A 0.5-M-diameter net of 80-micron (μ) mesh with a length-to-opening ratio of 5.1 to 1 was used for all zooplankton samples. The net was equipped with a removable 80- μ -mesh plankton bucket that concentrated the collection and allowed easy transfer to sample containers. Vertical tows were made by slowly lowering the net to approximately 0.5 M above the lake bottom and slowly raising the net to the water surface. Three replicate samples consisting of a single tow each were collected from C3501 and S3500 during May 1995, October 1996, and April 1997. Three replicate samples from S3500 were collected during June 1996. The contents of the net were washed into the plankton bucket prior to sample container transfer and preservation with 3 percent formalin solution.

6.2 Zooplankton Results

The zooplankton assemblage consisted of 14 different taxa, which included rotifers (Rotifera) and cladocera and copepods that represented the Crustacea. Zooplankton richness, diversity, and total density values were low and consistent with the oligotrophic to mildly mesotrophic lake conditions implicated by the phytoplankton. Copepods were typically most abundant and accounted for a mean of 77.2 percent and range of 2.5 to 52 percent of total zooplankton abundance. Copepods observed included *Diacyclops bicuspidatus thomasi*, *Diaptomus* sp. and *Mesocyclops edax*. Rotifers accounted for a mean of 17.9 percent with a range of 46.1 to 97.1 percent of total abundance. The most common rotifer identified was *Asplanchna herricki*. Cladocera (*Bosmina longirostris* and *Daphnia*) accounted for a mean of 4.7 percent of the total zooplankton identified with a maximum of 11.6 percent of total abundance for a single sample. Zooplankton richness and diversity were low. Mean richness was 4.5 taxa with a range of 3 to 7 taxa (Figure 6-1). Actual richness may be slightly higher because the determination of richness values included immature specimens that could not be classified. However, based on the mature specimens in the samples at the time of collection, an increase in taxa from among the immature life stages would be still reflect low richness. Appendix B lists the zooplankton taxa and abundance data for all the collections.

Zooplankton density ranged from a low of 1,648 organisms/cubic meter (organisms/M³) to a high of 7,914 organisms/M³ with a mean density of 4,098.7 organisms/M³ (Figure 6-2). The assemblage was highly variable with respect to abundance within each group among sample replicates. Total density values among replicates were usually similar although typically were higher during late summer and fall. Early summer and spring samples contained the highest number of copepod nauplii and copepodids that could not be identified to genus.

Variability in zooplankton richness and density was expected because of the many factors (currents, temperature, light, food availability, and predation) that influence zooplankton distribution and periods of reproduction. Because of the highly variable nature of zooplankton communities, especially in a physically turbulent habitat such as present at the sampling locations, the collection methods and analyses used here focus on the overall zooplankton assemblage. This approach maximizes the ability to detect composition differences at two locations at any one time.

Diversity values were determined with the inclusion immature specimens that could not be classified because it was believed the immature specimens likely represented a pulse bloom of a single taxon within the organism group. Simpson's Diversity values ranged from 0.9 to 0.29 on a scale of 1.0 for no diversity to 0.0 for maximum diversity. The mean Simpson's Diversity value for the zooplankton was 0.51. Shannon-Weiner Diversity values ranged from 0.24 depicting an assemblage with very low diversity to a value of 1.73 depicting moderate diversity for the number taxa typically represented by the zooplankton. Abundance values of nauplii copepods for all samples collected during April 1997 were well in excess of abundance values for other organisms and abundance values of nauplii observed in previous samples from the study sites. As a result, Simpson's Diversity and Shannon-Weiner Diversity values for the April 1997 zooplankton samples reflected the lowest diversity measures (Table 6.1).

7.0 CHLOROPHYLL *a*

7.1 Chlorophyll *a* Collection Methods

Chlorophyll *a* samples were obtained from a composite of the water column at position "B0" as described for phytoplankton in Section 5.0 above. To ensure that sufficient material was present for accurate chlorophyll determination, chlorophyll *a* samples consisted of two 1.0-L bottles that were combined and mixed prior to filtering and subsequent extraction for analysis.

Five replicate grab samples for chlorophyll *a* (consisting of two 1.0-L bottles each replicate) were retained for analyses during May 1995 from each of C3501 and S3500. Six replicate chlorophyll *a* samples were collected from S3500 during June 1996. Three replicate chlorophyll *a* samples were collected from C3501 and S3500 during October 1996 and April 1997. All chlorophyll *a* samples were immediately fixed with 1.0 mL of magnesium carbonate suspension and stored in the dark on ice until received by the analytical laboratory.

7.2 Chlorophyll *a* Results

Chlorophyll *a* concentrations ranged from 0.32 to 2.5 mg/M³ with a mean value of 1.0 mg/M³. The low concentration values are consistent with oligotrophic to mild mesotrophic lake conditions as indicated by the phytoplankton and water chemistry samples collected from the study sites. It is important to note the chlorophyll *a* concentrations from the study sites are expressed as mg/M³ rather than the more conventional mg/L unit of measure. Additionally, two liters of sample water per replicate were necessary to achieve a reliable analytical result. These two factors provide further evidence of the oligotrophic nature of the study sites. Table 7-1 shows the chlorophyll *a* concentration data for each study site and sampling period. A plot of the data against the mean concentration of 1.0 mg/M³ is shown in Figure 7-1.

8.0 WATER CHEMISTRY

8.1 Water Chemistry Collection Methods

Water chemistry samples were obtained from a composite of the water column at position "B0" as described for phytoplankton in Section 5.0 above. One composite water column grab sample was analyzed for water chemistry parameters at each of C3501 and S3500 during May 1995. Two replicate samples were retained for water chemistry analyses at S3500 during June 1996. Two replicate water chemistry samples were collected and averaged from C3501, and one water chemistry sample was retained for analysis from S3500 during October 1996. One water chemistry sample was collected for analysis at each of C3501 and S3500 during April 1997. Water chemistry data and the list of parameters measured for each of the samples listed above are identified in Appendix C. All water chemistry sample containers were stored in the dark on ice until received by the analytical laboratory.

8.2 Water Chemistry Results

Water chemistry parameter values determined by laboratory analyses for samples collected from the study sites are within values expected for southern Lake Michigan. Nitrogen and phosphorus related analytes exhibited some variability at concentrations near or below analytical detection limits indicating oligotrophic to mild mesotrophic nutrient conditions. A

summary table of mean, minimum, and maximum values for the analytes is presented in Table 8-1.

9.0 IN-SITU WATER QUALITY

9.1 In-situ Water Quality Collection Methods

Depth profiled water quality determinations were measured *in-situ* using a Series III Datasonde probe and transmitter (Hydrolab Inc.). Parameters included pH (s.u.), conductivity ($\mu\text{mhos/cm}$), water temperature ($^{\circ}\text{C}$), and dissolved oxygen (mg/L), which were measured at discrete levels of the water column from just above the lake bottom to the surface. Readings were taken at 3- or 5-foot intervals, depending upon surface wave height, and were measured over an average depth of 27 feet. Whenever possible, water quality determinations were made at each sample location every day monitoring activities were conducted.


9.2 In-situ Water Quality Results

Field determined water quality parameters indicate that complete mixing of the water column occurs at C3501 and S3500. Determinations of dissolved oxygen show profile of saturation or near saturation from the surface to the bottom. Differences in conductivity determinations from the surface to the bottom were absent or negligible. Temperature differences between the surface water and water at the lake sediment surface were typically less than two degrees ($^{\circ}\text{C}$) and attributable to effects of ambient air near the top of the water column. In-situ water quality measurements are presented in Appendix C. Table 9-1 is a summary of the field determined water quality and shows the mean, minimum, and maximum values by depth for each of the parameters measured.



10.0 REFERENCES

- ADVENT. 1994. *AMOCO NPDES Permit Renewal Application Volume II, Mixing Zone Demonstration*. Prepared for Amoco Oil Company, by The ADVENT Group, Inc., and Advanced Aquatic Technology Associates, Inc. August.
- Cumming, B.F., S.E. Wilson, R.I. Hall, and J.P. Smol. 1995. *Diatoms from British Columbia (Canada) Lakes and Their Relationship to Salinity, Nutrients and Other Limnological Variables*. *Bibliotheca Diatomologica*. (31):1-207.
- Great Lakes Water Quality Board. 1977. Great Lakes Water Quality Fifth Annual Report. Appendix B, Annual Report of the Surveillance Subcommittee to the Implementation Committee of the Great Lakes Water Quality Board. Whole Lake Problems, Local Area Problems. June.
- Pringle, C.M., D.S. White, C.P. Rice, and M.L. Tuchman. 1981. *The Biological Effects of Chloride and Sulfate With Special Emphasis on the Laurentian Great Lakes*. University of Michigan Great Lakes Research Division. Publication No. 20. 33pp.
- Saunders, K.D. and L.S. Van Loon. 1976. Nearshore Currents and Water Temperatures in Southwestern Lake Michigan (June – December, 1975). Water Resources Research Program, Argonne National Laboratory. ANL/WR-76-2.
- Sonzogni, W.L., P.W. Rogers, W.L. Richardson, and T.J. Monteith. 1982. Chloride pollution of the Great Lakes. *Journal of the Water Pollution Control Federation*. 55(5):513-521.
- Theriot, E., and E.F. Stoermer. 1981. Some aspects of morphological variation in *Stephanodiscus niagarae* (Bacillariophyceae species attributed to Fredrich Hustedt). *Transactions of the American Microscopical Society*. 101(4):368-374.
- Wilson, S.E., B.F. Cumming, and J.P. Smol. 1994. Diatom salinity relationships in 111 lakes from the Interior Plateau of British Columbia, Canada: The development of diatom-based modes for paleosalinity reconstructions. *Journal of Paleolimnology*. 12:197-221.

Figure 2-1
Proposed Diffuser Location (S3500) in Lake Michigan



Diffuser Detail 1" = 50'



Amoco Sediment Characterization Sampling Configuration

- Two Replicate Core Sediment Samples
- Multiple Core Sampling (6 Samples)
- Transect Line
- - - Pipeline
- Depth Contour
- ▨ Diffuser

Station numbers correspond to distance from diffuser in feet.




Figure 3-1. Amoco S3500 Sampling Site.

Figure 3-2a




Figure 3-2b




Figure 3-2c






Figure 3-2d



Diffuser Detail 1" = 50'



Station numbers correspond to distance from diffuser in feet.

Benthos and Sediment Sampling Configuration

- Sample Position
- Transect Line
- - - Pipeline
- ▨ Depth Contour
- ▨ Diffuser

Figure 4-1. Benthos and Sediment Sampling Configuration.

Benthos Richness




Figure 4-3




Figure 4-4




Figure 5-1




Figure 5-2




Figure 5-3

Phytoplankton Diatom Diversity




Figure 5-4

Phytoplankton Distribution




Figure 5-5




Figure 6-1




Figure 6-2





Figure 7-1



Tables

Table 1-1
Amoco NPDES Permit Reapplication Biomonitoring Support Sampling Schedule

| Siting Method Location | Visual Landmarks | | GPS Positioning | | | | | | | | |
|---------------------------|------------------|-------|-----------------|-------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | S3500 | C3501 | S3500 | S3500 | Nov-95 | Jun-96 | C3501 | S3500 | C3501 | S3500 | |
| Date | May-95 | | | | | | | | | | |
| Sample Type | Sampling Method | | | | | | | | | | |
| | | | | | Core sample | Core sample | Core sample | Core sample | Core sample | Core sample | Core sample |
| Benthos | Dredge sample | | | | no sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample |
| Phytoplankton | Grab sample | | | | no sample | Net sample | Net sample | Net sample | Net sample | Net sample | Net sample |
| Zooplankton | Net sample | | | | no sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample |
| Water Chemistry | Grab sample | | | | no sample | Meter | Meter | Meter | Meter | Meter | Meter |
| Hydrolab readings | Meter | | | | Core sample | Core sample | Core sample | Core sample | Core sample | Core sample | Core sample |
| Sediment Size | Dredge sample | | | | no sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample |
| Chlorophyll a | Grab sample | | | | no sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample | Grab sample |

Table 4-1
Lake Michigan Benthos Summary

| Parameter | Units | Mean | Minimum | Maximum |
|---------------------------|---------------------|------|---------|---------|
| Total Density | No./dm ³ | 50 | 0 | 344 |
| Richness | Number | 3 | 0 | 10 |
| Simpson's Diversity | Value | 0.64 | 0.15 | 0 |
| Shannon-Weiner Diversity | Value | 0.64 | 0 | 2.04 |
| Percent Oligochaetes | Percent | 50 | 0 | 100 |
| Percent Snails | Percent | 23.8 | 0 | 100 |
| Percent Clams and Mussels | Percent | 11.3 | 0 | 100 |
| Percent Chironomids | Percent | 14.5 | 0 | 100 |

Table 5-1
Lake Michigan Phytoplankton Summary

| Parameter | Units | Mean | Minimum | Maximum |
|----------------------------|--------------|-------------|----------------|----------------|
| Total Density | No./mL | 688 | 292 | 1239 |
| Soft Algae | | | | |
| Richness | Number | 10 | 7 | 15 |
| Density | No./mL | 369 | 210 | 616 |
| Simpson's Diversity | Value | 0.33 | 0.82 | 0.19 |
| Shannon-Weiner Diversity | Value | 1.47 | 0.48 | 1.9 |
| Percent Diatoms | Percent | 43.4 | 21.1 | 55.3 |
| Percent Green Algae | Percent | 14 | 2.1 | 33.8 |
| Percent Yellow-Green Algae | Percent | 27 | 5.4 | 53.7 |
| Percent Dinoflagellates | Percent | 8.3 | 0 | 23.9 |
| Percent Blue-Green Algae | Percent | 1.2 | 0 | 5.0 |
| Diatoms | | | | |
| Richness | Number | 44 | 26 | 55 |
| Density | No./mL | 319 | 82 | 654 |
| Simpson's Diversity | Value | 0.1 | 0.17 | 0.07 |
| Shannon-Weiner Diversity | Value | 2.83 | 2.29 | 3.12 |

Table 6.1
Lake Michigan Zooplankton Summary

| Parameter | Units | Mean | Minimum | Maximum |
|--------------------------|--------------------|----------|---------|---------|
| Total Density | No./M ³ | 4,098.70 | 1,648 | 7,914 |
| Richness | Number | 6.1 | 4 | 8 |
| Simpson's Diversity | Value | 5.1 | 0.9 | 0.3 |
| Shannon-Weiner Diversity | Value | 1.0 | 0.2 | 1.7 |
| Percent Rotifers | Percent | 18 | 2.6 | 51.5 |
| Percent Cladocera | Percent | 4.8 | 0.0 | 11.6 |
| Percent Copepods | Percent | 77.3 | 46.2 | 97.1 |

Table 7.1
Chlorophyll *a* Determinations (mg/M³)

| Date | May-95 | | Jun-96 | Oct-96 | | Apr-97 | |
|-------------|--------|-------|--------|--------|-------|--------|-------|
| Location | C3501 | S3500 | S3500 | C3501 | S3500 | C3501 | S3500 |
| Replicate 1 | 0.72 | 1.04 | 0.8 | 1.6 | 1.8 | 0.64 | 0.53 |
| Replicate 2 | 0.32 | 1.44 | 0.67 | 2.5 | 2.2 | 0.64 | 0.73 |
| Replicate 3 | 0.4 | 1.28 | 0.8 | 2.5 | 1.2 | 0.75 | 0.53 |
| Replicate 4 | 1.02 | 1.44 | 0.53 | none | none | none | none |
| Replicate 5 | 0.64 | 1.12 | 0.67 | none | none | none | none |
| Replicate 6 | none | none | 0.4 | none | none | none | none |

Table 8-1
Lake Michigan Water Chemistry Constituents

| Parameter | Units | Method | Mean | Min. | Max. | n Samples |
|---------------------------------|-------|----------|--------|--------|--------|-----------|
| pH | s.u. | 9040A | 7.82 | 6.90 | 8.50 | 6 |
| Total Suspended Solids (TSS) | mg/L | EPA160.2 | 1.64 | 0.90 | 3.00 | 8 |
| Total Dissolved Solids (TDS) | mg/L | EPA160.1 | 172.00 | 140.00 | 198.00 | 8 |
| Alkalinity as CaCO ₃ | mg/L | EPA310.2 | 110.00 | 110.00 | 110.00 | 2 |
| Chloride | mg/L | 2951 | 14.30 | 12.50 | 17.00 | 8 |
| Total Organic Carbon (TOC) | mg/L | EPA415.1 | 6.79 | 2.50 | 20.00 | 8 |
| Hardness as CaCO ₃ | mg/L | EPA130.2 | 150.38 | 133.00 | 160.00 | 8 |
| Total Kjeldahl Nitrogen (TKN) | mg/L | EPA351.1 | 0.77 | 0.40 | 1.90 | 6 |
| Nitrate/Nitrite | mg/L | 9200 | 0.45 | 0.09 | 1.50 | 8 |
| Total Nitrogen | mg/L | Calc. | 1.65 | 1.56 | 1.74 | 2 |
| Total Phosphorus | mg/L | EPA365.4 | 0.08 | 0.01 | 0.20 | 8 |
| Ortho-Phosphorus | mg/L | EPA365.2 | 0.06 | 0.01 | 0.20 | 8 |
| Silica | mg/L | 6010 | 0.57 | 0.38 | 0.70 | 8 |
| Sulfate | mg/L | EPA375.4 | 25.50 | 25.00 | 26.00 | 2 |
| Total Calcium | mg/L | EPA215.1 | 69.50 | 54.00 | 85.00 | 2 |
| Total Magnesium | mg/L | EPA242.1 | 12.00 | 12.00 | 12.00 | 2 |
| Total Sodium | mg/L | EPA273.1 | 7.35 | 7.00 | 7.70 | 2 |
| Total Potassium | mg/L | EPA258.1 | 1.80 | 0.30 | 3.30 | 2 |

Table 9-1
In-Situ Water Quality Summary

| Depth (ft) | Dissolved Oxygen (mg/L) | | | | Temperature (C) | | | | Conductivity (umhos/cm) | | | | pH (s.u.) | | | |
|------------|-------------------------|------|------|------------------|-----------------|------|------|-----|-------------------------|-------|------|-----|-----------|------|------|-----|
| | Min. | Mean | Max. | n = ¹ | Min. | Mean | Max. | n = | Min. | Mean | Max. | n = | Min. | Mean | Max. | n = |
| surface | 9.6 | 11.1 | 12.7 | 14 | 8.5 | 13.1 | 15.1 | 14 | 289 | 300.3 | 318 | 14 | 7.4 | 8.1 | 8.2 | 14 |
| 2 to 3 | 9.6 | 10.9 | 12.7 | 11 | 8.5 | 13.0 | 15.1 | 10 | 286 | 301.5 | 317 | 10 | 7.4 | 8.0 | 8.2 | 10 |
| 5 to 6 | 9.6 | 11.1 | 12.6 | 14 | 8.5 | 13.0 | 15.0 | 14 | 287 | 298.6 | 315 | 14 | 7.3 | 8.1 | 8.2 | 14 |
| 8 to 9 | 9.6 | 10.9 | 12.6 | 11 | 8.4 | 12.5 | 14.7 | 11 | 290 | 297.8 | 306 | 11 | 7.3 | 8.0 | 8.2 | 11 |
| 11 to 12 | 9.5 | 11.2 | 13.3 | 14 | 8.2 | 12.6 | 14.5 | 14 | 289 | 296.8 | 305 | 14 | 7.2 | 8.1 | 8.2 | 14 |
| 14 to 15 | 9.5 | 11.3 | 12.8 | 14 | 8.0 | 12.5 | 14.5 | 14 | 290 | 297.6 | 305 | 14 | 7.1 | 8.1 | 8.2 | 14 |
| 17 to 18 | 9.5 | 11.1 | 12.8 | 11 | 7.9 | 12.3 | 14.4 | 11 | 278 | 295.5 | 304 | 11 | 7.0 | 8.0 | 8.2 | 11 |
| 20 to 21 | 9.5 | 11.3 | 12.8 | 14 | 7.9 | 12.5 | 14.4 | 14 | 288 | 296.6 | 302 | 14 | 6.9 | 8.0 | 8.2 | 14 |
| 24 to 25 | 9.5 | 10.9 | 12.8 | 9 | 7.8 | 12.1 | 14.4 | 11 | 289 | 295.5 | 300 | 11 | 7.9 | 8.2 | 9.8 | 11 |
| 27 to 28 | 9.5 | 11.3 | 12.7 | 14 | 7.8 | 12.4 | 14.4 | 14 | 280 | 296.4 | 306 | 14 | 6.7 | 8.0 | 8.3 | 14 |

¹ Number of observations.

Appendix A

Sediment Core Data

Appendix A
Proposed Diffuser Site Sediment Core Data

| Date | Location | Site | Pct. Gravel | Pct. Sand | Pct. Silt | Pct. Clay |
|---------|----------|--------|-------------|-----------|-----------|-----------|
| Nov. 95 | S3500 | A-25D | 0.00 | 85.76 | 9.75 | 4.49 |
| Nov. 95 | S3500 | A-25E | 0.10 | 78.55 | 19.11 | 2.24 |
| Nov. 95 | S3500 | A-25F | 0.05 | 80.93 | 14.21 | 4.81 |
| Nov. 95 | S3500 | B+125A | 0.00 | 81.71 | 13.64 | 4.65 |
| Nov. 95 | S3500 | B+125B | 0.00 | 69.84 | 26.48 | 3.68 |
| Nov. 95 | S3500 | B+250A | 0.30 | 78.76 | 16.30 | 4.64 |
| Nov. 95 | S3500 | B+250C | 0.45 | 83.33 | 13.66 | 2.56 |
| Nov. 95 | S3500 | B+25A | 0.05 | 82.40 | 13.54 | 4.01 |
| Nov. 95 | S3500 | B+25B | 0.00 | 81.90 | 15.86 | 2.24 |
| Nov. 95 | S3500 | B+500A | 0.00 | 75.35 | 20.64 | 4.01 |
| Nov. 95 | S3500 | B+500B | 0.00 | 77.43 | 18.40 | 4.17 |
| Nov. 95 | S3500 | B+750D | 0.10 | 75.53 | 21.65 | 2.72 |
| Nov. 95 | S3500 | B+750E | 0.00 | 76.51 | 21.89 | 1.60 |
| Nov. 95 | S3500 | B+750F | 5.36 | 79.71 | 13.17 | 1.76 |
| Nov. 95 | S3500 | B+75B | 0.00 | 84.31 | 13.13 | 2.56 |
| Nov. 95 | S3500 | B+75C | 0.00 | 80.36 | 16.76 | 2.88 |
| Nov. 95 | S3500 | B-125A | 0.60 | 67.18 | 27.73 | 4.49 |
| Nov. 95 | S3500 | B-125B | 0.00 | 78.79 | 18.01 | 3.20 |
| Nov. 95 | S3500 | B-250A | 0.00 | 77.94 | 18.86 | 3.20 |
| Nov. 95 | S3500 | B-250B | 0.30 | 85.34 | 12.44 | 1.92 |
| Nov. 95 | S3500 | B-25A | 0.85 | 67.86 | 26.47 | 4.81 |
| Nov. 95 | S3500 | B-25B | 0.25 | 81.57 | 15.14 | 3.04 |
| Nov. 95 | S3500 | B-500A | 0.60 | 70.15 | 25.08 | 4.17 |
| Nov. 95 | S3500 | B-500B | 0.20 | 79.37 | 17.55 | 2.88 |
| Nov. 95 | S3500 | B-750A | 0.00 | 79.89 | 15.94 | 4.17 |
| Nov. 95 | S3500 | B-750B | 0.00 | 77.17 | 18.34 | 4.49 |
| Nov. 95 | S3500 | B-75A | 0.00 | 70.18 | 26.30 | 3.52 |
| Nov. 95 | S3500 | B-75B | 0.10 | 82.51 | 14.83 | 2.56 |
| Nov. 95 | S3500 | B0D | 0.00 | 79.59 | 17.21 | 3.20 |
| Nov. 95 | S3500 | B0E | 0.40 | 74.65 | 20.14 | 4.81 |
| Nov. 95 | S3500 | B0F | 0.05 | 84.02 | 12.73 | 3.20 |
| Nov. 95 | S3500 | C+25D | 0.05 | 78.33 | 16.94 | 4.68 |
| Nov. 95 | S3500 | C+25E | 0.80 | 78.47 | 19.13 | 1.60 |
| Nov. 95 | S3500 | C+25F | 0.00 | 72.24 | 22.95 | 4.81 |
| Jun-96 | S3500 | A0 | 11.36 | 73.26 | 12.01 | 3.37 |
| Jun-96 | S3500 | B+125 | 0.00 | 77.66 | 20.23 | 2.11 |
| Jun-96 | S3500 | B+250 | 0.98 | 68.69 | 28.35 | 1.98 |
| Jun-96 | S3500 | B+500 | 0.00 | 85.22 | 13.77 | 1.01 |
| Jun-96 | S3500 | B+75 | 0.00 | 79.47 | 17.89 | 2.64 |
| Jun-96 | S3500 | B+750 | 0.00 | 80.91 | 18.18 | 0.91 |
| Jun-96 | S3500 | B-125 | 0.45 | 80.28 | 18.37 | 0.90 |
| Jun-96 | S3500 | B-250 | 0.00 | 80.41 | 18.60 | 0.99 |
| Jun-96 | S3500 | B-500 | 0.30 | 81.57 | 15.34 | 2.79 |
| Jun-96 | S3500 | B-75 | 0.10 | 78.86 | 18.87 | 2.17 |
| Jun-96 | S3500 | B-750 | 0.00 | 81.30 | 17.50 | 1.20 |
| Jun-96 | S3500 | B0 | 0.00 | 84.44 | 14.37 | 1.19 |
| Jun-96 | S3500 | C0 | 0.00 | 75.86 | 22.29 | 1.85 |
| Jun-96 | S3500 | D+125 | 0.00 | 82.73 | 16.32 | 0.95 |

Appendix A
Proposed Diffuser Site Sediment Core Data

| Date | Location | Site | Pct. Gravel | Pct. Sand | Pct. Silt | Pct. Clay |
|---------|----------|-------|-------------|-----------|-----------|-----------|
| Jun-96 | S3500 | D+250 | 0.05 | 74.63 | 23.45 | 1.87 |
| Jun-96 | S3500 | D+500 | 0.00 | 71.11 | 27.20 | 1.69 |
| Jun-96 | S3500 | D+75 | 0.00 | 84.55 | 13.45 | 2.00 |
| Jun-96 | S3500 | D+750 | 0.00 | 77.89 | 21.26 | 0.85 |
| Oct. 96 | C3501 | A0 | 0.00 | 56.87 | 42.23 | 0.90 |
| Oct. 96 | C3501 | B+125 | 0.30 | 69.23 | 28.93 | 1.54 |
| Oct. 96 | C3501 | B+250 | 0.00 | 69.42 | 25.87 | 4.71 |
| Oct. 96 | C3501 | B+500 | 0.00 | 77.40 | 20.09 | 2.51 |
| Oct. 96 | C3501 | B+75 | 0.10 | 77.73 | 20.65 | 1.52 |
| Oct. 96 | C3501 | B+750 | 0.00 | 90.95 | 7.43 | 1.62 |
| Oct. 96 | C3501 | B-125 | 0.00 | 61.06 | 38.16 | 0.78 |
| Oct. 96 | C3501 | B-250 | 0.00 | 76.14 | 22.24 | 1.62 |
| Oct. 96 | C3501 | B-500 | 0.00 | 77.13 | 21.21 | 1.66 |
| Oct. 96 | C3501 | B-75 | 0.00 | 60.04 | 39.26 | 0.70 |
| Oct. 96 | C3501 | B-750 | 0.00 | 78.88 | 19.47 | 1.65 |
| Oct. 96 | C3501 | B0 | 0.00 | 69.09 | 29.64 | 4.27 |
| Oct. 96 | C3501 | C0 | 0.00 | 70.62 | 27.43 | 1.95 |
| Oct. 96 | C3501 | D+125 | 0.00 | 73.72 | 24.46 | 1.82 |
| Oct. 96 | C3501 | D+250 | 0.00 | 69.58 | 29.27 | 1.15 |
| Oct. 96 | C3501 | D+500 | 0.00 | 75.16 | 23.10 | 1.74 |
| Oct. 96 | C3501 | D+75 | 0.00 | 61.87 | 37.02 | 1.11 |
| Oct. 96 | C3501 | D+750 | 0.00 | 90.92 | 7.93 | 1.15 |
| Oct. 96 | S3500 | A0 | 0.40 | 71.36 | 27.88 | 0.36 |
| Oct. 96 | S3500 | B+125 | 0.00 | 68.51 | 30.83 | 0.66 |
| Oct. 96 | S3500 | B+250 | 0.00 | 72.86 | 25.73 | 1.41 |
| Oct. 96 | S3500 | B+500 | 0.25 | 71.58 | 26.17 | 2.00 |
| Oct. 96 | S3500 | B+75 | 0.00 | 75.88 | 22.11 | 2.01 |
| Oct. 96 | S3500 | B+750 | 0.50 | 74.45 | 23.42 | 1.63 |
| Oct. 96 | S3500 | B-125 | 0.00 | 75.99 | 21.91 | 2.10 |
| Oct. 96 | S3500 | B-250 | 0.00 | 75.04 | 23.62 | 1.34 |
| Oct. 96 | S3500 | B-500 | 0.10 | 73.31 | 24.49 | 2.10 |
| Oct. 96 | S3500 | B-75 | 0.00 | 77.07 | 20.61 | 2.32 |
| Oct. 96 | S3500 | B-750 | 0.00 | 75.41 | 23.08 | 1.51 |
| Oct. 96 | S3500 | B0 | 0.20 | 71.22 | 26.60 | 1.98 |
| Oct. 96 | S3500 | C0 | 0.00 | 74.84 | 22.81 | 2.35 |
| Oct. 96 | S3500 | D+125 | 0.00 | 75.41 | 22.60 | 1.99 |
| Oct. 96 | S3500 | D+250 | 0.35 | 82.40 | 16.11 | 1.14 |
| Oct. 96 | S3500 | D+500 | 0.00 | 79.57 | 17.78 | 2.65 |
| Oct. 96 | S3500 | D+75 | 0.00 | 71.97 | 25.86 | 2.17 |
| Oct. 96 | S3500 | D+750 | 0.00 | 72.77 | 25.16 | 2.07 |
| Apr-97 | C3501 | A0 | 0.10 | 77.55 | 19.83 | 2.50 |
| Apr-97 | C3501 | B+125 | 0.00 | 75.92 | 21.67 | 2.41 |
| Apr-97 | C3501 | B+250 | 0.25 | 49.08 | 50.30 | 3.36 |
| Apr-97 | C3501 | B+500 | 0.24 | 64.60 | 33.41 | 1.75 |
| Apr-97 | C3501 | B+75 | 0.00 | 74.25 | 23.44 | 2.31 |
| Apr-97 | C3501 | B+750 | 0.30 | 76.12 | 19.53 | 4.04 |
| Apr-97 | C3501 | B-125 | 0.00 | 89.28 | 9.61 | 1.11 |
| Apr-97 | C3501 | B-250 | 0.00 | 70.91 | 27.33 | 1.76 |
| Apr-97 | C3501 | B-500 | 0.00 | 72.08 | 25.02 | 2.90 |
| Apr-97 | C3501 | B-75 | 0.00 | 84.40 | 12.72 | 2.89 |

Appendix A
Proposed Diffuser Site Sediment Core Data

| Date | Location | Site | Pct. Gravel | Pct. Sand | Pct. Silt | Pct. Clay |
|--------|----------|-------|-------------|-----------|-----------|-----------|
| Apr-97 | C3501 | B-750 | 0.72 | 72.79 | 25.75 | 0.74 |
| Apr-97 | C3501 | B0 | 0.00 | 78.63 | 18.78 | 2.59 |
| Apr-97 | C3501 | C0 | 0.00 | 84.11 | 13.91 | 1.98 |
| Apr-97 | C3501 | D+125 | 0.00 | 82.16 | 16.90 | 0.94 |
| Apr-97 | C3501 | D+250 | 0.71 | 81.69 | 16.67 | 0.93 |
| Apr-97 | C3501 | D+500 | 0.00 | 66.77 | 32.60 | 0.62 |
| Apr-97 | C3501 | D+75 | 0.05 | 81.15 | 17.88 | 0.92 |
| Apr-97 | C3501 | D+750 | 0.10 | 85.50 | 11.34 | 3.06 |
| Apr-97 | S3500 | A0 | 0.10 | 84.60 | 13.30 | 2.00 |
| Apr-97 | S3500 | B+125 | 0.35 | 78.09 | 20.71 | 0.85 |
| Apr-97 | S3500 | B+250 | 0.20 | 78.49 | 20.45 | 0.85 |
| Apr-97 | S3500 | B+500 | 0.10 | 74.78 | 22.78 | 2.34 |
| Apr-97 | S3500 | B+75 | 0.00 | 72.90 | 25.62 | 1.48 |
| Apr-97 | S3500 | B+750 | 0.00 | 71.52 | 26.34 | 2.14 |
| Apr-97 | S3500 | B-125 | 0.00 | 77.15 | 20.36 | 2.49 |
| Apr-97 | S3500 | B-250 | 0.00 | 83.37 | 13.72 | 2.91 |
| Apr-97 | S3500 | B-500 | 0.05 | 72.11 | 26.39 | 1.45 |
| Apr-97 | S3500 | B-75 | 0.20 | 74.11 | 21.85 | 3.85 |
| Apr-97 | S3500 | B-750 | 0.00 | 69.75 | 28.21 | 2.04 |
| Apr-97 | S3500 | B0 | 0.25 | 82.31 | 15.55 | 1.89 |
| Apr-97 | S3500 | C0 | 0.05 | 69.64 | 27.60 | 2.71 |
| Apr-97 | S3500 | D+125 | 0.20 | 76.68 | 20.65 | 2.46 |
| Apr-97 | S3500 | D+250 | 0.55 | 72.90 | 24.32 | 2.26 |
| Apr-97 | S3500 | D+500 | 0.00 | 84.01 | 13.03 | 2.96 |
| Apr-97 | S3500 | D+75 | 0.00 | 70.89 | 27.71 | 1.40 |
| Apr-97 | S3500 | D+750 | 0.00 | 77.98 | 19.47 | 2.55 |
| | | | | | | |
| Mean | | | 0.25 | 76.29 | 21.19 | 2.32 |
| s.d. | | | 1.13 | 6.57 | 6.88 | 1.15 |
| Min | | | 0 | 49.08 | 7.43 | 0.36 |
| Max | | | 11.36 | 90.95 | 50.30 | 4.81 |
| UCL | | | 2.46 | 89.17 | 34.67 | 4.58 |
| LCL | | | -1.97 | 63.41 | 7.71 | 0.07 |

Appendix B

Biological Data

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|---|--|-------------|-------------|------------|------------|------------|------------|-------------|-------------|------------|
| Date | Nov. 95 | Nov. 95 | Nov. 95 | Nov. 95 | Nov. 95 | Nov. 95 | Nov. 95 | Nov. 95 | Jun-96 | Jun-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B+75 | B-75 | B+250 | B-250 | B+750 | D+75 | D+500 | B0 | B-75 | B-125 |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | 8 | | | | | | 4 | 10 | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | 3 | | | | | |
| <i>Chryptochironomus</i> | | | | | | | | | 5 | |
| <i>Phaenopsectra</i> | 4 | | | | | | | | | |
| <i>Polypedilum</i> | | | | | | 5 | | | | |
| Orthoclaadiinae | | | 15 | 4 | | 20 | | | | |
| <i>Corynoneura</i> | | | | | 3 | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | | | | | | | | | | |
| Tubificid immature | 32 | 24 | 30 | 32 | 42 | | | | 15 | 30 |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | 4 | | | | | | | | |
| <i>Amnicola pilsbryi</i> | | 8 | | 4 | | | 5 | 4 | | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | | | | | | | | | | |
| <i>Physella</i> | | | 5 | | | | | | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | | 4 | 5 | | | | | | | |
| <i>Valvata bicarinata</i> | | | | | | | | 4 | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | 4 | | | 3 | | | | | 5 |
| <i>Pisidium</i> | 4 | 8 | 20 | 8 | 3 | | 15 | | 5 | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | 5 | | | | |
| Total Density (no./dm³) | 40 | 60 | 75 | 48 | 54 | 30 | 20 | 12 | 35 | 35 |
| Richness | 3 | 7 | 5 | 4 | 5 | 3 | 2 | 3 | 4 | 2 |
| Simpson's Diversity | .65 | .21 | .27 | .48 | .61 | .48 | .61 | .27 | .29 | .75 |
| Shannon-Weiner Diversity | .63 | 1.71 | 1.40 | .98 | .84 | .87 | .56 | 1.10 | 1.23 | .41 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|---|--|------------|-----------|------------|------------|------------|------------|-----------|------------|-----------|
| Date | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B-250 | B-500 | B-750 | B+75 | B+125 | B+250 | B+500 | B+750 | D+75 | D+125 |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | 4 | | | | | 4 | 12 | 5 | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chrytochironomus</i> | | | | | | | | | | |
| <i>Phaenopsectra</i> | | | | 4 | | | | | | |
| <i>Polypedilum</i> | | | | | | 7 | | | | |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diametinae | | | | | | | | | | |
| Oligochaeta | | | | | | | | | | |
| Tubificid immature | 6 | 28 | 19 | 47 | 23 | 7 | 32 | | 30 | 53 |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | | | | | | | | 11 | |
| <i>Amnicola pilsbryi</i> | | | | 4 | | | | | 11 | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | | | | | | | | | | |
| <i>Physella</i> | | | | | | | | | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | | | | | | | | | 5 | |
| <i>Valvata bicarinata</i> | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | | | 4 | 28 | | | | |
| <i>Pisidium</i> | | | | | | | | | 261 | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm³) | 6 | 32 | 19 | 55 | 27 | 42 | 36 | 12 | 323 | 53 |
| Richness | 1 | 2 | 1 | 3 | 2 | 3 | 2 | 1 | 6 | 1 |
| Simpson's Diversity | 1 | .77 | 1 | .74 | .74 | .49 | .80 | 1 | .66 | 1 |
| Shannon-Weiner Diversity | 0 | .38 | 0 | .52 | .42 | .87 | .35 | 0 | .75 | 0 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|---|--|-------------|-------------|----------|-------------|------------|-------------|-------------|------------|-----------|
| Date | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Jun-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | D+250 | D+500 | D+750 | A0 | C0 | B+750a | B+750b | B+500a | B+500b | B+250a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | 3 | | | 4 | | | | | |
| Chironomini | | | | | | | | 4 | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chrytochironomus</i> | | 3 | | | | | 4 | | 4 | |
| <i>Phaenopsectra</i> | | | | | | | | | | |
| <i>Polypedilum</i> | | | | | | 4 | 8 | 8 | | |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | 4 | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | | | | | | 24 | 20 | 32 | 44 | 60 |
| Tubificid immature | 30 | 12 | 4 | | | | | | | |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | | | | | | | 16 | | |
| <i>Amnicola pilsbryi</i> | | 6 | 4 | | | | | 24 | | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | 4 | | |
| <i>Marstonia</i> | | | | | | | | | | |
| <i>Physella</i> | | | | | | | | 4 | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | | | | | 4 | | 8 | 16 | | |
| <i>Valvata bicarinata</i> | | 6 | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | | | 4 | 24 | 12 | | | |
| <i>Pisidium</i> | 6 | 3 | 4 | | | | | 12 | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm³) | 36 | 33 | 12 | 0 | 12 | 52 | 52 | 124 | 48 | 60 |
| Richness | 2 | 6 | 3 | 0 | 3 | 3 | 5 | 10 | 2 | 1 |
| Simpson's Diversity | .71 | .20 | .27 | 1 | .27 | .42 | .24 | .15 | .84 | 1 |
| Shannon-Weiner Diversity | .45 | 1.64 | 1.10 | 0 | 1.10 | .91 | 1.48 | 2.04 | .29 | 0 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B+250b | B+125a | B+125b | B+75a | B+75b | B0a | B0b | B-75a | B-75b | B-125a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | 4 | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | | 3 | | 3 | 4 | | | 3 | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | | | | 4 | | | 3 | | |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | 3 | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 21 | 15 | 28 | 18 | 32 | 9 | 16 | 9 | 15 | 24 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | | 4 | 6 | 3 | |
| Amnicola pilsbryi | | | | | | | | | 3 | |
| Bulimnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | | 6 | | | | | 32 | | | |
| Valvata bicarinata | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | | 12 | 6 | |
| Pisidium | | | | | | | | 9 | 6 | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 21 | 24 | 28 | 21 | 44 | 9 | 52 | 45 | 33 | 24 |
| Richness | 1 | 3 | 1 | 2 | 4 | 1 | 3 | 7 | 5 | 1 |
| Simpson's Diversity | 1 | .45 | 1 | .62 | .54 | 1 | .47 | .16 | .26 | 1 |
| Shannon-Weiner Diversity | 0 | .90 | 0 | .54 | .89 | 0 | .86 | 1.81 | 1.41 | 0 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B-125b | B-250a | B-250b | B-500a | B-500b | B-750a | B-750b | D+75a | D+75b | D+125a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | | | | 3 | 6 | 9 | 8 | 8 | 3 | |
| Phaenopsectra | | | | | | | | | | |
| Polypedium | 3 | | | | | 3 | 8 | | 18 | |
| Orthoclaadiinae | | | | | | 3 | 4 | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | 3 | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladus | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 12 | 20 | 40 | 15 | 60 | 27 | 44 | 24 | 39 | 36 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | 3 | | | 3 | |
| Amnicola pilsbryi | | 8 | 8 | 3 | | 12 | 8 | 8 | | 4 |
| Bulinnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | 3 | 12 | 8 | 12 | | 12 | 12 | 8 | | 8 |
| Valvata bicarinata | | | | | | | | | | |
| Pelycepod | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | | | 3 | |
| Pisidium | | 20 | | 6 | 6 | 6 | 4 | 8 | 6 | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 18 | 60 | 56 | 42 | 72 | 75 | 88 | 56 | 72 | 48 |
| Richness | 3 | 4 | 3 | 6 | 3 | 8 | 7 | 5 | 6 | 3 |
| Simpson's Diversity | .47 | .27 | .54 | .23 | 70.00 | .20 | .29 | .25 | .40 | .29 |
| Shannon-Weiner Diversity | .87 | 1.32 | .80 | 1.57 | .57 | 1.80 | 1.55 | 1.48 | 1.28 | .72 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | D+125b | D+250a | D+250b | D+500a | D+500b | D+750a | D+750b | A0a | A0b | C0a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | | | | | | | | | | 3 |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | | 15 | | | | 8 | | 4 | |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 8 | 16 | 5 | 3 | 15 | 24 | 32 | 21 | 12 | 21 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | | | | | |
| Amnicola pilsbryi | | | | 3 | | | 4 | | | |
| Bulinnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | 4 | 8 | | | 5 | | | | 4 | |
| Valvata bicarinata | | | | | | | | | | |
| Pelycepeoda | | | | | | | | | | |
| Dreissena polymorpha | | | 5 | 3 | | | | 3 | | |
| Pisidium | 4 | 8 | 5 | 6 | 5 | | | 3 | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 16 | 32 | 30 | 15 | 25 | 24 | 44 | 27 | 20 | 24 |
| Richness | 3 | 3 | 4 | 4 | 3 | 1 | 3 | 3 | 3 | 2 |
| Simpson's Diversity | .44 | .35 | .31 | .23 | .42 | 1 | .56 | .62 | .41 | .77 |
| Shannon-Weiner Diversity | .86 | 1.04 | 1.24 | 1.33 | .95 | 0 | .26 | .68 | .95 | .38 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | S3500 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | C0b | B+750a | B+750b | B+500a | B+500b | B+250a | B+250b | B+125a | B+125b | B+75a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chryptochironomus</i> | | | | 4 | | 3 | | | | |
| <i>Phaenopsectra</i> | | | | | | | | | | |
| <i>Polypedilum</i> | | | | 12 | 4 | 3 | | | | |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 28 | | | 32 | 36 | 24 | 24 | 15 | 24 | 40 |
| Tubificid immature | | | | | | | | | | |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | | | | | | | | | |
| <i>Amnicola pilsbryi</i> | | | | | | | | 3 | | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | | | | | | | | | | |
| <i>Physella</i> | | | | | | | | | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | 16 | | | 4 | | | | 6 | | |
| <i>Valvata bicarinata</i> | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | | | | | | | | 4 |
| <i>Pisidium</i> | 8 | | | | | | | | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm ³) | 52 | 0 | 0 | 52 | 40 | 30 | 24 | 24 | 24 | 44 |
| Richness | 3 | 0 | 0 | 4 | 2 | 3 | 1 | 3 | 1 | 2 |
| Simpson's Diversity | .40 | 1 | 1 | .43 | .82 | .65 | 1 | .45 | 1 | .83 |
| Shannon-Weiner Diversity | .98 | 0 | 0 | 1.03 | .33 | .64 | 0 | .90 | 0 | .30 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | B+75b | B0a | B0b | B-75a | B-75b | B-125a | B-125b | B-250a | B-250b | B-500a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | 4 | | | | | | | | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | 5 | | | | 4 | | | 8 | 3 |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 16 | 10 | 28 | 44 | 48 | 52 | 28 | 52 | 36 | 27 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | | | | | |
| Amnicola pilsbryi | | 10 | 4 | | | | | | | 6 |
| Bulimnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | | 5 | | 4 | | 4 | | | | |
| Valvata bicarinata | | | | | | | | | | |
| Pelycepeoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | 8 | | | | |
| Pisidium | | | | | | | | 4 | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 20 | 30 | 32 | 48 | 48 | 68 | 28 | 56 | 44 | 36 |
| Richness | 2 | 4 | 2 | 2 | 1 | 4 | 1 | 2 | 2 | 3 |
| Simpson's Diversity | .66 | .25 | .77 | .84 | 1 | .60 | 1 | .86 | .70 | .59 |
| Shannon-Weiner Diversity | .50 | 1.33 | .38 | .29 | 0 | .79 | 0 | .26 | .47 | .72 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | B-500b | B-750a | B-750b | D+75a | D+75b | D+125a | D+125b | D+250a | D+250b | D+500a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chrytochironomus | | | | 3 | 3 | | | | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | 5 | 4 | | | | 4 | | 3 | |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 24 | 20 | 28 | 36 | 18 | 28 | 16 | 20 | 12 | 21 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | 8 | | | | 4 | | | |
| Amnicola pilsbryi | | | 4 | | | | | | 9 | |
| Bulinnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | 3 | |
| Radix | | | | | | | | | | |
| Valvata | | | 8 | | | | | 10 | 12 | 9 |
| Valvata bicarinata | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| Dreissena polymorpha | | | 4 | | | | | | | |
| Pisidium | | | | | | | | | | 3 |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 24 | 25 | 56 | 39 | 21 | 28 | 24 | 30 | 39 | 33 |
| Richness | 1 | 2 | 6 | 2 | 2 | 1 | 3 | 2 | 5 | 3 |
| Simpson's Diversity | 1 | .67 | .29 | .85 | .85 | 1 | .49 | .54 | .23 | .47 |
| Shannon-Weiner Diversity | 0 | .50 | 1.47 | .27 | .27 | 0 | .87 | .64 | 1.46 | .86 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| | Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Apr-97 | Apr-97 |
| | Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | S3500 | S3500 |
| | Site | D+500b | D+750a | D+750b | A0a | A0b | C0a | C0b | B+750a | B+750b |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chrytochironomus | | | | | | | | 4 | 6 | 3 |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | 20 | 12 | | 6 | | | | 4 | 6 |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | 4 | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | | 28 | 44 | 24 | 42 | 12 | 9 | 12 | 20 | 24 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | | | | 4 | 6 |
| Amnicola pilsbryi | | | | 4 | | | | | 4 | 6 |
| Bulimnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | 4 | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | | 4 | | | | | | | 32 | |
| Valvata bicarinata | | | | | | | | | | |
| Pelycepeoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | | | | |
| Pisidium | | | | | | | | 4 | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | | 52 | 56 | 28 | 48 | 12 | 9 | 20 | 72 | 48 |
| Richness | | 3 | 2 | 2 | 2 | 1 | 1 | 3 | 7 | 5 |
| Simpson's Diversity | | .43 | .66 | .75 | .78 | 1 | 1 | .41 | .28 | .30 |
| Shannon-Weiner Diversity | | .90 | .52 | .41 | .38 | 0 | 0 | .95 | 1.52 | 1.39 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B+500b | B+250a | B+250b | B+125a | B+125b | B+75a | B+75b | B0a | B0b | B-75a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chryptochironomus</i> | | | | | | | 4 | | | 4 |
| <i>Phaenopsectra</i> | | | | | | | | | | |
| <i>Polypedilum</i> | 3 | | 8 | | | 8 | 4 | | 5 | 16 |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | 5 | |
| Oligochaeta | | 12 | 12 | 8 | 8 | 8 | 16 | 30 | 5 | 8 |
| Tubificid immature | | | | | | | | | | |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | | 72 | 48 | 12 | | | | | |
| <i>Amnicola pilsbryi</i> | 3 | 12 | 8 | 40 | 4 | | 8 | 5 | | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | | 8 | | 8 | 8 | 4 | | | | |
| <i>Physella</i> | | | | 92 | | | | | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | 3 | 24 | 80 | 24 | 4 | 8 | 32 | 15 | | 4 |
| <i>Valvata bicarinata</i> | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | 4 | | | | | | | |
| <i>Pisidium</i> | | 12 | 48 | 80 | 40 | 4 | 4 | | | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm ³) | 9 | 68 | 232 | 300 | 76 | 32 | 68 | 50 | 15 | 32 |
| Richness | 3 | 5 | 7 | 7 | 6 | 5 | 6 | 3 | 3 | 4 |
| Simpson's Diversity | .25 | .22 | .26 | .21 | .32 | .19 | .29 | .49 | .29 | .32 |
| Shannon-Weiner Diversity | 1.10 | 1.54 | 1.51 | 1.67 | 1.41 | 1.56 | 1.45 | .90 | 1.10 | 1.21 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | B-75b | B-125a | B-125b | B-250a | B-250b | B-500a | B-500b | B-750a | B-750b | D+75a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | 4 | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | | | | 5 | | | | | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | | 9 | 10 | 4 | 10 | 5 | 4 | 3 | 10 |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 16 | 12 | 24 | 15 | 8 | 25 | 10 | 12 | 6 | 5 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | | | | | 4 | 6 | |
| Amnicola pilsbryi | 36 | 4 | 6 | 5 | 4 | | | 4 | 6 | |
| Bulinnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | | | | | | | | |
| Physella | 4 | | | | | | | | | |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | 20 | 16 | 6 | 5 | 4 | 10 | 5 | 12 | 27 | |
| Valvata bicarinata | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | | 4 | 3 | |
| Pisidium | | | | | | | | | 12 | 5 |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 76 | 32 | 45 | 40 | 20 | 45 | 20 | 44 | 63 | 20 |
| Richness | 4 | 3 | 4 | 5 | 4 | 3 | 3 | 7 | 7 | 3 |
| Simpson's Diversity | .33 | .39 | .35 | .23 | .24 | .39 | .34 | .17 | .24 | .34 |
| Shannon-Weiner Diversity | 1.19 | .97 | 1.19 | 1.49 | 1.33 | 1.00 | 1.04 | 1.80 | 1.64 | 1.10 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Site | D+75b | D+125a | D+125b | D+250a | D+250b | D+500a | D+500b | D+750a | D+750b | A0a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | | | 5 | | | | | 5 | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | | 8 | 5 | | 5 | 5 | | 25 | | |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | | |
| Zalutschia | | | | | | | | 5 | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | | 12 | 10 | 4 | 25 | 25 | 12 | 30 | | 5 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | 4 | | | | | | 35 |
| Amnicola pilsbryi | | | 5 | | | | | 10 | | |
| Bulinnea | | | | | | | | | | 5 |
| Fossaria | | | | | | | | | | |
| Marstonia | | 8 | | 4 | | | | | 4 | 5 |
| Physella | | 4 | | | | | | | | 10 |
| Pleurocera | | | | | | | | | | |
| Radix | | | | | | | | | | |
| Valvata | 5 | 16 | 20 | 12 | 5 | | | 20 | | 80 |
| Valvata bicarinata | | | | | | | | | | |
| Pelycepeoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | | 5 | | |
| Pisidium | | 4 | 10 | | | | | 10 | 4 | 60 |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 5 | 52 | 55 | 24 | 35 | 30 | 12 | 110 | 8 | 200 |
| Richness | 1 | 6 | 6 | 4 | 3 | 2 | 1 | 8 | 2 | 7 |
| Simpson's Diversity | 1 | .19 | .21 | .30 | .54 | .71 | 1 | .17 | .43 | .28 |
| Shannon-Weiner Diversity | 0 | 1.67 | 1.64 | 1.24 | .80 | .45 | 0 | 1.86 | .69 | 1.46 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | S3500 | S3500 | S3500 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | A0b | C0a | C0b | B+750a | B+750b | B+500a | B+500b | B+250a | B+250b | B+125a | B+125a |
| Chironomidae | | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | | |
| Chironomini | | | | | | | | | | | |
| Chironomus | | | | | | | | | | | |
| Chryptochironomus | | | | | | | | | | | |
| Phaenopsectra | | | | | | | | | | | |
| Polypedilum | | | 8 | 4 | | | 12 | | | | 20 |
| Orthoclaadiinae | | | | | | | | | 5 | | |
| Corynoneura | | | | | | | | | | | |
| Diplocladius | | | | | | | | | | | |
| Nanocladus | | | | | | | | | | | |
| Orthocladus | | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | | |
| Stilocladus | | | | | | | | | | | |
| Zelutschia | | | | | | | | | | | |
| Diamesinae | | | | | | | | | | | |
| Oligochaeta | 32 | 10 | 4 | 12 | 4 | | 24 | 5 | 5 | | 36 |
| Tubificid immature | | | | | | | | | | | |
| Potomothrix | | | | | | | | | | | |
| Naididae | | | | | | | | | | | |
| Piquetiella | | | | | | | | | | | |
| Hirudinae | | | | | | | | | | | |
| Marvinmeyeria | | | | | | | | | | | |
| Gastropoda | | | | | | | | | | | |
| Pseudosuccinea | 40 | | | 4 | | | | 5 | | | |
| Amnicola pilsbryi | 4 | | 20 | 8 | | | 12 | | | | |
| Bulinnea | 8 | | | | | | | | | | |
| Fossaria | | | | | | | | | | | |
| Marstonia | 8 | | | | | | | | | | |
| Physella | 8 | | | | | | | 5 | | | |
| Pleurocera | | | | | | | | | | | |
| Radix | 4 | | | | | | | | | | |
| Valvata | 80 | 15 | 4 | 32 | 4 | 3 | 16 | 10 | 10 | | 8 |
| Valvata bicarinata | | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | | |
| Dreissena polymorpha | | | | | | 3 | 32 | | | | |
| Pisidium | 160 | | 8 | | | | 8 | 5 | | | |
| Turbellaria | | | | | | | | | | | |
| Amphipoda | | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | | |
| Total Density (no./dm ³) | 344 | 25 | 44 | 60 | 8 | 6 | 104 | 30 | 20 | | 64 |
| Richness | 9 | 2 | 5 | 5 | 2 | 2 | 6 | 5 | 3 | | 3 |
| Simpson's Diversity | .29 | .50 | .27 | .34 | .43 | .40 | .20 | .20 | .34 | | .42 |
| Shannon-Weiner Diversity | 1.53 | .67 | 1.41 | 1.29 | .69 | .69 | 1.68 | 1.56 | 1.10 | | .95 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | B+125b | B+75a | B+75b | B0a | B0b | B-75a | B-75b | B-125a | B-125b | B-250a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chryptochironomus</i> | | 4 | | | | | | | | 8 |
| <i>Phaenopsectra</i> | | | | | | | | | | |
| <i>Polypedilum</i> | 5 | 4 | | 10 | | | | | | |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | 10 | 16 | 35 | 20 | | 5 | 10 | | 14 | 8 |
| Tubificid immature | | | | | | | | | | |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | 5 | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | | | | | | | | | | |
| <i>Amnicola pilsbryi</i> | | | 5 | | | | | | | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | | | | 5 | 20 | | | | | |
| <i>Physella</i> | | | | | | | | | | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | 5 | | 5 | | | 15 | 5 | | | 4 |
| <i>Valvata bicarinata</i> | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | | 20 | | | 5 | 5 | | |
| <i>Pisidium</i> | | | 10 | 5 | | 5 | | 10 | | 8 |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm ³) | 20 | 24 | 55 | 60 | 25 | 25 | 20 | 15 | 14 | 28 |
| Richness | 3 | 3 | 4 | 5 | 2 | 3 | 3 | 2 | 1 | 4 |
| Simpson's Diversity | .34 | .48 | .39 | .25 | .67 | .42 | .34 | .52 | 1 | .24 |
| Shannon-Weiner Diversity | 1.04 | .87 | 1.10 | 1.45 | .50 | .95 | 1.04 | .64 | 0 | 1.35 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Site | B-250b | B-500a | B-500b | B-750a | B-750b | D+75a | D+75b | D+125a | D+125b | D+250a |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| Chironomus | | | | | | | | | | |
| Chryptochironomus | 10 | | | | | | 5 | 5 | | |
| Phaenopsectra | | | | | | | | | | |
| Polypedilum | 15 | 5 | | 25 | 20 | 4 | 10 | 15 | | 12 |
| Orthoclaadiinae | | | | | | | | | | |
| Corynoneura | | | | | | | | | | |
| Diplocladius | | | | | | | | | | |
| Nanocladus | | | | | | | | | | |
| Orthocladus | | | | | | | | | | |
| Psectrocladius | | | | | | | | | | |
| Stilocladius | | | | | | | | | 5 | |
| Zalutschia | | | | | | | | | | |
| Diamesinae | | | | | | | | | | 4 |
| Oligochaeta | 5 | 5 | | 5 | 20 | 12 | 15 | 10 | 5 | 8 |
| Tubificid immature | | | | | | | | | | |
| Potomothrix | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| Piquetiella | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| Marvinmeyeria | | | | | | 4 | | | | |
| Gastropoda | | | | | | | | | | |
| Pseudosuccinea | | | | 5 | 15 | | | 5 | | |
| Amnicola pilsbryi | | | | 10 | 10 | | | | 10 | 4 |
| Bulinnea | | | | | | | | | | |
| Fossaria | | | | | | | | | | |
| Marstonia | | | 5 | | | | | | | |
| Physella | | | | | | | | | | |
| Pleurocera | | | | | 5 | | | | | |
| Radix | | | | | | | | | | |
| Valvata | 5 | 5 | 10 | 20 | 20 | | | 5 | | 4 |
| Valvata bicarinata | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| Dreissena polymorpha | | | | | | | 5 | | 5 | |
| Pisidium | | | | 10 | 20 | | | | 15 | 4 |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| Pontoporeia hoyi | | | | | | | | | | |
| Total Density (no./dm ³) | 35 | 15 | 15 | 75 | 110 | 20 | 35 | 40 | 40 | 36 |
| Richness | 4 | 3 | 2 | 6 | 7 | 3 | 4 | 5 | 5 | 6 |
| Simpson's Diversity | .26 | .29 | .52 | .22 | .16 | .41 | .29 | .23 | .23 | .19 |
| Shannon-Weiner Diversity | 1.28 | 1.10 | .64 | 1.62 | 1.87 | .95 | 1.28 | 1.49 | 1.49 | 1.67 |

Appendix B
Proposed Diffuser Site Benthos Data

| | Number of Benthos Organisms per Cubic Decimeter (dm ³) | | | | | | | | | |
|--------------------------------------|--|--------|--------|--------|--------|--------|--------|--------|--------|--|
| Date | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | |
| Site | D+250b | D+500a | D+500b | D+750a | D+750b | A0a | A0b | C0a | C0b | |
| Chironomidae | | | | | | | | | | |
| Chironomidae immature | | | | | | | | | | |
| Chironomini | | | | | | | | | | |
| <i>Chironomus</i> | | | | | | | | | | |
| <i>Chrytochironomus</i> | | 5 | | | 5 | | 5 | | | |
| <i>Phaenopsectra</i> | | | | | | | | | | |
| <i>Polypedilum</i> | | 15 | 12 | 6 | | 4 | 5 | 5 | 10 | |
| Orthoclaadiinae | | | | | | | | | | |
| <i>Corynoneura</i> | | | | | | | | | | |
| <i>Diplocladius</i> | | | | | | | | | | |
| <i>Nanocladus</i> | | | | | | | | | | |
| <i>Orthocladus</i> | | | | | | | | | | |
| <i>Psectrocladius</i> | | | | | | | | | | |
| <i>Stilocladus</i> | | | | | | | 5 | | | |
| <i>Zalutschia</i> | | | | | | | | | | |
| Diamesinae | | | | | | | | | | |
| Oligochaeta | | 15 | 3 | 6 | 5 | 4 | 10 | 10 | 35 | |
| Tubificid immature | | | | | | | | | | |
| <i>Potomothrix</i> | | | | | | | | | | |
| Naididae | | | | | | | | | | |
| <i>Piquetiella</i> | | | | | | | | | | |
| Hirudinae | | | | | | | | | | |
| <i>Marvinmeyeria</i> | | | | | | | | | | |
| Gastropoda | | | | | | | | | | |
| <i>Pseudosuccinea</i> | 18 | | | | | | | | 25 | |
| <i>Amnicola pilsbryi</i> | 18 | | | | 5 | | | | 45 | |
| <i>Bulinnea</i> | | | | | | | | | | |
| <i>Fossaria</i> | | | | | | | | | | |
| <i>Marstonia</i> | 6 | | | | | | | | 10 | |
| <i>Physella</i> | | | | | | | | | 5 | |
| <i>Pleurocera</i> | | | | | | | | | | |
| <i>Radix</i> | | | | | | | | | | |
| <i>Valvata</i> | 60 | 5 | 9 | 24 | 15 | 4 | 5 | 10 | 50 | |
| <i>Valvata bicarinata</i> | | | | | | | | | | |
| Pelyceopoda | | | | | | | | | | |
| <i>Dreissena polymorpha</i> | | | | | | | | | | |
| <i>Pisidium</i> | 18 | | | 6 | | | | 10 | 100 | |
| Turbellaria | | | | | | | | | | |
| Amphipoda | | | | | | | | | | |
| <i>Pontoporeia hoyi</i> | | | | | | | | | | |
| Total Density (no./dm ³) | 120 | 40 | 24 | 42 | 30 | 12 | 30 | 35 | 280 | |
| Richness | 5 | 4 | 3 | 4 | 4 | 3 | 5 | 4 | 8 | |
| Simpson's Diversity | .31 | .29 | .38 | .37 | .31 | .27 | .20 | .24 | .21 | |
| Shannon-Weiner Diversity | 1.35 | 1.26 | .97 | 1.15 | 1.24 | 1.10 | 1.56 | 1.35 | 1.75 | |

Appendix B
Proposed Diffuser Site Zooplankton Data

| | Number of Zooplankton per Cubic Meter (No./M ³) | | | | | | | | | | | |
|--|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | Date | May-95 | May-95 | May-95 | May-95 | May-95 | May-95 | Jun-96 | Jun-96 | Jun-96 | Oct-96 | Oct-96 |
| Location | | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 |
| Rotifera | | 1726 | 2474 | 1540 | 588 | 629 | 400 | | | | | |
| <i>Ascomorpha ovalis</i> | | | | | | | | | | | | |
| <i>Asplanchna priodonta</i> | | | | | | | | | | | | |
| <i>Asplanchna herricki</i> | | | | | | | | 1218 | 1654 | 1231 | | |
| <i>Karatella cochlearis</i> | | | | | | | | | | | 6 | |
| <i>Karatella crassa</i> | | | | | | | | | | | | 9 |
| <i>Karatella longispina</i> | | | | | | | | | | | | |
| <i>Ploesoma truncatum</i> | | | | | | | | | | | | |
| <i>Polyarthra</i> | | | | | | | | | | | 211 | 307 |
| Crustacea | | | | | | | | | | | | |
| Cladocera | | 66 | 112 | 145 | 63 | 218 | 248 | | | | | |
| <i>Bosmina longirostris</i> | | | | | | | | 26 | | 13 | 508 | 567 |
| <i>Daphnia</i> | | | | | | | | | | | | |
| <i>Microcyclops varicans rubellus</i> | | | | | | | | 77 | 173 | 231 | | |
| Copepoda | | 21 | 33 | 12 | 11 | 30 | 19 | | | | | |
| <i>Diacyclops bicuspidatus thomasi</i> | | | | | | | | | | | 483 | 697 |
| <i>Diaptomus</i> | | | | | | | | 667 | 1808 | 1065 | 2693 | 3409 |
| <i>Mesocyclops edax</i> | | | | | | | | | | | 19 | 19 |
| Copepodids | | 1115 | 1412 | 1099 | 696 | 1173 | 799 | 179 | | 114 | | |
| Nauplii | | 487 | 772 | 578 | 422 | 540 | 666 | 2038 | 1058 | 526 | 539 | 957 |
| Total Density (no./cu. M) | | 3416 | 4803 | 3374 | 1780 | 2590 | 2131 | 4205 | 4693 | 3180 | 4459 | 5965 |
| Richness | | 3 | 3 | 3 | 3 | 3 | 3 | 4 | 3 | 4 | 6 | 6 |
| Simpson's Diversity | | 0.38 | 0.38 | 0.35 | 0.32 | 0.31 | 0.29 | 0.35 | 0.32 | 0.3 | 0.41 | 0.38 |
| Shannon-Weiner Diversity | | 1.09 | 1.11 | 1.18 | 1.22 | 1.29 | 1.34 | 1.24 | 1.19 | 1.36 | 1.22 | 1.27 |
| | | | | | | | | | | | | |
| | Date | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 | |
| Location | | C3501 | S3500 | S3500 | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | |
| Rotifera | | | | | | | | | | | | |
| <i>Ascomorpha ovalis</i> | | | | | | 26 | | 33 | 44 | 48 | 37 | |
| <i>Asplanchna priodonta</i> | | | | | | 70 | 73 | 16 | 18 | 88 | 19 | |
| <i>Asplanchna herricki</i> | | | | | | | | | | | | |
| <i>Karatella cochlearis</i> | | | 9 | | | 9 | | | | | | |
| <i>Karatella crassa</i> | | 9 | | | | | | | 44 | | | |
| <i>Karatella longispina</i> | | | | | | | | | | | | |
| <i>Ploesoma truncatum</i> | | | | | | | | 8 | | 16 | 19 | |
| <i>Polyarthra</i> | | 437 | 297 | 223 | 266 | 9 | | | 9 | | 28 | |
| Crustacea | | | | | | | | | | | | |
| Cladocera | | | | | | | | | | | | |
| <i>Bosmina longirostris</i> | | 325 | 604 | 455 | 415 | 35 | 21 | 24 | 18 | 8 | | |
| <i>Daphnia</i> | | | | | | | | 8 | | | | |
| <i>Microcyclops varicans rubellus</i> | | | | | | | | | | | | |
| Copepoda | | | | | | | | | | | | |
| <i>Diacyclops bicuspidatus thomasi</i> | | 362 | 1161 | 994 | 994 | | | | | | | |
| <i>Diaptomus</i> | | 2619 | 5006 | 3873 | 3873 | 150 | 42 | 49 | 88 | 120 | 65 | |
| <i>Mesocyclops edax</i> | | | 19 | 9 | | | | | | | | |
| Copepodids | | | 56 | 93 | 93 | 18 | | 8 | 9 | 32 | 19 | |
| Nauplii | | 446 | 762 | 734 | 734 | 3507 | 2681 | 1502 | 4123 | 5235 | 2233 | |
| Total Density (no./cu. M) | | 4198 | 7914 | 6381 | 6375 | 3824 | 2817 | 1648 | 4353 | 5547 | 2420 | |
| Richness | | 5 | 7 | 6 | 5 | 6 | 3 | 6 | 6 | 5 | 5 | |
| Simpson's Diversity | | 0.42 | 0.44 | 0.41 | 0.41 | 0.84 | 0.9 | 0.83 | 0.89 | 0.89 | 0.85 | |
| Shannon-Weiner Diversity | | 1.19 | 1.73 | 1.22 | 1.21 | 0.41 | 0.24 | 0.45 | 0.29 | 0.3 | 0.4 | |

Appendix B
Proposed Diffuser Site Phytoplankton Data

| Taxa | Date | Number of Cells per milliliter (No./mL) | | | | | | | |
|---|------|---|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | | May-95 | May-95 | May-95 | May-95 | May-95 | May-95 | Jun-95 | Jun-95 |
| Location | | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 |
| Chlorophyta | | | | | | | | | |
| <i>Actinastrum hantzschii</i> Lagerheim | | | | | | | | | |
| <i>Ankistrodesmus braunii</i> (Naeg.) Brunthaller | | | | | | | | 5 | 7 |
| <i>Chlamydomonas globosa</i> Snow | | 18 | 12 | 6 | 35 | 44 | 25 | | |
| <i>Chlamydomonas</i> sp. Ehrenberg | | | | | | 13 | 18 | 54 | 43 |
| <i>Chlorella/Chlorococcum humicola</i> (Naeg.) Rabenhorst | | 30 | 23 | 7 | 16 | 18 | 45 | 60 | 84 |
| <i>Cosmarium</i> sp. Corda | | | | | | | | 3 | 1 |
| <i>Elakatothrix viridis</i> (Snow) Printz | | | | | | | | | |
| <i>Golenkinia paucispina</i> West & West | | | | 0.5 | | 1 | | 19 | 12 |
| <i>Pediastrum boryanum</i> (Turp.) Meneghini | | | | | | | | | |
| <i>Pediastrum simplex</i> (Meyen) Lemmermann | | | | | | | | | |
| <i>Scenedesmus bijuga</i> (Turp.) Lagerheim | | | | | | | | 1 | |
| <i>Scenedesmus brasiliensis</i> Bohlin | | | | | | | | | |
| <i>Scenedesmus quadricauda</i> (Turp.) deBrebisson | | | | | | | | 4 | |
| <i>Scenedesmus</i> sp. Meyen | | | | | | | | | |
| <i>Selenastrum minutum</i> (Naeg.) Collins | | | | | | | | 37 | 28 |
| <i>Selenastrum westii</i> G.M. Smith | | | | | | | | | |
| <i>Sphaerocystis Schroeteri</i> Chodat | | | 35 | | | | | | |
| Unknown green spheres | | | | | | | | | |
| Cyanophyta | | | | | | | | | |
| <i>Agmenellum tenuissimum</i> Lemmermann | | | | | | | | | |
| <i>Aphanocapsa delicatissima</i> West & West | | | 35 | | 10 | | | | |
| <i>Chroococcus limneticus</i> Lemmermann | | | | | | 4 | 1 | | |
| <i>Chroococcus minor</i> (Kuetz.) Naegeli | | 7 | | | 4 | 8 | | 10 | 7 |
| <i>Gomphosphaeria lacustris</i> | | | | 0.5 | 1 | | 3 | | |
| <i>Microcystis aeruginosa</i> Kuetz. amend Elenkin | | | | | | | | 1 | 3 |
| <i>Microcystis incerta</i> Lemmermann | | | | | 8 | 11 | | | |
| <i>Oscillatoria limnetica</i> Vaucher | | | 18 | | | | | 2 | |
| Chrysophyta | | | | | | | | | |
| <i>Cladomonas fruticulosa</i> Stein | | 35 | | | 10 | | | 4 | |
| <i>Dinobryon cylindricum</i> Imhoff ex. Ahlstrom | | | | | | | | 19 | 18 |
| <i>Dinobryon sociale</i> var. <i>americum</i> (Brunn.) Bachmann | | 320 | 359 | 336 | 465 | 314 | 420 | 194 | 91 |
| <i>Mallomonas caudata</i> Iwanoff | | 14 | 16 | 5 | 41 | 37 | 20 | 10 | 15 |
| <i>Mallomonas</i> sp. Perty | | | | | | | | | |
| Pyrrhophyta | | | | | | | | | |
| <i>Chroomonas nordstedtii</i> Hansgirg | | | | | | | | | |
| <i>Glenodinium pulvisculum</i> (Ehr.) Stein | | | | | | | | | 1 |
| Cryptophyta | | | | | | | | | |
| <i>Cryptomonas erosa</i> Ehrenberg | | 23 | 32 | 9 | 23 | 37 | 52 | | |
| Euglenophyta | | | | | | | | | |
| <i>Euglena</i> Ehrenberg | | 4 | 7 | 6 | 3 | 6 | 1 | | |
| Bacillariophyta (Diatoms) | | | | | | | | | |
| | | 440 | 523 | 265 | 455 | 518 | 654 | 253 | 210 |
| Total Non-Diatom Algae Density (cells/mL) | | 451 | 537 | 370 | 616 | 493 | 585 | 423 | 310 |
| Richness | | 8 | 9 | 8 | 11 | 11 | 9 | 15 | 12 |
| Simpson's Diversity | | 0.52 | 0.46 | 0.82 | 0.58 | 0.43 | 0.53 | 0.26 | 0.19 |
| Shannon-Weiner Diversity | | 1.11 | 1.29 | 0.48 | 1.03 | 1.37 | 1.06 | 1.80 | 1.90 |

Appendix B
Proposed Diffuser Site Phytoplankton Data

| Taxa | | Number of Cells per milliliter (No./mL) | | | | | | | |
|---|----------|---|--------|--------|--------|--------|--------|--------|--------|
| | Date | Jun-95 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Oct-96 | Apr-97 |
| | Location | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | C3501 |
| Chlorophyta | | | | | | | | | |
| <i>Actinastrum hantzschii</i> Lagerheim | | | | | | 2 | | | |
| <i>Ankistrodesmus braunii</i> (Naeg.) Brunthaller | | 7 | | | 1 | | | | |
| <i>Chlamydomonas globosa</i> Snow | | | | | | | | | |
| <i>Chlamydomonas</i> sp. Ehrenberg | | 35 | 108 | 58 | 77 | 78 | 55 | 94 | 42 |
| <i>Chlorella/Chlorococcum humicola</i> (Naeg.) Rabenhorst | | 32 | 31 | 20 | 36 | 48 | 47 | 61 | 42 |
| <i>Cosmarium</i> sp. Corda | | | | 1 | | | | | |
| <i>Elakatothrix viridis</i> (Snow) Printz | | 2 | | | | | | | |
| <i>Golenkinia paucispina</i> West & West | | 10 | | | | | | | |
| <i>Pediastrum boryanum</i> (Turp.) Meneghini | | | 2 | 1 | 2 | 4 | 3 | 2 | |
| <i>Pediastrum simplex</i> (Meyen) Lemmermann | | | 1 | 2 | 2 | | | 1 | |
| <i>Scenedesmus bijuga</i> (Turp.) Lagerheim | | | | | | | | | |
| <i>Scenedesmus brasiliensis</i> Bohlin | | | | | | | | | |
| <i>Scenedesmus quadricauda</i> (Turp.) deBrebisson | | | 4 | 1 | 1 | | 4 | 2 | |
| <i>Scenedesmus</i> sp. Meyen | | | 3 | 7 | 6 | 1 | 1 | 3 | |
| <i>Selenastrum minutum</i> (Naeg.) Collins | | 25 | | | | | | | |
| <i>Selenastrum westii</i> G.M. Smith | | | | | | | 2 | | |
| <i>Sphaerocystis Schroeteri</i> Chodat | | | | | | | | | |
| Unknown green spheres | | | | | | | | | |
| Cyanophyta | | | | | | | | | |
| <i>Agmenellum tenuissima</i> Lemmermann | | | | | | | 1 | 1 | |
| <i>Aphanocapsa delicatissima</i> West & West | | | | | | | | | |
| <i>Chroococcus limneticus</i> Lemmermann | | | | | | | | | 6 |
| <i>Chroococcus minor</i> (Kuetz.) Naegeli | | 7 | | | | | | | |
| <i>Gomphosphaeria lacustris</i> | | | | | | | | | |
| <i>Microcystis aeruginosa</i> Kuetz. amend Elenkin | | 2 | | | 1 | | | | |
| <i>Microcystis incerta</i> Lemmermann | | | | | | | | | |
| <i>Oscillatoria limnetica</i> Vaucher | | | | | | | | | |
| Chrysophyta | | | | | | | | | |
| <i>Cladomonas fruticulosa</i> Stein | | 7 | 33 | 24 | 29 | 61 | 44 | 50 | 93 |
| <i>Dinobryon cylindricum</i> Imhoff ex. Ahlstrom | | 35 | | | | | | | |
| <i>Dinobryon sociale</i> var. <i>americanum</i> (Brunn.) Bachmann | | 134 | | 1 | | | | | 3 |
| <i>Mallomonas caudata</i> Iwanoff | | 13 | | | | | | | 9 |
| <i>Mallomonas</i> sp. Perty | | | 19 | 8 | 15 | 16 | 9 | 22 | |
| Pyrrhophyta | | | | | | | | | |
| <i>Chroomonas nordstedtii</i> Hansgirg. | | | 200 | 116 | 195 | 124 | 105 | 203 | 75 |
| <i>Glenodinium pulvisculus</i> (Ehr.) Stein | | | | | | | | | |
| Cryptophyta | | | | | | | | | |
| <i>Cryptomonas erosa</i> Ehrenberg | | | | | | | | | |
| Euglenophyta | | | | | | | | | |
| <i>Euglena</i> Ehrenberg | | | | | | | | | |
| Bacillariophyta (Diatoms) | | 359 | 437 | 284 | 452 | 289 | 335 | 410 | 185 |
| | | | | | | | | | |
| Total Non-Diatom Algae Density (cells/mL) | | 309 | 401 | 239 | 365 | 334 | 271 | 439 | 270 |
| Richness | | 12 | 9 | 11 | 11 | 8 | 10 | 10 | 7 |
| Simpson's Diversity | | 0.23 | 0.33 | 0.31 | 0.35 | 0.25 | 0.25 | 0.29 | 0.24 |
| Shannon-Weiner Diversity | | 1.86 | 1.37 | 1.48 | 1.4 | 1.54 | 1.59 | 1.47 | 1.55 |

Appendix B
Proposed Diffuser Site Phytoplankton Data

| Taxa | Date | Number of Cells per milliliter (No./mL) | | | | |
|---|----------|---|--------|--------|--------|--------|
| | | Apr-97 | Apr-97 | Apr-97 | Apr-97 | Apr-97 |
| | Location | C3501 | C3501 | S3500 | S3500 | S3500 |
| Chlorophyta | | | | | | |
| <i>Actinastrum hantzschii</i> Lagerheim | | | | | | |
| <i>Ankistrodesmus braunii</i> (Naeg.) Brunthaller | | | 3 | | 3 | 3 |
| <i>Chlamydomonas globosa</i> Snow | | | | | | |
| <i>Chlamydomonas</i> sp. Ehrenberg | | 48 | 36 | 33 | 36 | 54 |
| <i>Chlorella/Chlorococcum humicola</i> (Naeg.) Rabenhorst | | 60 | 69 | 24 | 48 | 39 |
| <i>Cosmarium</i> sp. Corda | | | | | | |
| <i>Elakatothrix viridis</i> (Snow) Printz | | | | | | |
| <i>Golenkinia paucispina</i> West & West | | | | | | |
| <i>Pediastrum boryanum</i> (Turp.) Meneghini | | | | | | |
| <i>Pediastrum simplex</i> (Meyen) Lemmermann | | | | | | |
| <i>Scenedesmus bijuga</i> (Turp.) Lagerheim | | | | | | |
| <i>Scenedesmus brasiliensis</i> Bohlin | | | | | | |
| <i>Scenedesmus quadricauda</i> (Turp.) deBrebisson | | 3 | 3 | | 3 | |
| <i>Scenedesmus</i> sp. Meyen | | | | | | |
| <i>Selenastrum minutum</i> (Naeg.) Collins | | | | | | |
| <i>Selenastrum westii</i> G.M. Smith | | 3 | 3 | | | |
| <i>Sphaerocystis Schroeteri</i> Chodat | | | | | | |
| Unknown green spheres | | 3 | 6 | 12 | | 6 |
| Cyanophyta | | | | | | |
| <i>Agmenellum tenuissimum</i> Lemmermann | | | 3 | | 3 | |
| <i>Aphanocapsa delicatissima</i> West & West | | | | | | |
| <i>Chroococcus limneticus</i> Lemmermann | | 6 | 12 | 3 | 3 | 3 |
| <i>Chroococcus minor</i> (Kuetz.) Naegeli | | | | | | |
| <i>Gomphosphaeria lacustris</i> | | | | | | |
| <i>Microcystis aeruginosa</i> Kuetz. amend Elenkin | | | | | | |
| <i>Microcystis incerta</i> Lemmermann | | | | | | |
| <i>Oscillatoria limnetica</i> Vaucher | | | | | | |
| Chrysophyta | | | | | | |
| <i>Cladomonas fruticulosa</i> Stein | | 87 | 120 | 66 | 84 | 75 |
| <i>Dinobryon cylindricum</i> Imhoff ex. Ahlstrom | | | | | | |
| <i>Dinobryon sociale</i> var. <i>americanum</i> (Brunn.) Bachmann | | | | 3 | | 3 |
| <i>Mallomonas caudata</i> Iwanoff | | 27 | 18 | 21 | 9 | 12 |
| <i>Mallomonas</i> sp. Perty | | | | | | |
| Pyrrhophyta | | | | | | |
| <i>Chroomonas nordstedtii</i> Hansgirg | | 87 | 60 | 48 | 36 | 57 |
| <i>Glenodinium pulvisculum</i> (Ehr.) Stein | | | | | | |
| Cryptophyta | | | | | | |
| <i>Cryptomonas erosa</i> Ehrenberg | | | | | | |
| Euglenophyta | | | | | | |
| <i>Euglena</i> Ehrenberg | | | | | | |
| Bacillariophyta (Diatoms) | | | | | | |
| | | 162 | 110 | 56 | 89 | 121 |
| Total Non-Diatom Algae Density (cells/mL) | | | | | | |
| | | 324 | 333 | 210 | 225 | 252 |
| Richness | | | | | | |
| | | 9 | 11 | 8 | 9 | 9 |
| Simpson's Diversity | | | | | | |
| | | 0.20 | 0.21 | 0.20 | 0.23 | 0.20 |
| Shannon-Weiner Diversity | | | | | | |
| | | 1.71 | 1.76 | 1.76 | 1.64 | 1.7 |

Appendix B
Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | May-95 | | | | | | Jun-96 | | | Oct-96 | |
|---|--------|-------|-------|-------|-------|-------|--------|-------|-------|--------|-------|
| | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 |
| <i>Achnanthes affinis</i> Grunow | | | | | | | | | | | |
| <i>Achnanthes exigua</i> Grun. in Cleve & Grunow | | | | | | | | 1 | 2 | | |
| <i>Achnanthes exigua</i> var. <i>heterovalvata</i> Krasske | | | | | | | | | | 2 | 1 |
| <i>Achnanthes clevei</i> var. <i>rostrata</i> Hustedt | | | | | | 1 | | | | | |
| <i>Achnanthes flexella</i> Kutzling | | | | | | | | | 1 | | |
| <i>Achnanthes lanceolata</i> var. <i>rostrata</i> (Ostrup.) Hustedt | | | | | | | | | | | |
| <i>Achnanthes linearis</i> W. Smith | | | | | | | | | | | |
| <i>Achnanthes microcephala</i> Kutzling | | | | | | | | | | 1 | |
| <i>Achnanthes minutissima</i> Kutzling | | 1 | | | 3 | 3 | 1 | 1 | 1 | 9 | 1 |
| <i>Amphipleura pellucida</i> Kutzling | | | | | | | | | | | |
| <i>Amphora pediculus</i> Kutzling | 1 | 1 | 1 | 2 | 3 | 3 | 1 | 1 | 1 | 1 | 1 |
| <i>Amphora perpusilla</i> (Grun.) Grunow | | 2 | 1 | 1 | 3 | 1 | | 1 | 1 | 1 | 1 |
| <i>Anomoeoneis seriens</i> var. <i>brachysira</i> (deBreb.) Husted | | | | | | | | | | 1 | |
| <i>Anomoeoneis vitrea</i> (Grun.) Ross | | | | | | | | | | 6 | 1 |
| <i>Asterionella formosa</i> Hassal | 44 | 36 | 16 | 17 | 26 | 45 | 19 | 8 | 25 | 9 | 19 |
| <i>Aulacoseira ambigua</i> (Grun.) Simonsen | | | | | | | | | | | |
| <i>Aulacoseira distans</i> var. <i>lirata</i> | | | | 3 | 7 | 9 | | | | | |
| <i>Aulacoseira granulata</i> (Ehr.) Simonson | | | | | | | 2 | 1 | 1 | | |
| <i>Aulacoseira islandica</i> (O. Muller) Simonson | | | | | | 6 | | | | | |
| <i>Aulacoseira italica</i> (Ehr.) Simonson | | | | | | | | | | | |
| <i>Aulacoseira italica</i> var. <i>tenuissima</i> (Grun.) Simonson | | | | | | | | 1 | 1 | 1 | 1 |
| <i>Caloneis bacillum</i> (Grun.) Meresch. | | | | | | 1 | | | | | |
| <i>Cocconeis pediculus</i> Ehrenberg | | | | | | | | | | | |
| <i>Cocconies placentula</i> var. <i>euglypta</i> (Ehr.) Cleve | | | | | | | 1 | | 2 | 4 | 4 |
| <i>Cocconeis placentula</i> var. <i>lineata</i> Cleve | 3 | 6 | 3 | 3 | 3 | 5 | | | | | |
| <i>Cocconeis thumensis</i> A. Mayer | | | | 1 | 1 | 1 | | | | | |
| <i>Cyclotella compta</i> (Ehr.) Kutzling | | | | | | | | | | 2 | 1 |
| <i>Cyclotella meneghiniana</i> Kutzling | | | | | | | | | | | |
| <i>Cyclotella michiginiana</i> Skv. | 5 | 3 | 1 | 6 | 9 | 8 | | | | 10 | 8 |
| <i>Cyclotella ocellata</i> Pant. | | | | | | | 1 | 1 | 3 | 49 | 15 |
| <i>Cyclotella pseudostelligera</i> Husted | | | | | | | 1 | 1 | 1 | | |
| <i>Cyclotella socialis</i> Schutt | | | | | | | | | | 3 | |
| <i>Cyclotella stelligera</i> (Cleve et Grun.) V.H. | 3 | 3 | 1 | 3 | 3 | 1 | 3 | 1 | 4 | 11 | 11 |
| <i>Cymatopleura elliptica</i> (deBreb.) W. Smith | | | | | | | | | | | |
| <i>Cymatopleura solea</i> (deBreb.) W. Smith | | | | | 1 | | | | | | |
| <i>Cymbella affinis</i> Kutzling | | | | | | | | | | 6 | |
| <i>Cymbella amphicephala</i> Naegeli | | | | | | | | | | | |
| <i>Cymbella cuspidata</i> Kutzling | | 1 | 1 | 1 | 3 | 1 | | | | | |
| <i>Cymbella microcephala</i> Grunow | | | | | | | | | | 2 | |
| <i>Cymbella minuta</i> var. <i>pseudogracilis</i> (Choln.) Reim | | | | | | 1 | | | | | |
| <i>Cymbella naviculiformis</i> Auerswald | | | | | | | | | | | 1 |
| <i>Cymbella parva</i> (W. Smith) Cleve | | | | | | | | | | | |
| <i>Cymbella perpusilla</i> A. Cleve | | | | | | | | | | 7 | |
| <i>Cymbella prostata</i> (Berkeley) Cleve | | | | | | | | | | 1 | |
| <i>Cymbella ventricosa</i> Kutzling | | | | | | | | | | 1 | |
| <i>Diatoma anceps</i> (Ehr.) Grunow | | 1 | | | | | | | | | |
| <i>Diatoma tenue</i> Agardh | 44 | 71 | 46 | 68 | 72 | 90 | 35 | 25 | 40 | 4 | 1 |
| <i>Diatoma tenue</i> var. <i>elongatum</i> Lyngbye | 78 | 90 | 39 | 54 | 55 | 79 | 92 | 70 | 98 | | |
| <i>Diatoma vulgare</i> Bory | | | | | | | | | | | |
| <i>Diatoma vulgare</i> var. <i>Breve</i> | 1 | 6 | 2 | 5 | 5 | 6 | 1 | 1 | 3 | | |
| <i>Diploneis ovalis</i> (Hilse.) Cleve | | | | | | | | | | | |
| <i>Diploneis puella</i> (Schumann) Cleve | | | | | | 1 | | | | | |
| <i>Epithemia emarginata</i> Andrews | 1 | | | | | | | | | | |
| <i>Fragilaria brevistriata</i> Grunow | | | | | | | | | | 1 | |
| <i>Fragilaria capucina</i> Desmzeires | | | 1 | | | 4 | | | | | |
| <i>Fragilaria capucina</i> var. <i>gracilis</i> (Oestr.) Hustedt | 25 | 39 | 17 | 40 | 39 | 33 | | | | | |
| <i>Fragilaria capucina</i> var. <i>mesolepta</i> (Rabh.) Grunow | 26 | 36 | 11 | 18 | 19 | 33 | | | | | |

Appendix B

Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | May-95 | | | | | | Jun-96 | | | Oct-96 | |
|--|--------|-------|-------|-------|-------|-------|--------|-------|-------|--------|-------|
| | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 |
| <i>Fragilaria capucina</i> var. <i>vaucheriae</i> (Kutz.) Lange-Bertalot | 49 | 45 | 18 | 21 | 7 | 16 | | 1 | | | |
| <i>Fragilaria consturens</i> (Ehr.) Grunow | | | | | | | | | | | |
| <i>Fragilaria construens</i> var. <i>binodis</i> (Ehr.) Grunow | 6 | 10 | 20 | 48 | 67 | 85 | | | | | |
| <i>Fragilaria construens</i> var. <i>venter</i> (Ehr.) Grunow | | 3 | 5 | 32 | 28 | 37 | | | | 4 | 1 |
| <i>Fragilaria crotonensis</i> Kitton | | 6 | 4 | | | 15 | | | 9 | 4 | 8 |
| <i>Fragilaria delicatissima</i> (W. Smith) Lange-Bertalot | | | | | | | | | | | |
| <i>Fragilaria intermedia</i> Grunow | | | | | | | | | | 1 | 2 |
| <i>Fragilaria pinnata</i> Ehrenberg | 1 | 2 | 2 | 9 | 5 | 6 | | | | | |
| <i>Fragilaria tenera</i> (W. Smith) Lange-Bertalot | | | | | | | | | | | |
| <i>Fragilaria virescens</i> Ralfs | | | | | | | 21 | 29 | 44 | 7 | 3 |
| <i>Gomphonema angustatum</i> var. <i>producta</i> Grunow | | | | | | | | | | 3 | |
| <i>Gomphonema intricatum</i> Kutzing | | | | | | | | | | | 1 |
| <i>Gomphonema olivaceum</i> (Lyngbye) Kutzing | | | | | | | | 1 | | | |
| <i>Gomphonema parvulum</i> (Kutz.) Grunow | | | | | | | | | | | |
| <i>Gyrosigma acuminatum</i> (Kutz.) Rabh. | | | 1 | | | | | | | | |
| <i>Melosira varians</i> C.A. Agardh | 1 | 2 | 1 | 1 | 3 | 4 | | | | | |
| <i>Navicula</i> 2 | 1 | 1 | | | | | | | | | |
| <i>Navicula arvensis</i> Hust. | | | 1 | 1 | 5 | 2 | | | | | 1 |
| <i>Navicula capitata</i> Ehrenberg | 1 | 7 | 2 | 4 | 6 | 3 | | | | | |
| <i>Navicula capitata</i> var. <i>lunebergensis</i> (Grun.) Patrick | | | | | | | | | | | |
| <i>Navicula cincta</i> (Ehr.) Kutzing | | | | | | | | | | | |
| <i>Navicula cohnii</i> (Hilse.) Grunow | | | | | | | | | | 2 | |
| <i>Navicula contenta</i> Grunow | | | | | | | | | | | |
| <i>Navicula cryptocephala</i> Kutzing | 1 | 4 | 2 | 9 | 11 | 6 | 1 | | 1 | 2 | 2 |
| <i>Navicula cryptocephala</i> var. <i>exilis</i> Kutzing | | | | | | | | 1 | | | |
| <i>Navicula frugalis</i> Hustedt | | | | | | | | | | | |
| <i>Navicula gastrum</i> (Ehr.) Donkin | | | | | | | 1 | 1 | 1 | | |
| <i>Navicula gracilis</i> Ehrenberg | | | | | | | | | | | |
| <i>Navicula hungarica</i> Grunow | | | | | | | | 1 | 1 | 3 | |
| <i>Navicula lacustris</i> Gregory | 1 | 1 | | | 1 | 1 | | | | | |
| <i>Navicula menisculus</i> Schumann | | | | | | | | | | 1 | 2 |
| <i>Navicula minima</i> Grunow | | 1 | 1 | | 1 | | | | | | 1 |
| <i>Navicula mutica</i> Kutzing | | | | | | | | | | | |
| <i>Navicula nitrophila</i> B. Petersen | | | | | | | | 1 | | | |
| <i>Navicula perpussilla</i> Grunow | | | | | | | | | | | |
| <i>Navicula pseudoreinhardtii</i> Patrick | 1 | 3 | 1 | 1 | 3 | 2 | | | | | |
| <i>Navicula pupula</i> Kutzing | | | | 1 | 1 | | 1 | | | | |
| <i>Navicula pupula</i> var. <i>mutata</i> (Krasske) Hustedt | 1 | 1 | | | | | | | | | |
| <i>Navicula pusio</i> Cleve | 1 | 1 | 3 | 1 | 3 | 3 | | | | | |
| <i>Navicula radiosa</i> Kutzing | | | | 1 | | 1 | | 1 | 1 | | 1 |
| <i>Navicula radiosa</i> var. <i>tenella</i> (deBreb. ex Katz.) Grunow | | | | | 1 | 1 | | | | | |
| <i>Navicula schmassmannii</i> Hustedt | | | | | | | | | | | |
| <i>Navicula seminulum</i> Grunow | | | | | | | | | | 2 | 1 |
| <i>Navicula</i> 1 | | | | | | | | | | 1 | |
| <i>Navicula subtilissima</i> Cleve | 1 | | | | | | | | | | |
| <i>Navicula symmetrica</i> Patrick | | 1 | 2 | | 1 | 3 | | | | | |
| <i>Navicula variostrata</i> Krasske | | | | | | | | | | | 1 |
| <i>Neidium dubium</i> (Ehr.) Cleve | | | | | | | | 1 | | | |
| <i>Nitzschia</i> (longissima?) (deBreb.) Ralfs | | | | | | | | | 11 | | |
| <i>Nitzschia acicularis</i> W. Smith | 15 | 10 | 1 | 5 | 5 | 7 | 7 | 2 | 5 | 1 | |
| <i>Nitzschia amphibia</i> Grunow | | | | 1 | | | | | | | |
| <i>Nitzschia angustata</i> (W. Smith) Grunow | 1 | 1 | 2 | 2 | 2 | 6 | | | | | |
| <i>Nitzschia denticula</i> Grunow | | | | | | | | | | 1 | |
| <i>Nitzschia dissipata</i> (Kutz.) Grunow | 10 | 4 | 3 | 9 | 5 | 4 | | | | | |
| <i>Nitzschia fonticola</i> Grunow | 3 | 8 | 2 | 2 | 3 | 6 | | | | | |
| <i>Nitzschia frustulum</i> Grunow | | 3 | | 1 | | | 2 | 1 | 1 | 30 | 11 |
| <i>Nitzschia</i> GLRD 1 | | | 1 | 4 | 1 | 4 | | | | | |

Appendix B
Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | May-95 | | | | | | Jun-96 | | | Oct-96 | |
|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 |
| <i>Nitzschia gracilis</i> Hantzsch. | 10 | 11 | 9 | 9 | 13 | 23 | | | 3 | | |
| <i>Nitzschia linearis</i> W. Smith | | | | 4 | 5 | 6 | | 1 | 1 | 3 | 1 |
| <i>Nitzschia paleacea</i> Grunow | 6 | 5 | 1 | 5 | 3 | 4 | | | | 64 | 48 |
| <i>Nitzschia romana</i> Grunow | | | | | | | | | | 61 | 30 |
| <i>Nitzschia sublinearis</i> Hustedt | 13 | 13 | 5 | 5 | 17 | 15 | | | | | |
| <i>Nitzschia thermalis</i> Kutzig | | | 1 | | | | | | | | |
| <i>Rhizosolenia eriensis</i> H.L. Smith | | | | | | | 1 | 1 | 3 | | |
| <i>Rhoicosphenia curvata</i> (Kutz.) Grunow | 2 | 1 | 1 | 2 | 3 | 1 | | | | | |
| <i>Sellophora bacillum</i> (Ehr.) D. Mann | | 1 | | | | | | | | | |
| <i>Stephanodiscus alpinus</i> Hust. | | | | | | | 2 | 3 | 5 | 25 | 17 |
| <i>Stephanodiscus hantzschii</i> Grun. in Cleve & Grunow | 46 | 45 | 17 | 30 | 40 | 29 | 20 | 18 | 22 | 43 | 47 |
| <i>Stephanodiscus hantzschii</i> var. <i>tenuis</i> (Hust.) Hakansson & Stoermer | | | | | | | 10 | 6 | 16 | 33 | 35 |
| <i>Stephanodiscus niagarae</i> Ehrenberg | | | | | | | | | | 3 | |
| <i>Stephanodiscus parvus</i> Stoermer & Hakansson | 13 | 17 | 6 | 5 | 6 | 4 | 3 | 2 | 1 | | |
| <i>Sunirella didyma</i> Kutzig | | 1 | 1 | 2 | 1 | 1 | | | | | |
| <i>Sunirella linearis</i> W. Smith | | | | | | | | | | 4 | 1 |
| <i>Sunirella ovata</i> Kutzig | 1 | | | 1 | 1 | | | | | | |
| <i>Sunirella ovata</i> var. <i>pinnata</i> W. Smith | | | | | | | | | | | 1 |
| <i>Synedra acus</i> var. <i>angustissima</i> Grunow | | | | | | | 9 | 11 | 17 | 4 | 2 |
| <i>Synedra delicatissima</i> W. Smith | 13 | 8 | 7 | 11 | 10 | 11 | 10 | 9 | 23 | | |
| <i>Synedra nana</i> Meister | | | | | | | 4 | 1 | | | |
| <i>Synedra pulchella</i> Kutzig | | | 1 | | | | | | | | |
| <i>Synedra ulna</i> (Nitz.) Ehrenberg | 2 | 2 | 2 | 1 | 2 | 1 | | | | 2 | |
| <i>Synedra ulna</i> var. <i>chaseana</i> Thomas | 11 | 6 | 4 | 5 | 9 | 10 | | 1 | 2 | | |
| <i>Synedra ulna</i> var. <i>danica</i> (Kutz.) Grunow | | | | | | | 5 | 4 | 5 | | |
| <i>Tabellaria flocculosa</i> (Roth) Kutzig | | 1 | | | 1 | 1 | | | | | |
| <i>Tabellaria quadrisepitata</i> Knudson | 1 | 1 | 1 | 1 | 1 | 2 | | 2 | | 1 | 1 |
| Total Diatom Density (cells/mL) | 440 | 523 | 265 | 455 | 518 | 654 | 253 | 210 | 359 | 437 | 284 |
| Richness | 38 | 47 | 45 | 46 | 50 | 54 | 26 | 36 | 35 | 47 | 37 |
| Simpson's Diversity | 0.08 | 0.08 | 0.08 | 0.07 | 0.07 | 0.07 | 0.17 | 0.15 | 0.13 | 0.08 | 0.09 |
| Shannon-Weiner Diversity | 2.78 | 2.93 | 3.01 | 3.03 | 3.12 | 3.12 | 2.29 | 2.46 | 2.51 | 2.95 | 2.69 |

Appendix B Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | Oct-96 | | | | Apr-97 | | | | | | | |
|---|--------|-------|-------|-------|--------|-------|-------|-------|-------|-------|-------|-------|
| | C3501 | S3500 | S3500 | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | S3500 |
| <i>Achnanthes affinis</i> Grunow | | | | | | | | | | | | 1 |
| <i>Achnanthes exigua</i> Grun. in Cleve & Grunow | | | | | | | | | | | | |
| <i>Achnanthes exigua</i> var. <i>heterovalvata</i> Krasske | 3 | 3 | | | | | | | | | | |
| <i>Achnanthes clevei</i> var. <i>rostrata</i> Hustedt | | | | | | | | | | | | |
| <i>Achnanthes flexella</i> Kutzing | | | | | | | | | | | | |
| <i>Achnanthes lanceolata</i> var. <i>rostrata</i> (Ostrup.) Hustedt | | | | | | | | 1 | 1 | | | |
| <i>Achnanthes linearis</i> W. Smith | | | | | 1 | | | | | | | 1 |
| <i>Achnanthes microcephala</i> Kutzing | 1 | | | 2 | | | | | | | | |
| <i>Achnanthes minutissima</i> Kutzing | 7 | 3 | 3 | 6 | 2 | 2 | | 1 | 1 | 1 | | |
| <i>Amphipleura pellucida</i> Kutzing | | | | | | | | | | | | |
| <i>Amphora pediculus</i> Kutzing | 1 | 3 | 2 | 3 | 1 | 1 | 2 | 1 | 1 | 1 | 1 | |
| <i>Amphora perpusilla</i> (Grun.) Grunow | 1 | 3 | 2 | | 1 | 2 | 1 | 1 | 1 | 1 | 1 | |
| <i>Anomoeoneis seriens</i> var. <i>brachysira</i> (deBreb.) Hustedt | | | 2 | | | | | | | | | |
| <i>Anomoeoneis vitrea</i> (Grun.) Ross | 2 | | 7 | 4 | | | | | | | | |
| <i>Asterionella formosa</i> Hassal | 3 | 10 | 5 | 8 | 1 | 2 | 1 | 1 | 1 | 1 | 1 | |
| <i>Aulacoseira ambigua</i> (Grun.) Simonsen | | | | | 1 | 1 | | | | 1 | 1 | |
| <i>Aulacoseira distans</i> var. <i>lirata</i> | | | | | | | | | | | | |
| <i>Aulacoseira granulata</i> (Ehr.) Simonson | | | | | | | | | | | | |
| <i>Aulacoseira islandica</i> var. <i>helvetica</i> | | | | | | | | | | | | |
| <i>Aulacoseira italica</i> (Ehr.) Simonson | | | | | | | | | | | | |
| <i>Aulacoseira italica</i> var. <i>tenuissima</i> (Grun.) Simonson | | | 2 | 1 | | | | | | | | |
| <i>Caloneis bacillum</i> (Grun.) Meresch. | | | | 1 | | | | | | | | |
| <i>Cocconeis pediculus</i> Ehrenberg | 3 | 1 | 1 | | | | | | | | | |
| <i>Cocconeis placentula</i> var. <i>euglypta</i> (Ehr.) Cleve | 4 | 3 | 3 | 5 | 3 | 2 | 1 | 1 | 3 | 2 | | |
| <i>Cocconeis placentula</i> var. <i>lineata</i> Cleve | | | | | 1 | 1 | 1 | | 1 | 1 | | |
| <i>Cocconeis thumensis</i> A. Mayer | | | | | | 1 | 1 | 1 | 1 | 1 | 1 | |
| <i>Cyclotella compta</i> (Ehr.) Kutzing | 2 | | | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | |
| <i>Cyclotella meneghiniana</i> Kutzing | | | | | 1 | 1 | 1 | | 1 | 1 | | |
| <i>Cyclotella michiganiana</i> Skv. | 12 | 11 | 9 | 11 | | | | | | | | |
| <i>Cyclotella ocellata</i> Pant. | 44 | 14 | 42 | 45 | 10 | 3 | 1 | 1 | 1 | 2 | | |
| <i>Cyclotella pseudostelligera</i> Hustedt | | | | | | | | | | | | |
| <i>Cyclotella socialis</i> Schutt | 2 | 3 | 1 | 4 | | | | | | | | |
| <i>Cyclotella stelligera</i> (Cleve et Grun.) V.H. | 20 | 4 | 7 | 12 | 14 | 22 | 17 | 8 | 15 | 16 | | |
| <i>Cymatopleura elliptica</i> (deBreb.) W. Smith | | | | | 1 | 1 | | 1 | | | | |
| <i>Cymatopleura solea</i> (deBreb.) W. Smith | | | | | | | | | | | | |
| <i>Cymbella affinis</i> Kutzing | 1 | | 3 | | | | | | | | | |
| <i>Cymbella amphicephala</i> Naegeli | | | | | | 1 | | 1 | 1 | 1 | | |
| <i>Cymbella cuspidata</i> Kutzing | | | | | | | | | | | | |
| <i>Cymbella microcephala</i> Grunow | 1 | | 3 | | 1 | 1 | 1 | 1 | | 1 | | |
| <i>Cymbella minuta</i> var. <i>pseudogracilis</i> (Choln.) Reim | | | | | | | | | | | | |
| <i>Cymbella naviculiformis</i> Auerswald | | | | | | | | | | | | |
| <i>Cymbella parva</i> (W. Smith) Cleve | | | | | | | | 1 | | | | |
| <i>Cymbella perpusilla</i> A. Cleve | 1 | | 4 | | | | | | | | | |
| <i>Cymbella prostata</i> (Berkeley) Cleve | 2 | | | | | | | | | | | |
| <i>Cymbella ventricosa</i> Kutzing | 3 | 4 | 2 | 1 | 1 | | 1 | 1 | 1 | 1 | | |
| <i>Diatoma anceps</i> (Ehr.) Grunow | | | | | | | | | | | | |
| <i>Diatoma tenuis</i> Agardh | 1 | 3 | 1 | 2 | 3 | 4 | 5 | 1 | 3 | 3 | | |
| <i>Diatoma tenuis</i> var. <i>elongatum</i> Lyngbye | | | | | | | | | | | | |
| <i>Diatoma vulgare</i> Bory | | | | | 2 | 1 | 3 | 2 | 3 | 3 | | |
| <i>Diatoma vulgare</i> var. <i>Breve</i> | | | 1 | 1 | | | | | | | | |
| <i>Diploneis ovalis</i> (Hilse.) Cleve | | | | | | | 1 | | | | | |
| <i>Diploneis puella</i> (Schumann) Cleve | | | | | | | | | | | | |
| <i>Epithemia emarginata</i> Andrews | | | | | | | | | | | | |
| <i>Fragilaria brevistriata</i> Grunow | | | | 1 | | | | | | | | |
| <i>Fragilaria capucina</i> Desmzeires | | | | | 5 | 1 | 3 | 1 | 2 | 2 | | |
| <i>Fragilaria capucina</i> var. <i>gracilis</i> (Oestr.) Hustedt | | | | | 1 | 1 | 1 | 1 | 1 | 1 | | |
| <i>Fragilaria capucina</i> var. <i>mesolepta</i> (Rabh.) Grunow | | | | | | | | | | | | |

Appendix B
Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | Oct-96 | | | | Apr-97 | | | | | |
|--|--------|-------|-------|-------|--------|-------|-------|-------|-------|-------|
| | C3501 | S3500 | S3500 | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 |
| <i>Fragilaria capucina</i> var. <i>vaucheriae</i> (Kutz.) Lange-Bertalot | | | | | 8 | 6 | 5 | 4 | 6 | 4 |
| <i>Fragilaria consturens</i> (Ehr.) Grunow | 1 | | | 1 | 4 | 5 | 1 | 1 | 3 | 3 |
| <i>Fragilaria construens</i> var. <i>binodis</i> (Ehr.) Grunow | | | | | | | | | | |
| <i>Fragilaria construens</i> var. <i>venter</i> (Ehr.) Grunow | 1 | 3 | 3 | 9 | 1 | 3 | 2 | 1 | 1 | 1 |
| <i>Fragilaria crotonensis</i> Kitton | 3 | | | | | | | | | |
| <i>Fragilaria delicatissima</i> (W. Smith) Lange-Bertalot | | | | | 1 | 1 | 1 | 1 | | 1 |
| <i>Fragilaria intermedia</i> Grunow | 3 | | 6 | | | | | | | |
| <i>Fragilaria pinnata</i> Ehrenberg | | | | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Fragilaria tenera</i> (W. Smith) Lange-Bertalot | | | | | | 1 | | | | |
| <i>Fragilaria virescens</i> Ralfs | 17 | 25 | 17 | 6 | | | | | | |
| <i>Gomphonema angustatum</i> var. <i>producta</i> Grunow | 2 | | 2 | 2 | | | | | | 1 |
| <i>Gomphonema intricatum</i> Kutzing | | | | | | | | | | |
| <i>Gomphonema olivaceum</i> (Lyngbye) Kutzing | | | | | | | | | | |
| <i>Gomphonema parvulum</i> (Kutz.) Grunow | | | | | 1 | | | | | |
| <i>Gyrosigma acuminatum</i> (Kutz.) Rabh. | | | | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Melosira varians</i> C.A. Agardh | | | | | | 1 | | 1 | 1 | |
| <i>Navicula</i> 2 | | | | | | | | | | |
| <i>Navicula arvensis</i> Hust. | | | | | 1 | | | 1 | 1 | |
| <i>Navicula capitata</i> Ehrenberg | | | | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Navicula capitata</i> var. <i>lunebergensis</i> (Grun.) Patrick | | | | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Navicula cincta</i> (Ehr.) Kutzing | | | | | | | | 1 | 1 | |
| <i>Navicula cohnii</i> (Hilse.) Grunow | 1 | | 2 | | 1 | | 1 | 1 | 1 | 1 |
| <i>Navicula contenta</i> Grunow | | | | | | | | | | |
| <i>Navicula cryptocephala</i> Kutzing | 4 | | 1 | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Navicula cryptocephala</i> var. <i>exilis</i> Kutzing | | | | | | | | | | |
| <i>Navicula frugalis</i> Hustedt | | | | | | | | | 1 | |
| <i>Navicula gastrum</i> (Ehr.) Donkin | | | | | 1 | 1 | 1 | | 1 | 0 |
| <i>Navicula gracilis</i> Ehrenberg | | | | | 1 | 1 | 1 | 1 | 1 | 1 |
| <i>Navicula hungarica</i> Grunow | 3 | | 1 | 1 | | | | | | |
| <i>Navicula lacustris</i> Gregory | | | | | | 1 | 1 | | 1 | 1 |
| <i>Navicula menisculus</i> Schumann | 1 | 2 | 2 | 3 | 3 | 2 | 1 | 1 | 1 | 1 |
| <i>Navicula minima</i> Grunow | 1 | | | | 0 | 1 | 1 | 1 | 1 | 1 |
| <i>Navicula mutica</i> Kutzing | | | | | | 0 | | | | |
| <i>Navicula nitrophila</i> B. Petersen | | | | | | | | | | |
| <i>Navicula perpusilla</i> Grunow | | | | | | | | | | |
| <i>Navicula pseudoreinhardtii</i> Patrick | | | | | | | | | | |
| <i>Navicula pupula</i> Kutzing | | | | | | | | | | |
| <i>Navicula pupula</i> var. <i>mutata</i> (Krasske) Hustedt | | | | | | | | | | |
| <i>Navicula pusio</i> Cleve | | | | | | | | | | |
| <i>Navicula radiosa</i> Kutzing | 2 | 2 | | | | | | | | |
| <i>Navicula radiosa</i> var. <i>tenella</i> (deBreb. ex Katz.) Grunow | | | | | 1 | | 1 | 1 | 1 | 1 |
| <i>Navicula schmassmannii</i> Hustedt | | | 1 | | | | | | | |
| <i>Navicula seminulum</i> Grunow | | | | 3 | 1 | | 1 | 1 | | 1 |
| <i>Navicula</i> 1 | | 3 | | 1 | | | | | | |
| <i>Navicula subtilissima</i> Cleve | | | | | | | | 1 | | |
| <i>Navicula symmetrica</i> Patrick | | | | | | | | | | |
| <i>Navicula variostrata</i> Krasske | | | | | 1 | 1 | 1 | 1 | 1 | 3 |
| <i>Neidium dubium</i> (Ehr.) Cleve | | | | | | | | 1 | | 1 |
| <i>Nitzschia</i> (longissima?) (deBreb.) Ralfs | | | | | | | | | | |
| <i>Nitzschia acicularis</i> W. Smith | | | | 1 | 3 | 4 | 2 | 1 | 1 | 1 |
| <i>Nitzschia amphibia</i> Grunow | | | | | | 1 | 1 | 1 | 1 | |
| <i>Nitzschia angustata</i> (W. Smith) Grunow | | | | | | | | | | |
| <i>Nitzschia denticula</i> Grunow | | | | | | | | | | |
| <i>Nitzschia dissipata</i> (Kutz.) Grunow | | | | 1 | 2 | 1 | 1 | 1 | 1 | |
| <i>Nitzschia fonticola</i> Grunow | | | | | | | | | | |
| <i>Nitzschia frustulum</i> Grunow | 31 | 35 | 21 | 24 | 1 | 1 | 1 | | | 1 |
| <i>Nitzschia</i> GLRD 1 | | | | | | | | | | |

Appendix B
Proposed Diffuser Site Phytoplankton Diatom Data

| Taxa | Oct-96 | | | | Apr-97 | | | | | | |
|--|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------|
| | C3501 | S3500 | S3500 | S3500 | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 |
| <i>Nitzschia gracilis</i> Hantzsch. | | | | | | | | | | | |
| <i>Nitzschia linearis</i> W. Smith | 3 | 1 | | 1 | | 1 | 1 | 1 | 2 | 1 | |
| <i>Nitzschia paleacea</i> Grunow | 64 | 47 | 51 | 64 | 19 | 19 | 7 | 4 | 4 | 11 | |
| <i>Nitzschia romana</i> Grunow | 33 | 6 | 21 | 42 | 9 | 11 | 2 | 1 | 1 | 3 | |
| <i>Nitzschia sublinearis</i> Hustedt | | | | | | | | | | | |
| <i>Nitzschia thermalis</i> Kutzing | | | | | | | | | | | |
| <i>Rhizosolenia eriensis</i> H.L. Smith | | | | | | | | | | | |
| <i>Rhoicosphenia curvata</i> (Kutz.) Grunow | | 3 | | | 1 | 1 | 1 | 1 | 1 | 1 | |
| <i>Sellophora bacillum</i> (Ehr.) D. Mann | | | | | 1 | 1 | | 1 | 1 | | |
| <i>Stephanodiscus alpinus</i> Hust. | 22 | 25 | 24 | 41 | 8 | 7 | 6 | 2 | 4 | 5 | |
| <i>Stephanodiscus hantzschii</i> Grun. in Cleve & Grunow | 76 | 37 | 48 | 50 | 44 | 35 | 29 | 12 | 21 | 26 | |
| <i>Stephanodiscus hantzschii</i> var. <i>tenuis</i> (Hust.) Hakansson & Stoermer | 55 | 24 | 29 | 38 | 23 | 14 | 9 | 6 | 8 | 12 | |
| <i>Stephanodiscus niagarae</i> Ehrenberg | 1 | 2 | 2 | 3 | | | | | | | |
| <i>Stephanodiscus parvus</i> Stoermer & Hakansson | | | | | | | | | | | |
| <i>Surirella didyma</i> Kutzing | | | | | | | | | | | |
| <i>Surirella linearis</i> W. Smith | 2 | | | 3 | | | | | | | |
| <i>Surirella ovata</i> Kutzing | | | | | | | | | | | |
| <i>Surirella ovata</i> var. <i>pinnata</i> W. Smith | 1 | 2 | | 6 | 1 | 1 | 1 | 1 | | 1 | |
| <i>Synedra acus</i> var. <i>angustissima</i> Grunow | 6 | 3 | 4 | 1 | 3 | 1 | 2 | 1 | 1 | 3 | |
| <i>Synedra delicatissima</i> W. Smith | | | | | | | | | | | |
| <i>Synedra nana</i> Meister | | | | | | | | | | | |
| <i>Synedra pulchella</i> Kutzing | | | | | | | | | | | |
| <i>Synedra ulna</i> (Nitz.) Ehrenberg | 1 | | | | 1 | 1 | 1 | 1 | 1 | 1 | |
| <i>Synedra ulna</i> var. <i>chaseana</i> Thomas | | | | | | | | | | | |
| <i>Synedra ulna</i> var. <i>danica</i> (Kutz.) Grunow | | | | | | | | | | | |
| <i>Tabellaria flocculosa</i> (Roth) Kutzing | | | | | | | | | | | |
| <i>Tabellaria quadrisepata</i> Knudson | 2 | 4 | | | 1 | 1 | | 1 | 1 | 1 | |
| Total Diatom Density (cells/mL) | 450 | 289 | 335 | 410 | 185 | 176 | 124 | 82 | 111 | 132 | |
| Richness | 45 | 30 | 36 | 38 | 52 | 53 | 49 | 55 | 53 | 54 | |
| Simpsons Diversity | 0.09 | 0.11 | 0.08 | 0.09 | 0.10 | 0.09 | 0.11 | 0.10 | 0.10 | 0.09 | |
| Shannon-Weiner Diversity | 2.81 | 2.52 | 2.83 | 2.78 | 2.88 | 2.92 | 2.83 | 2.99 | 2.96 | 3.00 | |

Appendix C

Chemical Data

Appendix C **Lake Michigan Water Chemistry Data**

| Parameter | Units | May-95 | | Jun-96 | | Oct-96 | | Apr-97 | |
|---|-------|--------|-------|--------|-------|--------|-------|--------|-------|
| | | C3501 | S3500 | S3500 | S3500 | C3501 | S3500 | C3501 | S3500 |
| pH | s.u. | | | 7.0 | 6.9 | 8.1 | 8.1 | 8.5 | 8.3 |
| Total Suspended Solids (TSS) | mg/L | 2.0 | 3.0 | 0.9 | 0.9 | 2.5 | 2.0 | 0.9 | 0.9 |
| Total Dissolved Solids (TDS) | mg/L | 188 | 198 | 194 | 188 | 148 | 140 | 160 | 160 |
| Alkalinity as CaCO ₃ | mg/L | 110 | 110 | | | | | | |
| Chloride | mg/L | 14.0 | 14.0 | 12.7 | 13.2 | 12.5 | 14.0 | 17.0 | 17.0 |
| Total Organic Carbon (TOC) ¹ | mg/L | 3.20 | 3.20 | 4.30 | 4.50 | 2.50 | 2.60 | 14.00 | 20.00 |
| Hardness as CaCO ₃ | mg/L | 158 | 133 | 147 | 150 | 155 | 150 | 150 | 160 |
| Total Kjeldahl Nitrogen (TKN) | mg/L | 1.1 | 1.9 | | | 0.4 | 0.4 | 0.4 | 0.4 |
| Nitrate/Nitrite | mg/L | 1.50 | 0.29 | 0.35 | 0.34 | 0.30 | 0.40 | 0.34 | 0.09 |
| Total Nitrogen | mg/L | | | 1.74 | 1.56 | | | | |
| Total Phosphorus | mg/L | 0.100 | 0.120 | 0.009 | 0.009 | 0.020 | 0.020 | 0.200 | 0.200 |
| Ortho-Phosphorus | mg/L | 0.009 | 0.050 | 0.009 | 0.009 | 0.020 | 0.020 | 0.200 | 0.200 |
| Silica | mg/L | 0.50 | 0.60 | 0.70 | 0.65 | 0.50 | 0.38 | 0.60 | 0.59 |
| Sulfate | mg/L | 25 | 26 | | | | | | |
| Total Calcium | mg/L | 85 | 54 | | | | | | |
| Total Magnesium | mg/L | 12 | 12 | | | | | | |
| Total Sodium | mg/L | 7.7 | 7.0 | | | | | | |
| Total Potassium | mg/L | 0.3 | 3.3 | | | | | | |

¹Method 9060 with extraction.

²Method 9060 total combustion.

Appendix C
Lake Michigan Water Chemistry Sampling Schedule

| Parameter | Units | Method | Dates Collected ¹ | | | |
|---------------------------------|-------|----------|------------------------------|--------|--------|--------|
| pH | s.u. | 9040A | | Jun-96 | Oct-96 | Apr-97 |
| Total Suspended Solids (TSS) | mg/L | EPA160.2 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Total Dissolved Solids (TDS) | mg/L | EPA160.1 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Alkalinity as CaCO ₃ | mg/L | EPA310.2 | May-95 | | | |
| Chloride | mg/L | 2951 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Total Organic Carbon (TOC) | mg/L | EPA415.1 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Hardness as CaCO ₃ | mg/L | EPA130.2 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Total Kjeldahl Nitrogen (TKN) | mg/L | EPA351.1 | May-95 | | Oct-96 | Apr-97 |
| Nitrate/Nitrite | mg/L | 9200 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Total Nitrogen | mg/L | Calc. | | Jun-96 | | |
| Total Phosphorus | mg/L | EPA365.4 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Ortho-Phosphorus | mg/L | EPA365.2 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Silica | mg/L | 6010 | May-95 | Jun-96 | Oct-96 | Apr-97 |
| Sulfate | mg/L | EPA375.4 | May-95 | | | |
| Total Calcium | mg/L | EPA215.1 | May-95 | | | |
| Total Magnesium | mg/L | EPA242.1 | May-95 | | | |
| Total Sodium | mg/L | EPA273.1 | May-95 | | | |
| Total Potassium | mg/L | EPA258.1 | May-95 | | | |

¹Collection dates were May 23-25, 1995; June 5-6, 1996; October 21-24, 1996; and April 28-30, 1997.

Appendix C

In-Situ Water Quality Determinations

| Dissolved Oxygen (mg/L) | | | | | | | | | | | | | |
|-------------------------|---------|---------|---------|---------|---------|---------|--------|----------|----------|----------|----------|---------|---------|
| Date | 5/23/95 | 5/24/95 | 5/25/95 | 5/23/95 | 5/24/95 | 5/25/95 | 6/5/96 | 10/21/96 | 10/24/96 | 10/21/96 | 10/22/96 | 4/28/97 | 4/29/97 |
| Location | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 | S3500 | S3500 | C3501 | S3500 |
| Depth (ft) | | | | | | | | | | | | | |
| surface | 11.0 | 12.5 | 12.0 | 10.9 | 12.6 | 12 | 10.3 | 9.6 | 9.9 | 9.6 | 9.7 | 11.6 | 11.3 |
| 2 to 3 | | | 12.0 | 10.9 | | 12 | 10.3 | 9.6 | 9.8 | 9.6 | 9.7 | 11.5 | 11.3 |
| 5 to 6 | 11.1 | 12.6 | 12.0 | 11 | 12.6 | 12 | 10.3 | 9.6 | 9.8 | 9.6 | 9.6 | 11.6 | 11.2 |
| 8 to 9 | | | 12.0 | 11.1 | | 12 | 10.3 | 9.6 | 9.8 | 9.6 | 9.6 | 12.1 | 11.7 |
| 11 to 12 | 11.1 | 12.6 | 12.0 | 11.1 | 12.6 | 12 | 10.4 | 9.6 | 9.8 | 9.5 | 9.5 | 12.1 | 11.7 |
| 14 to 15 | 11.2 | 12.6 | 12.0 | 11.1 | 12.6 | 12 | 10.4 | 9.7 | 9.8 | 9.5 | 9.7 | 12.2 | 12.1 |
| 17 to 18 | | | 12.0 | 11.1 | | 12 | 10.6 | 9.7 | 9.8 | 9.5 | 9.7 | 12.2 | 12.2 |
| 20 to 21 | 11.1 | 12.6 | 12.0 | 11.1 | 12.6 | 12 | 10.6 | 9.7 | 9.9 | 9.5 | 9.7 | 12.2 | 12.2 |
| 24 to 25 | | | | 11.4 | | | 10.6 | 9.6 | 9.8 | 9.5 | 9.7 | 12.2 | 12.2 |
| 27 to 28 | 11.5 | 12.6 | 12.0 | 11.5 | 12.6 | 12 | 10.6 | 9.7 | 9.8 | 9.5 | 9.7 | 12.2 | 12.3 |

| Temperature (°C) | | | | | | | | | | | | | |
|------------------|---------|---------|---------|---------|---------|---------|--------|----------|----------|----------|----------|---------|---------|
| Date | 5/23/95 | 5/24/95 | 5/25/95 | 5/23/95 | 5/24/95 | 5/25/95 | 6/5/96 | 10/21/96 | 10/24/96 | 10/21/96 | 10/22/96 | 4/28/97 | 4/29/97 |
| Location | C3501 | C3501 | C3501 | S3500 | S3500 | S3500 | S3500 | C3501 | C3501 | S3500 | S3500 | C3501 | S3500 |
| Depth (ft) | | | | | | | | | | | | | |
| surface | 13.3 | 13.3 | 13.7 | 14 | 13.3 | 13.5 | 15 | 14.8 | 13.6 | 14.7 | 15.1 | 9.7 | 10.7 |
| 2 to 3 | | | 13.7 | 14 | | | 15 | 14.8 | 13.6 | 14.7 | 15.1 | 9.7 | 10.7 |
| 5 to 6 | 13.3 | 13.3 | 13.7 | 13.3 | 13.3 | 13.5 | 15 | 14.8 | 13.6 | 14.7 | 15 | 9.1 | 10.7 |
| 8 to 9 | | | 13.7 | 13.2 | | 13.5 | 14 | 14.6 | 13.6 | 14.7 | 14.7 | 8.4 | 8.5 |
| 11 to 12 | 13.3 | 13.3 | 13.7 | 13 | 13.3 | 13.5 | 14 | 14.5 | 13.6 | 14.4 | 14.5 | 8.2 | 8.4 |
| 14 to 15 | 13.3 | 13.3 | 13.7 | 13 | 13.3 | 13.5 | 14 | 14.5 | 13.6 | 14.4 | 14.3 | 8 | 8.4 |
| 17 to 18 | | | 13.7 | 13 | | 13.5 | 14 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 8.3 |
| 20 to 21 | 13.3 | 13.3 | 13.7 | 12.7 | 13.3 | 13.5 | 14 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 8.3 |
| 24 to 25 | | | 13.7 | 12.5 | | 13.5 | 13 | 14.4 | 13.6 | 14.3 | 14.2 | 7.8 | 8.3 |
| 27 to 28 | 13.3 | 13.3 | 13.7 | 12.2 | 13.3 | 13.5 | 13 | 14.4 | 13.6 | 14.4 | 14.2 | 7.9 | 8.3 |

Appendix C

In-Situ Water Quality Determinations

| Conductivity (µmhos/cm) | | | | | | | | | | | | |
|-------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|--------|--------|--------|
| Date | 5/23/95 | 5/24/95 | 5/25/95 | 5/26/95 | 5/27/95 | 5/28/95 | 5/29/95 | 5/30/95 | 5/31/95 | 6/1/95 | 6/2/95 | 6/3/95 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Depth (ft) | | | | | | | | | | | | |
| surface | 301 | 295 | 298 | 301 | 291 | 289 | 300 | 308 | 294 | 306 | 299 | 313 |
| 2 to 3 | | | 290 | 299 | | | 301 | 308 | 294 | 309 | 298 | 313 |
| 5 to 6 | 296 | 292 | 290 | 296 | 298 | 289 | 304 | 308 | 291 | 305 | 298 | 311 |
| 8 to 9 | | | 291 | 296 | | 290 | 297 | 306 | 294 | 305 | 297 | 303 |
| 11 to 12 | 289 | 289 | 292 | 295 | 301 | 290 | 305 | 305 | 298 | 301 | 294 | 303 |
| 14 to 15 | 305 | 293 | 291 | 296 | 300 | 292 | 300 | 305 | 294 | 304 | 292 | 301 |
| 17 to 18 | | | 294 | 297 | | 289 | 300 | 304 | 294 | 301 | 289 | 301 |
| 20 to 21 | 300 | 301 | 293 | 296 | 297 | 296 | 300 | 300 | 288 | 302 | 289 | 300 |
| 24 to 25 | | | 293 | 294 | | 294 | 300 | 300 | 289 | 300 | 289 | 300 |
| 27 to 28 | 306 | 301 | 292 | 294 | 297 | 280 | 302 | 300 | 294 | 300 | 289 | 298 |

| pH (s.u.) | | | | | | | | | | | | |
|------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|--------|--------|--------|
| Date | 5/23/95 | 5/24/95 | 5/25/95 | 5/26/95 | 5/27/95 | 5/28/95 | 5/29/95 | 5/30/95 | 5/31/95 | 6/1/95 | 6/2/95 | 6/3/95 |
| Location | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 | C3501 |
| Depth (ft) | | | | | | | | | | | | |
| surface | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 7.9 |
| 2 to 3 | | | 8.2 | 8.2 | | | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 7.9 |
| 5 to 6 | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 8.1 | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 7.9 |
| 8 to 9 | | | 8.2 | 8.2 | | 8.1 | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 7.9 |
| 11 to 12 | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 8.1 | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 8 |
| 14 to 15 | 8.2 | 8.2 | 8.2 | 8.2 | 8.1 | 8.1 | 8.1 | 8.1 | 8.2 | 8.2 | 8.2 | 8 |
| 17 to 18 | | | 8.2 | 8.2 | | 8.1 | 8.1 | 8 | 8.2 | 8.2 | 8.1 | 7.9 |
| 20 to 21 | 8.2 | 8.2 | 8.2 | 8.2 | 8.1 | 8.1 | 8.1 | 8 | 8.2 | 8.2 | 8.1 | 7.9 |
| 24 to 25 | | | 8.2 | 8.2 | | 8.1 | 8.1 | 8 | 8.2 | 8.2 | 8.1 | 7.9 |
| 27 to 28 | 8.2 | 8.1 | 8.1 | 8.2 | 8.1 | 8.1 | 8.1 | 8 | 8.1 | 8.3 | 8.1 | 8 |

7

ATTACHMENT 7

STORET SYSTEM RETRIEVAL FOR WHITING INTAKE



STORET SYSTEM RETRIEVAL FOR WHITING INTAKE
1993 - 1996

| DATE | TOT HARD CACO3 MG/L | CHROMIUM Cr, Tot UG/L | CHROMIUM Cr(VI)Total UG/L | CYANIDE Total MG/L | MANGANESE UG/L | NICKEL NI,TOT UG/L |
|-----------------|---------------------------|-----------------------------|---------------------------------|--------------------------|-------------------|--------------------------|
| 1/12/93 | 142 k | 4 k | 10 k | 0.005 | 95 k | 4 |
| 2/23/93 | 148 k | 4 k | 10 k | 0.005 | 8 k | 4 |
| 3/16/93 | 148 k | 4 k | 10 k | 0.005 | 16 k | 4 |
| 5/11/93 | 148 k | 4 k | 10 k | 0.005 k | 6 k | 4 |
| 8/2/93 | 146 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 9/8/93 | 137 k | 4 k | 10 | 0.009 k | 6 k | 8 |
| 10/27/93 | 137 k | 4 k | 10 k | 0.005 k | 6 k | 8 |
| 11/17/93 | 155 k | 4 k | 10 k | 0.005 k | 6 k | 8 |
| 2/2/94 | 166 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 3/2/94 | 154 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 3/15/94 | 152 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 4/26/94 | 148 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 6/1/94 | 134 k | 4 k | 10 | k | 6 k | 6 |
| 8/1/94 | 142 k | 4 k | 10 | 0.006 k | 6 k | 6 |
| 8/31/94 | 138 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 10/3/94 | 154 k | 4 k | 10 k | 0.005 | 8 k | 6 |
| 11/9/94 | 151 k | 4 k | 10 k | 0.005 | 72 k | 6 |
| 1/18/95 | 139 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 3/7/95 | 161 k | 4 | k | 0.005 | 8 k | 6 |
| 4/26/95 | 145 k | 4 | k | 0.005 | 6 k | 6 |
| 5/18/95 | 143 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 6/15/95 | 134 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 7/26/95 | 138 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 8/29/95 | 132 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 9/26/95 | 136 k | 4 k | 10 k | 0.005 k | 6 k | 6 |
| 10/24/95 | 148 k | 4 | k | 0.005 k | 6 k | 6 |
| 11/14/95 | 140 k | 4 k | 10 k | 0.005 | 14 k | 6 |
| 12/20/95 | 146 k | 4 k | 10 k | 0.005 | 8 k | 6 |
| 1/22/96 | 160 k | 3 k | 10 k | 0.005 | 10 k | 6 |
| 2/27/96 | 150 | 4.6 k | 10 k | 0.005 | 6.8 k | 6 |
| 3/25/96 | 158 | 4.3 k | 10 k | 0.005 | 13 k | 6 |
| 4/23/96 | 152 k | 6 | k | 0.005 | 17 k | 6 |
| 5/21/96 | 164 k | 3 k | 10 k | 0.005 | 8 k | 6 |
| 6/18/96 | 162 | k | 10 k | 0.005 | | |
| 7/16/96 | 168 k | 3 k | 10 k | 0.005 | 3.7 k | 6 |
| 8/20/96 | 120 k | 3 k | 10 k | 0.005 k | 3 k | 6 |
| 9/17/96 | 136 | 12 k | 10 k | 0.005 | 14 k | 6 |
| 10/22/96 | 142 | 5.4 k | 10 k | 0.005 | 3.5 k | 6 |
| 11/12/96 | 138 k | 5 k | 10 k | 0.005 | 4.8 k | 6 |
| 12/10/96 | 150 k | 5 k | 10 k | 0.005 | 8.3 k | 6 |
| Count(93-96) | 40 | 39 | 36 | 39 | 39 | 39 |
| ND(93-96) | 0 | 35 | 36 | 37 | 20 | 39 |
| Average | 146.55 | 4.26 | 10 | 0.0051 | 11.31 | 5.95 |
| Minimum | 120 | 3 | 10 | 0.005 | 3 | 4 |
| Maximum | 168 | 12 | 10 | 0.009 | 95 | 8 |
| Stand Dev | 10.4 | 1.4 | 0.0 | 0.00066 | 17.5 | 0.9 |
| CV | 0.07 | 0.33 | 0 | 0.128 | 1.55 | 0.14 |
| Geomean (93-96) | 146.2 | 0.54 | 0 | 0.0003 | 5.39 | 0 |

STORET SYSTEM RETRIEVAL FOR WHITING INTAKE
1993 - 1996

| DATE | SELENIUM SE,TOT UG/L | COPPER CU,TOT UG/L | SULFATE SO4-TOT MG/L | ARSENIC AS,TOT UG/L | BARIUM BA,TOT UG/L | BERYLIUM BE, TOT UG/L | IRON FE,TOT UG/L |
|-----------------|----------------------------|--------------------------|----------------------------|---------------------------|--------------------------|-----------------------------|------------------------|
| 1/12/93 | 1 | 13 | 30 | 1 | 23 k | 1.2 | 1500 |
| 2/23/93 | 1 | 17 | 27 | 0.9 | 21 | | 320 |
| 3/16/93 | 1 | 44 | 27 | 1 | 22 | | 480 |
| 5/11/93 | 1 | 34 | 24 | 0.8 | 21 | | 51 |
| 8/2/93 | 1 | 21 | 24 | 0.8 | 19 k | 1.2 | 25 |
| 9/8/93 | 1 | 28 | 25 | 0.7 | 20 | k | 20 |
| 10/27/93 | 1 | 19 | 25 | 1.1 | 22 | | 33 |
| 11/17/93 | 1 | 14 | 28 | 1 | 23 | | 70 |
| 2/2/94 | 1 | 11 | 30 | 0.8 | 21 | | 27 |
| 3/2/94 | 1 | 11 | 26 | 0.7 | 22 | | 89 |
| 3/15/94 | 1 | 14 | 28 | 0.8 | 21 | | 100 |
| 4/26/94 | 1 | 26 | 27 | 0.8 | 20 | | 56 |
| 6/1/94 | 1 | 20 | 26 | 0.7 | 21 | | 210 |
| 8/1/94 | 1 | 13 | | 0.9 | 20 | | 85 |
| 8/31/94 | 1 | 43 | 25 | 1 | 18 | k | 20 |
| 10/3/94 | 1 | 32 | 27 | 0.8 | 19 | | 200 |
| 11/9/94 | 1 | 23 | | 2 | 28 | | 1900 |
| 1/18/95 | 1 | 22 | 24 | 0.8 | 17 | | 150 |
| 3/7/95 | 1 | 20 | 28 | 1.1 | 21 | | 300 |
| 4/26/95 | 1 | 22 | 25 | 0.6 | 20 | | 180 |
| 5/18/95 | 1 | 17 | 26 | 0.9 | 21 | | 81 |
| 6/15/95 | 1 | 14 | 22 | 0.6 | 20 | | 24 |
| 7/26/95 | 1 | 17 | 24 | 0.9 | 20 | k | 20 |
| 8/29/95 | 1 | 21 | 22 | 0.8 | 17 | k | 20 |
| 9/26/95 | 1 | 44 | 23 | 1.1 | 20 | | 54 |
| 10/24/95 | 1 | 36 | 25 | 0.9 | 20 | | 240 |
| 11/14/95 | 1 | 7 | 27 | 1.1 | 18 | | 650 |
| 12/20/95 | 1 | 7 | 26 | 0.8 | 20 | | 240 |
| 1/22/96 | 1 | 4.8 | 30 | 0.9 | 21 | | 120 |
| 2/27/96 | 1 | 5.3 | 26 | 0.9 | 24 | | 260 |
| 3/25/96 | 2 | 5.3 | 27 | 1.5 | 24 | | 760 |
| 4/23/96 | 2 | 70 | 26 | 2 | 23 | | 660 |
| 5/21/96 | 2 | 100 | 26 k | 2 | 21 | | 180 |
| 6/18/96 | | | 22 | | | | |
| 7/16/96 | 2 | 55 | 23 k | 2 | 20 | | 58 |
| 8/20/96 | 2 | 40 | 22 k | 2 | 20 | | 24 |
| 9/17/96 | 2 | 36 | 23 | 2 | 24 | | 310 |
| 10/22/96 | 2 | 31 | 26 k | 2 | 20 | | 51 |
| 11/12/96 | 2 | 25 | 27 k | 2 | 19 | | 77 |
| 12/10/96 | 2 | 41 | 30 k | 2 | 21 | | 130 |
| Count(93-96) | 39 | 39 | 38 | 39 | 39 | 2 | 39 |
| ND(93-96) | 38 | 0 | 0 | 6 | 0 | 2 | 4 |
| Average | 1.23 | 26.24 | 25.76 | 1.15 | 20.82 | 1.2 | 251 |
| Minimum | 1 | 5 | 22 | 1 | 17 | 1.2 | 20.0 |
| Maximum | 2 | 100 | 30 | 2 | 28 | 1.2 | 1,900 |
| Stand Dev | 0.4 | 18.9 | 2.3 | 0.50 | 2.1 | 0 | 391 |
| CV | 0.35 | 0.72 | 0.09 | 0.44 | 0.10 | 0 | 2 |
| Geomean (93-96) | 0.033 | 20.9 | 25.6646 | 1.03 | 20.7 | 0 | 113 |

STORET SYSTEM RETRIEVAL FOR WHITING INTAKE
1993 - 1996

| DATE | IRON FE,DISS UG/L | LEAD PB,TOT UG/L | ZINC ZN,TOT UG/L | AMMONIA NH3+NH4- MG/L | CHLORIDE CL, MG/L | TDS mg/L | PHOSPHORUS P, Tot mg/L |
|-----------------|-------------------------|------------------------|------------------------|-----------------------------|-------------------------|-------------|------------------------------|
| 1/12/93 | | k 6 | 20 k | 0.1 | 14 | 172 | 0.07 |
| 2/23/93 | | k 6 k | 10 | 0.1 | 14 | 171 k | 0.03 |
| 3/16/93 | | k 6 k | 10 k | 0.1 | 18 | 193 k | 0.03 |
| 5/11/93 | | k 6 k | 10 k | 0.1 | 12 | 178 k | 0.03 |
| 8/2/93 | | k 6 k | 10 k | 0.1 | 11 | 188 k | 0.03 |
| 9/8/93 | | k 6 k | 10 k | 0.1 | 11 | 149 k | 0.03 |
| 10/27/93 | | k 6 k | 10 k | 0.1 | 12 | 159 k | 0.03 |
| 11/17/93 | | k 6 k | 10 k | 0.1 | 15 | 170 k | 0.03 |
| 2/2/94 | | k 6 k | 10 k | 0.1 | 17 | 183 k | 0.03 |
| 3/2/94 | | k 6 k | 10 k | 0.1 | 12 | 182 k | 0.03 |
| 3/15/94 | | k 6 k | 10 k | 0.1 | 14 | 181 k | 0.03 |
| 4/26/94 | | k 6 k | 10 k | 0.1 | 13 | 172 | 0.04 |
| 6/1/94 | | k 6 k | 10 k | 0.1 | 12 | 171 k | 0.03 |
| 8/1/94 | 20 | k 6 k | 10 k | 0.1 | 11 | 162 k | 0.03 |
| 8/31/94 | | k 6 k | 10 k | 0.1 | 11 | 153 k | 0.03 |
| 10/3/94 | | k 6 | 10 k | 0.1 | 13 | 175 k | 0.03 |
| 11/9/94 | 88 | 9 | 20 k | 0.1 | 15 | 179 | 0.06 |
| 1/18/95 | | k 6 k | 10 k | 0.1 | 11 | 187 k | 0.03 |
| 3/7/95 | | k 6 | 20 k | 0.1 | 14 | 185 k | 0.03 |
| 4/26/95 | | k 6 k | 10 k | 0.1 | 12 | 169 k | 0.03 |
| 5/18/95 | | k 6 k | 10 k | 0.1 | 13 | 180 k | 0.03 |
| 6/15/95 | | k 6 k | 10 k | 0.1 | 11 | 165 k | 0.03 |
| 7/26/95 | | k 6 k | 10 k | 0.1 | 12 | 165 k | 0.03 |
| 8/29/95 | | k 6 k | 10 k | 0.1 | 11 | 165 k | 0.03 |
| 9/26/95 | | k 6 k | 10 k | 0.1 | 13 | 174 k | 0.03 |
| 10/24/95 | | k 6 k | 10 k | 0.1 | 12 | 170 k | 0.03 |
| 11/14/95 | | k 6 | 10 k | 0.1 | 13 | 165 k | 0.03 |
| 12/20/95 | | k 6 k | 10 k | 0.1 | 12 | 174 k | 0.03 |
| 1/22/96 | 79 | k 6 | 6.5 | 0.1 | 20 | 190 k | 0.03 |
| 2/27/96 | 250 | k 6 | 6.8 k | 0.1 | 12 | 190 k | 0.03 |
| 3/25/96 | 310 | 6.7 | 9.2 | 0.1 | 18 | 189 k | 0.03 |
| 4/23/96 | 320 | 6.4 | 7.6 k | 0.1 | 13 | k | 0.03 |
| 5/21/96 | 50 | k 6 | 13 k | 0.1 | 12 | 174 k | 0.03 |
| 6/18/96 | | | k | 0.1 | 12 | 167 k | 0.03 |
| 7/16/96 | 20 | k 6 | 5 k | 0.1 | 12 | 175 k | 0.03 |
| 8/20/96 | 20 | k 6 k | 4.5 k | 0.1 | 10 | 168 k | 0.03 |
| 9/17/96 | 170 | k 6 k | 4.5 k | 0.1 | 12 | 178 k | 0.03 |
| 10/22/96 | 41 | k 6 k | 4.5 k | 0.1 | 15 | 171 k | 0.03 |
| 11/12/96 | 120 | k 6 k | 4.5 k | 0.1 | 13 | 175 k | 0.03 |
| 12/10/96 | 150 | 6.4 k | 4.5 k | 0.1 | 18 | 186 k | 0.03 |
| Count(93-96) | 13 | 39 | 39 | 40 | 40 | 39 | 40 |
| ND(93-96) | 3 | 35 | 28 | 37 | 0 | 0 | 37 |
| Average | 126 | 6 | 9.76 | 0.1 | 13.2 | 174.4 | 0.032 |
| Minimum | 20.0 | 6 | 4.5 | 0.1 | 10.0 | 149.0 | 0.03 |
| Maximum | 320 | 9 | 20 | 0.1 | 20.0 | 193.0 | 0.07 |
| Stand Dev | 108 | 0.49 | 3.67 | 0 | 2 | 10 | 0.0079 |
| CV | 0.86 | 0.08 | 0.38 | 0 | 0.17 | 0.06 | 0.247 |
| Geomean (93-96) | 78.0 | 0.79 | 3.81 | 0.0097 | 12.98 | 174.06 | 0.0029 |

STORET SYSTEM RETRIEVAL FOR WHITING INTAKE
1993 - 1996

| DATE | FLUORIDE F, Total mg/l |
|-----------------|------------------------------|
| 1/12/93 | 0.2 |
| 2/23/93 | 0.2 |
| 3/16/93 | 0.2 |
| 5/11/93 | 0.1 |
| 8/2/93 | 0.1 |
| 9/8/93 k | 0.1 |
| 10/27/93 | 0.2 |
| 11/17/93 | 0.2 |
| 2/2/94 | 0.1 |
| 3/2/94 k | 0.1 |
| 3/15/94 | 0.1 |
| 4/26/94 | 0.2 |
| 6/1/94 | 0.1 |
| 8/1/94 | 0.1 |
| 8/31/94 k | 0.1 |
| 10/3/94 | 0.2 |
| 11/9/94 | 0.2 |
| 1/18/95 | 0.1 |
| 3/7/95 | 0.2 |
| 4/26/95 | 0.1 |
| 5/18/95 | 0.1 |
| 6/15/95 | 0.1 |
| 7/26/95 | 0.1 |
| 8/29/95 | 0.2 |
| 9/26/95 | 0.2 |
| 10/24/95 | 0.2 |
| 11/14/95 | 0.2 |
| 12/20/95 | 0.1 |
| 1/22/96 | 0.2 |
| 2/27/96 | 0.1 |
| 3/25/96 | 0.2 |
| 4/23/96 | 0.1 |
| 5/21/96 | 0.1 |
| 6/18/96 | 0.1 |
| 7/16/96 | 0.1 |
| 8/20/96 | 0.1 |
| 9/17/96 | 0.2 |
| 10/22/96 | 0.2 |
| 11/12/96 | 0.2 |
| 12/10/96 | 0.2 |
| Count(93-96) | 40 |
| ND(93-96) | 3 |
| Average | 0.148 |
| Minimum | 0.10 |
| Maximum | 0.20 |
| Stand Dev | 0.0506 |
| CV | 0.343 |
| Geomean (93-96) | 0.1382 |

STORET SYSTEM RETRIEVAL FOR WHITING INTAKE
1993 - 1996

NOTE:

1. In accordance with IDEM Office of Water Management 327 IAC 2-1,2-1.5, and 15 Regulations (February 13, 1997), Geomean calculations for parameters containing below detection level values used the following formula:
(limit of detection) x (1- # of nondetects/ total # of values).
2. Data obtained from USGS/USEPA STORET database.
3. k = below methd detection level.

TMT/INTAKE/LAKE

171410 LM W
 41 40 45.0 087 29 17.0 2
 WHITING PUBLIC WATER INTAKE CRIB
 18089 INDIANA LAKE
 LAKE MICHIGAN 084991
 CALUMET-BURNS DITCH COMPLEX
 211ND 04040001004 0004.240 ON
 0000 FEET DEPTH

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|---------------------------------------|--------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 00010 WATER TEMP CENT WATER | | | 98 | 11.28400 | 52.51700 | 7.246900 | 26.0 | .0 | 82/01/26 | 91/01/16 |
| 00076 TURB TRBDIMTR HACH FTU WATER | | | 85 | 11.18000 | 192.4800 | 13.87400 | 88.0 | .7 | 82/01/26 | 90/11/27 |
| 00095 CONDUCTVY AT 25C MICROMHO WATER | | | 96 | 265.9000 | 2709.100 | 52.04900 | 400 | 116 | 82/01/26 | 90/06/05 |
| 00300 DO MG/L WATER | | | 14 | 10.85900 | 2.409600 | 1.552300 | 13.3 | 8.6 | 84/05/15 | 90/06/05 |
| 00310 BOO 5 DAY MG/L WATER | | | 81 | 1.023500 | .0088198 | .0939140 | 1.7 | 1.0 | 82/01/26 | 93/08/02 |
| 00335 COO LOWLEVEL MG/L WATER | | | 124 | 8.491900 | 9.845500 | 3.137800 | 20.0 | 4.0 | 82/01/26 | 93/11/17 |
| 00400 PH SU WATER | | | 89 | 7.917800 | .1007600 | .3174300 | 8.50 | 6.40 | 82/01/26 | 90/06/05 |
| 00403 PH LAB SU WATER | | | 125 | 7.864800 | .0665010 | .2578900 | 8.5 | 6.8 | 82/01/26 | 93/11/17 |
| 00410 T ALK CACO3 MG/L WATER | | | 125 | 113.2100 | 28.01600 | 5.293000 | 141 | 94 | 82/01/26 | 93/11/17 |
| 00500 RESIDUE TOTAL MG/L WATER | | | 122 | 191.0300 | 4580.900 | 67.68200 | 863 | 17 | 82/01/26 | 93/11/17 |
| 00530 RESIDUE TOT NFLT MG/L WATER | | | 45 | 28.06700 | 2878.600 | 53.65300 | 219 | 1 | 82/01/26 | 92/05/19 |
| 00556 OIL-GRSE FREON-GR MG/L WATER | | | 44 | 3.011400 | 2.083800 | 1.443600 | 6.70 | 1.00 | 82/01/26 | 89/12/12 |
| 00610 NH3+NH4- N TOTAL MG/L WATER | | | 124 | .1008900 | .0002276 | .0150860 | .200 | .010 | 82/01/26 | 93/11/17 |
| 00625 TOT KJEL N MG/L WATER | | | 124 | .2887900 | .0081529 | .0902930 | .700 | .100 | 82/01/26 | 93/11/17 |
| 00630 NO2&NO3 N-TOTAL MG/L WATER | | | 124 | .3741900 | .1300600 | .3606400 | 4.00 | .10 | 82/01/26 | 93/11/17 |
| 00665 PHOS-TOT MG/L P WATER | | | 124 | .0513710 | .0397290 | .1993200 | 2.250 | .030 | 82/01/26 | 93/11/17 |
| 00680 T ORG C C MG/L WATER | | | 38 | 3.165800 | 1.805000 | 1.343500 | 9.2 | 1.5 | 82/01/26 | 85/06/20 |
| 00720 CYANIDE CN-TOT MG/L WATER | | | 123 | .0054959 | .0000184 | .0042950 | .050 | .005 | 82/01/26 | 93/11/17 |
| 00900 TOT HARD CACO3 MG/L WATER | | | 125 | 143.8700 | 80.10500 | 8.950100 | 176 | 124 | 82/01/26 | 93/11/17 |
| 00910 CALCIUM CACO3 MG/L WATER | | | 80 | 94.52500 | 50.20700 | 7.085700 | 130.0 | 74.0 | 85/11/21 | 92/12/15 |
| 00916 CALCIUM CA-TOT MG/L WATER | | | 2 | 95.00000 | 2.000000 | 1.414200 | 96.0 | 94.0 | 93/08/02 | 93/11/17 |
| 00920 MGNSIUM. CACO3 MG/L WATER | | | 37 | 51.05400 | 126.3900 | 11.24200 | 76.0 | 20.0 | 85/11/21 | 89/05/23 |
| 00929 SODIUM NA,TOT MG/L WATER | | | 124 | 6.882200 | 1.696400 | 1.302500 | 14.00 | 4.80 | 82/01/26 | 93/08/02 |
| 00937 PTSSIUM K,TOT MG/L WATER | | | 43 | 1.704700 | .3533300 | .5944100 | 5.00 | 1.20 | 82/01/26 | 85/12/19 |
| 00940 CHLORIDE TOTAL MG/L WATER | | | 125 | 11.65200 | 3.936400 | 1.984100 | 22 | 5 | 82/01/26 | 93/11/17 |
| 00945 SULFATE SO4-TOT MG/L WATER | | | 122 | 24.95100 | 6.329000 | 2.515800 | 32 | 19 | 82/01/26 | 93/11/17 |
| 00951 FLUORIDE F,TOTAL MG/L WATER | | | 125 | .1360000 | .0028063 | .0529740 | .40 | .10 | 82/01/26 | 93/11/17 |
| 00955 SILICA DISOLVED MG/L WATER | | | 112 | 1.444700 | 8.006800 | 2.829600 | 30.0 | .1 | 82/06/10 | 93/11/17 |
| 01002 ARSENIC AS,TOT UG/L WATER | | | 123 | .9382100 | .0340280 | .1844700 | 2 | .6 | 82/01/26 | 93/08/02 |
| 01007 BARIUM BA,TOT UG/L WATER | | | 77 | 19.81800 | 2.808900 | 1.676000 | 23 | 10 | 86/05/22 | 93/08/02 |
| 01012 BERYLIUM BE,TOT UG/L WATER | | | 13 | 1.876900 | .0902570 | .3004300 | 2.00 | 1.20 | 89/03/28 | 93/08/02 |
| 01027 CADMIUM CD,TOT UG/L WATER | | | 125 | 2.000000 | .0000000 | .0000000 | 2 | .2 | 82/01/26 | 93/08/02 |
| 01032 CHROMIUM HEX-VAL UG/L WATER | | | 123 | 10.00000 | .0000000 | .0000000 | 10 | 10 | 82/01/26 | 93/11/17 |
| 01034 CHROMIUM CR,TOT UG/L WATER | | | 124 | 10.85500 | 110.8400 | 10.52800 | 120 | 4 | 82/01/26 | 93/08/02 |
| 01042 COPPER CU,TOT UG/L WATER | | | 125 | 8.832000 | 115.4200 | 10.74300 | 58 | 4 | 82/01/26 | 93/08/02 |
| 01045 IRON FE,TOT UG/L WATER | | | 122 | 277.0200 | 98996.00 | 314.6400 | 1500 | 20 | 82/01/26 | 93/08/02 |
| 01046 IRON FE,DISS UG/L WATER | | | 51 | 45.88200 | 956.7100 | 30.93100 | 170 | 20 | 86/05/22 | 92/03/25 |
| 01051 LEAD PB,TOT UG/L WATER | | | 125 | 8.224000 | 12.74000 | 3.569300 | 41 | 6 | 82/01/26 | 93/08/02 |
| 01055 MANGNESE MN UG/L WATER | | | 125 | 40.00800 | 25650.00 | 160.1600 | 1800.0 | 6.0 | 82/01/26 | 93/08/02 |

/NTRTMT/INTAKE/LAKE

171410 LM W
41 40 45.0 087 29 17.0 2
WHITING PUBLIC WATER INTAKE CRIB
18089 INDIANA LAKE
LAKE MICHIGAN 084991
CALUMET-BURNS DITCH COMPLEX
211ND 04040001004 0004.240 OM
0000 FEET DEPTH

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-------------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 01059 THALLIUM TL,TOTAL | UG/L WATER | | 13 | 18.76900 | 19.69300 | 4.437700 | 20 | 4 | 89/03/28 | 93/08/02 |
| 01067 NICKEL NI,TOTAL | UG/L WATER | | 125 | 9.320000 | 221.5400 | 14.88400 | 100 | 4 | 82/01/26 | 93/08/02 |
| 01077 SILVER AG,TOT | UG/L WATER | | 77 | 9.870100 | .2461500 | .4961300 | 10.0 | 8.0 | 86/05/22 | 93/08/02 |
| 01092 ZINC ZN,TOT | UG/L WATER | | 125 | 13.60000 | 36.12900 | 6.010800 | 30 | 10 | 82/01/26 | 93/08/02 |
| 01097 ANTIMONY SB,TOT | UG/L WATER | | 13 | .6692300 | .0056411 | .0751080 | .7 | .5 | 89/03/28 | 93/08/02 |
| 01147 SELENIUM SE,TOT | UG/L WATER | | 75 | .5226700 | .0425880 | .2063700 | 1 | .2 | 86/05/22 | 93/08/02 |
| 01503 ALPHA DISOLVED | PC/L WATER | | 14 | .6700000 | 2.663900 | 1.632200 | 6 | -.7 | 82/03/16 | 84/12/21 |
| 01504 ALPHA-D ERROR | PC/L WATER | | 14 | 1.146400 | .5974700 | .7729600 | 4 | .3 | 82/03/16 | 84/12/21 |
| 01505 ALPHA SUSP | PC/L WATER | | 14 | .6421400 | .9097800 | .9538300 | 3 | -.3 | 82/03/16 | 84/12/21 |
| 01506 ALPHA-S ERROR | PC/L WATER | | 14 | 1.294300 | .4281100 | .6543000 | 3 | .3 | 82/03/16 | 84/12/21 |
| 03503 BETA DISOLVED | PC/L WATER | | 14 | 3.576400 | 7.398100 | 2.719900 | 9 | .03 | 82/03/16 | 84/12/21 |
| 03504 BETA-D ERROR | PC/L WATER | | 14 | 1.792100 | .2870700 | .5357900 | 3 | .8 | 82/03/16 | 84/12/21 |
| 03505 BETA SUSP | PC/L WATER | | 14 | 2.328600 | 5.456000 | 2.335800 | 7 | -.1 | 82/03/16 | 84/12/21 |
| 03506 BETA-S ERROR | PC/L WATER | | 14 | 1.760000 | .2565500 | .5065000 | 3 | .7 | 82/03/16 | 84/12/21 |
| 31501 TOT COLI MFIMENDO | /100ML WATER | | 44 | 21803.00 | 1143E+07 | 106920.0 | 650000 | 10 | 82/01/26 | 86/02/20 |
| 31616 FEC COLI MFM-FCBR | /100ML WATER | | 70 | 78.97200 | 96885.00 | 311.2600 | 1900 | 10 | 82/01/26 | 88/03/30 |
| 31648 E.COLI MTEC-MF | NO/100ML WATER | | 50 | 316.6000 | 4490300 | 2119.000 | 15000 | 10 | 88/04/28 | 93/11/17 |
| 32101 DICLBRMT | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |

| | | | | | | | | | |
|----------------------------|----------------|-----|----------|----------|----------|--------|-------|----------|----------|
| 32102 CARENTET | TOTUG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32103 12DICLET | TOTUG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32104 BROMOFRM WHL-WTR | UG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32105 CLD1BRMT | TOTUG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32106 CHLRFORM | TOTUG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32730 PHENOLS TOTAL | UG/L WATER | 123 | 5.105700 | .4559600 | .6752500 | 10 | 5 | 82/01/26 | 93/11/17 |
| 32732 PHENOLS | DIS UG/L WATER | 8 | 4.200000 | .0000000 | .0000000 | 4.20 | 4.20 | 89/03/28 | 92/04/21 |
| 34010 TOLUENE | TOT UG/L WATER | 9 | 1.500000 | .0000000 | .0000000 | 1.50 | 1.50 | 89/03/28 | 92/11/17 |
| 34030 BENZENE | TOT UG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.00 | 1.00 | 89/03/28 | 92/11/17 |
| 34200 ACENAPHT HYLENE | TOTWJG/L WATER | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34205 ACENAPHT HENE | TOTWJG/L WATER | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34220 ANTHRACE NE | TOTWJG/L WATER | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34230 BENZBLU ORANT TO TAL | UG/L WATER | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34242 BENZO(K) FLUORANT | TOTWJG/L WATER | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34247 BENZO(A) PYRENE | TOTWJG/L WATER | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34259 DELTABHC | TOTUG/L WATER | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 34273 BIS2CHLO ROETHYLE | TOTWJG/L WATER | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34278 BIS2CHLO ROETHOXY | TOTWJG/L WATER | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34283 BIS2CHLO ROISOPRO | TOTWJG/L WATER | 9 | 4.500000 | .0000000 | .0000000 | 4.500 | 4.500 | 89/03/28 | 92/04/21 |
| 34292 NSB PHTH TOTAL | UG/L WATER | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34301 CHLOROBE NZENE | TOTWJG/L WATER | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |

171410 LM W
41 40 45.0 057 29 17.0 2
WHITING PUBLIC WATER INTAKE CRIB
18089 INDIANA LAKE
LAKE MICHIGAN 084991
CALUMET-BURNS DITCH COMPLEX
211ND 04040001004 0004.240 ON
0000 FEET DEPTH

/NTRTMT/INTAKE/LAKE

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-------------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 34320 CHRYSENE | TOTWJG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34336 DIETHYLP HTHALATE | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34341 DIMETHYL PHTHALAT | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34346 12DIPHEN YLHYDRAZ | TOTWJG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34376 FLUORANT HENE | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34381 FLUORENE | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34386 HEXACHLO ROCYCLOP | TOTWJG/L WATER | | 10 | 4.600000 | 3.600000 | 1.897400 | 10.000 | 4.000 | 89/03/28 | 92/11/17 |
| 34396 HEXACHLO ROETHANE | TOTWJG/L WATER | | 10 | 4.600000 | 3.600000 | 1.897400 | 10.000 | 4.000 | 89/03/28 | 92/11/17 |
| 34403 INDENO(1 23CD)PYR | TOTWJG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34408 ISPHRONE | TOTUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34423 METHYLEN ECHLORID | TOTWJG/L WATER | | 9 | 6.000000 | 9.000000 | 3.000000 | 14.000 | 5.000 | 89/03/28 | 92/11/17 |
| 34428 NITROSOO IPROPYLE | TOTWJG/L WATER | | 10 | 6.400000 | 1.600000 | 1.264900 | 10.000 | 6.000 | 89/03/28 | 92/11/17 |
| 34447 NITROBEN ZENE | TOTWJG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34461 PHENANTH RENE | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/04/21 |
| 34469 PYRENE | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34475 TETRACHL OROETHYL | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34488 TRICHLOR OFLUOROM | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34496 11DICHLO ROETHANE | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34501 11DICHLO ROETHYLE | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34506 111TRICH LOROETHA | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34511 112TRICH LOROETHA | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34516 1122TETR ACHLOROE | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34521 BENZO(GH I)PERYLE | TOTWJG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34526 BENZO(A) ANTHRACE | TOTWJG/L WATER | | 10 | 3.700000 | 4.900000 | 2.213600 | 10.000 | 3.000 | 89/03/28 | 92/11/17 |
| 34536 12DICHLO ROBENZEN | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34541 12DICHLO ROPROPAN | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34546 12DICHLO ROETHENE | TOTWJG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34551 124TRICH LOROENZ | TOTWJG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34556 DIBENZ(A H)ANTHRA | TOTWJG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34566 13DICHLO ROBENZEN | TOTWJG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34571 14DICHLO ROBENZEN | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34581 2CHLOROM APHTHALE | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34586 2CHLOROP HENOL | TOTWJG/L WATER | | 10 | 4.420000 | 3.844100 | 1.960600 | 10.000 | 3.800 | 89/03/28 | 92/11/17 |
| 34591 2NITROPH ENOL | TOTWJG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34596 DINOCTPH | TOTUG/L WATER | | 10 | 16.75000 | 1035.000 | 32.17200 | 98.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34601 24DICHLO ROPHENOL | TOTWJG/L WATER | | 10 | 5.320000 | 2.704100 | 1.644400 | 10.000 | 4.800 | 89/03/28 | 92/11/17 |
| 34606 24DIMETH YLPHENOL | TOTWJG/L WATER | | 10 | 5.320000 | 2.704100 | 1.644400 | 10.000 | 4.800 | 89/03/28 | 92/11/17 |
| 34611 24DINITR OTOLUENE | TOTWJG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34616 24DINITR OPHENOL | TOTWJG/L WATER | | 10 | 3.940000 | 54.75600 | 7.399700 | 25.000 | 1.600 | 89/03/28 | 92/11/17 |

/NTRTMT/INTAKE/LAKE

171410 LM W
 41 40 45.0 087 29 17.0 2
 WHITING PUBLIC WATER INTAKE CRIB
 18089 INDIANA LAKE
 LAKE MICHIGAN 084991
 CALUMET-BURNS DITCH COMPLEX
 211ND
 0000 FEET DEPTH

04040001004 0004.240 ON

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|--------------------------|--------------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 34621 246TRICH LOROPHEN | TOTWUG/L WATER | | 10 | 6.580000 | 1.444000 | 1.201700 | 10.000 | 6.200 | 89/03/28 | 92/11/17 |
| 34626 260IN1TR OTOLUENE | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34636 4BROMOPH ENYLPHEN | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34641 4CHLOROP HENYLPHE | TOTWUG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34646 4NITROPH ENOL | TOTWUG/L WATER | | 10 | 7.360000 | 38.41600 | 6.198100 | 25.000 | 5.400 | 89/03/28 | 92/11/17 |
| 34696 NAPHTHALE NE | T OTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34699 T1,3-DCP | TOT WAT UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34704 C1,3-DCP | TOT WAT UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34705 C1,3-DCP DISS WAT | UG/L WATER | | 1 | 1.000000 | | | 1.000 | 1.000 | 89/03/28 | 89/03/28 |
| 39032 PCP | TOT UG/L WATER | | 10 | 2.620000 | 6.724000 | 2.593100 | 10.000 | 1.800 | 89/03/28 | 92/11/17 |
| 39100 B2ETHHXL PHTHALAT | TOT UG/L WATER | | 10 | 23.18000 | 1450.300 | 38.08300 | 110.000 | 1.500 | 89/03/28 | 92/11/17 |
| 39110 DNB PHTH TOTAL | UG/L WATER | | 10 | 1.370000 | .9023300 | .9499100 | 4.000 | 1.000 | 89/03/28 | 92/11/17 |
| 39180 TRICHLOR ETHYLENE | TOT UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 39330 ALDRIN | TOT UG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 39337 ALPHABHC | TOTUG/L WATER | | 10 | .0100000 | .0000000 | .0000000 | .010 | .010 | 89/03/28 | 92/11/17 |
| 39338 BETA BHC | TOTUG/L WATER | | 10 | .0300000 | .0000000 | .0000000 | .030 | .030 | 89/03/28 | 92/11/17 |
| 39340 GAMMABHC LINDANE | TOT.UG/L WATER | | 10 | .0100000 | .0000000 | .0000000 | .010 | .010 | 89/03/28 | 92/11/17 |
| 39350 CHLRDANE TECH&MET | TOT UG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39360 DDD WHL SMPL | UG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39365 DDE WHL SMPL | UG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39370 DDT WHL SMPL | UG/L WATER | | 10 | .1000000 | .0000000 | .0000000 | .100 | .100 | 89/03/28 | 92/11/17 |
| 39380 DIELDRIH | TOTUG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39388 ENDOSULN WHL SMPL | UG/L WATER | | 10 | .0400000 | .0000000 | .0000000 | .040 | .040 | 89/03/28 | 92/11/17 |
| 39400 ENDRIN | TOT UG/L WATER | | 10 | .0800000 | .0000000 | .0000000 | .080 | .080 | 89/03/28 | 92/11/17 |
| 39410 TOXAPHEN | TOTUG/L WATER | | 10 | 2.000000 | .0000000 | .0000000 | 2.000 | 2.000 | 89/03/28 | 92/11/17 |
| 39420 HPCHLREP | TOTUG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 39480 MTHXYCLR WHL SMPL | UG/L WATER | | 10 | .2000000 | .0000000 | .0000000 | .200 | .200 | 89/03/28 | 92/11/17 |
| 39488 PCB-1221 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39492 PCB-1232 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39496 PCB-1242 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39500 PCB-1248 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39504 PCB-1254 | TOTUG/L WATER | | 10 | .8000000 | .0666670 | .2582000 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 39508 PCB-1260 | TOTUG/L WATER | | 10 | .8000000 | .0666670 | .2582000 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 39700 HCB | TOT UG/L WATER | | 10 | 7.180000 | 39.20400 | 6.261300 | 25.000 | 5.200 | 89/03/28 | 92/11/17 |
| 39702 HEXCLBD | TOT UG/L WATER | | 10 | 3.700000 | 4.900000 | 2.213600 | 10.00 | 3.00 | 89/03/28 | 92/11/17 |
| 47501 WEATHER SAMPLING | CODE WATER | | 61 | 29512.00 | 3608E+05 | 18995.00 | 81834 | 10014 | 86/05/22 | 92/07/27 |
| 70300 RESIDUE DISS-180 C | MG/L WATER | | 79 | 171.7900 | 1076.600 | 32.81100 | 430 | 82 | 85/12/19 | 93/11/17 |
| 71900 MERCURY HG,TOTAL | UG/L WATER | | 125 | .1200000 | .0390320 | .1975700 | 2.3 | .1 | 82/01/26 | 93/08/02 |

171410 LM W
 41 40 45.0 087 29 17.0 2
 WHITING PUBLIC WATER INTAKE CRIB
 18089 INDIANA LAKE
 LAKE MICHIGAN 084991
 CALUMET-BURNS DITCH COMPLEX
 211ND
 0000 FEET DEPTH

04040001004 0004.240 OM

/NTRTMT/INTAKE/LAKE

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|----------------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 74041 WQF SAMPLE | UPDATED WATER | | 88 | 902100.0 | 5189E+05 | 22780.00 | 940518 | 861001 | 85/08/22 | 93/11/17 |
| 77089 ANILINE TOTAL | UG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 77147 BNZYLALC TOTAL | UG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 77247 BENZOICA TOTAL | UG/L WATER | | 10 | 2.530000 | 6.889000 | 2.624700 | 10.000 | 1.700 | 89/03/28 | 92/11/17 |
| 77416 2MNAPTHA TOTAL | UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 77571 CARBAZOL TOTAL | UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 77687 24STCLPH TOTAL | UG/L WATER | | 10 | 4.840000 | 50.17600 | 7.083500 | 25.000 | 2.600 | 89/03/28 | 92/11/17 |
| 78113 ETH BENZ WH WTR | UG/L WATER | | 9 | 2.000000 | .0000000 | .0000000 | 2.00 | 2.00 | 89/03/28 | 92/11/17 |
| 78300 3-NITRO ANILINE | TOT UG/L WATER | | 10 | 4.750000 | 50.62500 | 7.115100 | 25.000 | 2.500 | 89/03/28 | 92/11/17 |
| 81302 DIBENZO FURAN | TOT UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 81551 XYLENE | TOT UG/L WATER | | 9 | 9.000000 | .0000000 | .0000000 | 9.000 | 9.000 | 89/03/28 | 92/11/17 |
| 81552 ACETONE | TOT UG/L WATER | | 9 | 20.00000 | .0000000 | .0000000 | 20.000 | 20.000 | 89/03/28 | 92/11/17 |
| 81595 MTH ETH KETONE | TOT UG/L WATER | | 9 | 8.422200 | 43.80500 | 6.618500 | 26.000 | 6.000 | 89/03/28 | 92/11/17 |
| 81596 MTHISOSU KETONE | TOT UG/L WATER | | 9 | 3.000000 | .0000000 | .0000000 | 3.000 | 3.000 | 89/03/28 | 92/11/17 |
| 81648 PCB 1016 /1242 | TOT UG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 81649 PCB-1262 TOT | UG/L WATER | | 8 | .7500000 | .0714290 | .2672600 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 82623 ENDOSLFM -SO4 TOT | REC UG/L WATER | | 10 | .1400000 | .0060001 | .0774600 | .2 | .05 | 89/03/28 | 92/11/17 |
| 82624 ENDOSLFM BETA TOT | REC UG/L WATER | | 10 | .0800000 | .0006666 | .0258200 | .1 | .05 | 89/03/28 | 92/11/17 |
| 85810 12DICLR ETHL TRM EFF | UG/L WATER | | 1 | 1.000000 | | | 1.000 | 1.000 | 89/03/28 | 89/03/28 |

1STORET RETRIEVAL DATE 94/06/28

PGM=INVENT
GROSS

PAGE: 6

0 1 TOTAL STATIONS PROCESSED

| | STA BEG | STA END | # OF OBS | # OF SAMPLE | STA END-PERIOD OF RECD IN YRS | | | |
|-------|---------|---------|----------|-------------|-------------------------------|-----|----|-----|
| | | | | | =0 | <.5 | <3 | >=3 |
| <1975 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1975 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1976 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1977 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1978 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1979 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1980 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1981 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1982 | 1 | 0 | 427 | 12 | 0 | 0 | 0 | 0 |
| 1983 | 0 | 0 | 407 | 11 | 0 | 0 | 0 | 0 |
| 1984 | 0 | 0 | 501 | 14 | 0 | 0 | 0 | 0 |
| 1985 | 0 | 0 | 443 | 12 | 0 | 0 | 0 | 0 |
| 1986 | 0 | 0 | 474 | 12 | 0 | 0 | 0 | 0 |
| 1987 | 0 | 0 | 452 | 11 | 0 | 0 | 0 | 0 |
| 1988 | 0 | 0 | 511 | 13 | 0 | 0 | 0 | 0 |
| 1989 | 0 | 0 | 858 | 12 | 0 | 0 | 0 | 0 |
| 1990 | 0 | 0 | 708 | 11 | 0 | 0 | 0 | 0 |
| 1991 | 0 | 0 | 599 | 11 | 0 | 0 | 0 | 0 |
| 1992 | 0 | 0 | 500 | 10 | 0 | 0 | 0 | 0 |
| 1993 | 0 | 1 | 122 | 7 | 0 | 0 | 0 | 1 |
| 1994 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| TOTAL | 1 | 1 | 6002 | 136 | 0 | 0 | 0 | 1 |

1 TOTAL STATIONS PROCESSED

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|--------------------------------------|--------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 00010 WATER TEMP CENT WATER | | | 98 | 11.28400 | 52.51700 | 7.246900 | 26.0 | .0 | 82/01/26 | 91/01/16 |
| 00076 TURB TRSDMTR HACH FTU WATER | | | 85 | 11.18000 | 192.4800 | 13.87400 | 88.0 | .7 | 82/01/26 | 90/11/27 |
| 00095 CNDUCTVY AT 25C MICROMHO WATER | | | 96 | 265.9000 | 2709.100 | 52.04900 | 400 | 116 | 82/01/26 | 90/06/05 |
| 00300 DO MG/L WATER | | | 14 | 10.85900 | 2.409600 | 1.552300 | 13.3 | 8.6 | 84/05/15 | 90/06/05 |
| 00310 BOO 5 DAY MG/L WATER | | | 81 | 1.023500 | .0088198 | .0939140 | 1.7 | 1.0 | 82/01/26 | 93/08/02 |
| 00335 COO LOWLEVEL MG/L WATER | | | 124 | 8.491900 | 9.845500 | 3.137800 | 20.0 | 4.0 | 82/01/26 | 93/11/17 |
| 00400 PH SU WATER | | | 89 | 7.917800 | .1007600 | .3174300 | 8.50 | 6.40 | 82/01/26 | 90/06/05 |
| 00403 PH LAB SU WATER | | | 125 | 7.864800 | .0665010 | .2578800 | 8.5 | 6.8 | 82/01/26 | 93/11/17 |
| 00410 T ALK CACO3 MG/L WATER | | | 125 | 113.2100 | 28.01600 | 5.293000 | 141 | 94 | 82/01/26 | 93/11/17 |
| 00500 RESIDUE TOTAL MG/L WATER | | | 122 | 191.0300 | 4580.900 | 67.68200 | 863 | 17 | 82/01/26 | 93/11/17 |
| 00530 RESIDUE TOT NFLT MG/L WATER | | | 45 | 28.06700 | 2878.600 | 53.65300 | 219 | 1 | 82/01/26 | 92/05/19 |
| 00556 OIL-GRSE FREON-GR MG/L WATER | | | 44 | 3.011400 | 2.083800 | 1.443600 | 6.70 | 1.00 | 82/01/26 | 89/12/12 |
| 00610 NH3+NH4- N TOTAL MG/L WATER | | | 124 | .1008900 | .0002276 | .0150860 | .200 | .010 | 82/01/26 | 93/11/17 |
| 00625 TOT KJEL N MG/L WATER | | | 124 | .2887900 | .0081529 | .0902930 | .700 | .100 | 82/01/26 | 93/11/17 |
| 00630 NO2&NO3 N-TOTAL MG/L WATER | | | 124 | .3741900 | .1300600 | .3606400 | 4.00 | .10 | 82/01/26 | 93/11/17 |
| 00665 PHOS-TOT MG/L P WATER | | | 124 | .0513710 | .0397290 | .1993200 | 2.250 | .030 | 82/01/26 | 93/11/17 |
| 00680 T ORG C MG/L WATER | | | 38 | 3.165800 | 1.805000 | 1.343500 | 9.2 | 1.5 | 82/01/26 | 85/06/20 |
| 00720 CYANIDE CN-TOT MG/L WATER | | | 123 | .0054959 | .0000184 | .0042950 | .050 | .005 | 82/01/26 | 93/11/17 |
| 00900 TOT HARD CACO3 MG/L WATER | | | 125 | 143.8700 | 80.10500 | 8.950100 | 176 | 124 | 82/01/26 | 93/11/17 |
| 00910 CALCIUM CACO3 MG/L WATER | | | 80 | 94.52500 | 50.20700 | 7.085700 | 130.0 | 74.0 | 85/11/21 | 92/12/15 |
| 00916 CALCIUM CA-TOT MG/L WATER | | | 2 | 95.00000 | 2.000000 | 1.414200 | 96.0 | 94.0 | 93/08/02 | 93/11/17 |
| 00920 MGNSIUM CACO3 MG/L WATER | | | 37 | 51.05400 | 126.3900 | 11.24200 | 76.0 | 20.0 | 85/11/21 | 89/05/23 |
| 00929 SODIUM NA,TOT MG/L WATER | | | 124 | 6.882200 | 1.696400 | 1.302500 | 14.00 | 4.80 | 82/01/26 | 93/08/02 |
| 00937 PTSSIUM K,TOT MG/L WATER | | | 43 | 1.704700 | .3533300 | .5944100 | 5.00 | 1.20 | 82/01/26 | 85/12/19 |
| 00940 CHLORIDE TOTAL MG/L WATER | | | 125 | 11.65200 | 3.936400 | 1.984100 | 22 | 5 | 82/01/26 | 93/11/17 |
| 00945 SULFATE SO4-TOT MG/L WATER | | | 122 | 24.95100 | 6.329000 | 2.515800 | 32 | 19 | 82/01/26 | 93/11/17 |
| 00951 FLUORIDE F,TOTAL MG/L WATER | | | 125 | .1360000 | .0028063 | .0529740 | .40 | .10 | 82/01/26 | 93/11/17 |
| 00955 SILICA DISOLVED MG/L WATER | | | 112 | 1.444700 | 8.006800 | 2.829600 | 30.0 | .1 | 82/06/10 | 93/11/17 |
| 01002 ARSENIC AS,TOT UG/L WATER | | | 123 | .9382100 | .0340280 | .1844700 | 2 | .6 | 82/01/26 | 93/08/02 |
| 01007 BARIUM BA,TOT UG/L WATER | | | 77 | 19.81800 | 2.808900 | 1.676000 | 23 | 10 | 86/05/22 | 93/08/02 |
| 01012 BERYLIUM BE,TOT UG/L WATER | | | 13 | 1.876900 | .0902570 | .3004300 | 2.00 | 1.20 | 89/03/28 | 93/08/02 |
| 01027 CADMIUM CD,TOT UG/L WATER | | | 125 | 2.000000 | .0000000 | .0000000 | 2 | 2 | 82/01/26 | 93/08/02 |
| 01032 CHROMIUM HEX-VAL UG/L WATER | | | 123 | 10.00000 | .0000000 | .0000000 | 10 | 10 | 82/01/26 | 93/11/17 |
| 01034 CHROMIUM CR,TOT UG/L WATER | | | 124 | 10.85500 | 110.8400 | 10.52800 | 120 | 4 | 82/01/26 | 93/08/02 |
| 01042 COPPER CU,TOT UG/L WATER | | | 125 | 8.832000 | 115.4200 | 10.74300 | 58 | 4 | 82/01/26 | 93/08/02 |
| 01045 IRON FE,TOT UG/L WATER | | | 122 | 277.0200 | 98996.00 | 314.6400 | 1500 | 20 | 82/01/26 | 93/08/02 |
| 01046 IRON FE,DISS UG/L WATER | | | 51 | 45.88200 | 956.7100 | 30.93100 | 170 | 20 | 86/05/22 | 92/03/25 |
| 01051 LEAD PB,TOT UG/L WATER | | | 125 | 8.224000 | 12.74000 | 3.569300 | 41 | 6 | 82/01/26 | 93/08/02 |
| 01055 MANGNESE MN UG/L WATER | | | 125 | 40.00800 | 25650.00 | 160.1600 | 1800.0 | 6.0 | 82/01/26 | 93/08/02 |
| 01059 THALLIUM TL,TOTAL UG/L WATER | | | 13 | 18.76900 | 19.69300 | 4.437700 | 20 | 4 | 89/03/28 | 93/08/02 |
| 01067 NICKEL NI,TOTAL UG/L WATER | | | 125 | 9.320000 | 221.5400 | 14.88400 | 100 | 4 | 82/01/26 | 93/08/02 |
| 01077 SILVER AG,TOT UG/L WATER | | | 77 | 9.870100 | .2461500 | .4961300 | 10.0 | 8.0 | 86/05/22 | 93/08/02 |

0 1 TOTAL STATIONS PROCESSED

| 0 | PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-------|-------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 01092 | ZINC ZN,TOT | UG/L WATER | | 125 | 13.60000 | 36.12900 | 6.010800 | 30 | 10 | 82/01/26 | 93/08/02 |
| 01097 | ANTIMONY SB,TOT | UG/L WATER | | 13 | .6692300 | .0056411 | .0751080 | .7 | .5 | 89/03/28 | 93/08/02 |
| 01147 | SELENIUM SE,TOT | UG/L WATER | | 75 | .5226700 | .0425880 | .2063700 | 1 | .2 | 86/05/22 | 93/08/02 |
| 01503 | ALPHA DISOLVED | PC/L WATER | | 14 | .6700000 | 2.663900 | 1.632200 | 6 | -.7 | 82/03/16 | 84/12/21 |
| 01504 | ALPHA-D ERROR | PC/L WATER | | 14 | 1.146400 | .5974700 | .7729600 | 4 | .3 | 82/03/16 | 84/12/21 |
| 01505 | ALPHA SUSP | PC/L WATER | | 14 | .6421400 | .9097800 | .9538300 | 3 | -.3 | 82/03/16 | 84/12/21 |
| 01506 | ALPHA-S ERROR | PC/L WATER | | 14 | 1.294300 | .4281100 | .6543000 | 3 | .3 | 82/03/16 | 84/12/21 |
| 03503 | BETA DISOLVED | PC/L WATER | | 14 | 3.576400 | 7.398100 | 2.719900 | 9 | .03 | 82/03/16 | 84/12/21 |
| 03504 | BETA-D ERROR | PC/L WATER | | 14 | 1.792100 | .2870700 | .5357900 | 3 | .8 | 82/03/16 | 84/12/21 |
| 03505 | BETA SUSP | PC/L WATER | | 14 | 2.328600 | 5.456000 | 2.335800 | 7 | -1 | 82/03/16 | 84/12/21 |
| 03506 | BETA-S ERROR | PC/L WATER | | 14 | 1.760000 | .2565500 | .5065000 | 3 | .7 | 82/03/16 | 84/12/21 |
| 31501 | TOT COLI MFIMENDO | /100ML WATER | | 44 | 21803.00 | 1143E+07 | 106920.0 | 650000 | 10 | 82/01/26 | 86/02/20 |
| 31616 | FEC COLI MFH-FCBR | /100ML WATER | | 70 | 78.97200 | 96885.00 | 311.2600 | 1900 | 10 | 82/01/26 | 88/03/30 |
| 31648 | E.COLI MTEC-MF | NO/100ML WATER | | 50 | 316.6000 | 4490300 | 2119.000 | 15000 | 10 | 88/04/28 | 93/11/17 |
| 32101 | DICLBRMT | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32102 | CARENTEY | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32103 | 12DICLET | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32104 | BROMOFRM WHL-WTR | UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32105 | CLDIBRMT | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32106 | CHLRFORM | TOTUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.0 | 1.0 | 89/03/28 | 92/11/17 |
| 32730 | PHENOLS TOTAL | UG/L WATER | | 123 | 5.105700 | .4559600 | .6752500 | 10 | 5 | 82/01/26 | 93/11/17 |
| 32732 | PHENOLS | DIS UG/L WATER | | 8 | 4.200000 | .0000000 | .0000000 | 4.20 | 4.20 | 89/03/28 | 92/04/21 |
| 34010 | TOLUENE | TOT UG/L WATER | | 9 | 1.500000 | .0000000 | .0000000 | 1.50 | 1.50 | 89/03/28 | 92/11/17 |
| 34030 | BENZENE | TOT UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.00 | 1.00 | 89/03/28 | 92/11/17 |
| 34200 | ACENAPHT HYLENE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34205 | ACENAPHT HENE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34220 | ANTHRACE NE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34230 | BENZ5FLU ORANT TO | TAL UG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34242 | BENZO(K) FLUORANT | TOTWUG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34247 | BENZO(A) PYRENE | TOTWUG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34259 | DELTA8HC | TOTUG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 34273 | BIS2CHLO ROETHYLE | TOTWUG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34278 | BIS2CHLO ROETHOXY | TOTWUG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34283 | BIS2CHLO ROISOPRO | TOTWUG/L WATER | | 9 | 4.500000 | .0000000 | .0000000 | 4.500 | 4.500 | 89/03/28 | 92/04/21 |
| 34292 | NBB PHTH TOTAL | UG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34301 | CHLOROSE NZENE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34320 | CHRYSENE | TOTWUG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34336 | DIETHYLP HTHALATE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34341 | DIMETHYL PHTHALAT | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34346 | 12DIPHEM YLHYDRAZ | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34376 | FLUORANT HENE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34381 | FLUORENE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |

1 TOTAL STATIONS PROCESSED

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-------------------------|-----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 34386 HEXACHLO ROCYCLOP | TOTWUG/L WATER | | 10 | 4.600000 | 3.600000 | 1.897400 | 10.000 | 4.000 | 89/03/28 | 92/11/17 |
| 34396 HEXACHLO ROETHANE | TOTWUG/L WATER | | 10 | 4.600000 | 3.600000 | 1.897400 | 10.000 | 4.000 | 89/03/28 | 92/11/17 |
| 34403 INDENO(1 23CD)PYR | TOTWUG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34408 ISPHRONE | TOTUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34423 METHYLEN ECHLORID | TOTWUG/L WATER | | 9 | 6.000000 | 9.000000 | 3.000000 | 14.000 | 5.000 | 89/03/28 | 92/11/17 |
| 34428 NITROSOD IPROPYLA | TOTWUG/L WATER | | 10 | 6.400000 | 1.600000 | 1.264900 | 10.000 | 6.000 | 89/03/28 | 92/11/17 |
| 34447 NITROBEN ZENE | TOTWUG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 34461 PHENANTH RENE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/04/21 |
| 34469 PYRENE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34475 TETRACHL ORDETHYL | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34488 TRICHLOR OFLUOROM | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34496 11DICHLO ROETHANE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34501 11DICHLO ROETHYLE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34506 111TRICH LOROETHA | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34511 112TRICH LOROETHA | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34516 1122TETR ACHLOROE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34521 BENZO(GH I)PERYLE | TOTWUG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34526 BENZO(A) ANTHRACE | TOTWUG/L WATER | | 10 | 3.700000 | 4.900000 | 2.213600 | 10.000 | 3.000 | 89/03/28 | 92/11/17 |
| 34536 12DICHLO ROENZEN | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34541 12DICHLO ROPROPAN | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34546 12DICHLO ROETHENE | TOTWUG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34551 124TRICH LOROBENZ | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34556 DIBENZ(A H)ANTHRA | TOTWUG/L WATER | | 10 | 4.150000 | 4.225000 | 2.055500 | 10.000 | 3.500 | 89/03/28 | 92/11/17 |
| 34566 13DICHLO ROENZEN | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34571 14DICHLO ROENZEN | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34581 2CHLORON APHTHALE | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34586 2CHLOROP HENOL | TOTWUG/L WATER | | 10 | 4.420000 | 3.844100 | 1.960600 | 10.000 | 3.800 | 89/03/28 | 92/11/17 |
| 34591 2NITROPH ENOL | TOTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 4596 DINOCTPH | TOTUG/L WATER | | 10 | 16.75000 | 1035.000 | 32.17200 | 98.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34601 24DICHLO ROPHENOL | TOTWUG/L WATER | | 10 | 5.320000 | 2.704100 | 1.644400 | 10.000 | 4.800 | 89/03/28 | 92/11/17 |
| 34606 24DIMETH YLPHENOL | TOTWUG/L WATER | | 10 | 5.320000 | 2.704100 | 1.644400 | 10.000 | 4.800 | 89/03/28 | 92/11/17 |
| 34611 24DINITR OTOLUENE | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34616 24DINITR OPHENOL | TOTWUG/L WATER | | 10 | 3.940000 | 54.75600 | 7.399700 | 25.000 | 1.600 | 89/03/28 | 92/11/17 |
| 34621 246TRICH LOROPHEN | TOTWUG/L WATER | | 10 | 6.580000 | 1.444000 | 1.201700 | 10.000 | 6.200 | 89/03/28 | 92/11/17 |
| 34626 26DINITR OTOLUENE | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34636 4BROMOPH ENYLPHEN | TOTWUG/L WATER | | 10 | 2.800000 | 6.400000 | 2.529800 | 10.000 | 2.000 | 89/03/28 | 92/11/17 |
| 34641 4CHLOROP HENYLPHE | TOTWUG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 34646 4NITROPH ENOL | TOTWUG/L WATER | | 10 | 7.360000 | 38.41600 | 6.198100 | 25.000 | 5.400 | 89/03/28 | 92/11/17 |
| 34696 NAPHTHALE NE | T OTWUG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34699 T1,3-DCP TOT WAT | UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34704 C1,3-DCP TOT WAT | UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 34705 C1,3-DCP DISS WAT | UG/L WATER | | 1 | 1.000000 | | | 1.000 | 1.000 | 89/03/28 | 89/03/28 |

STORET RETRIEVAL DATE 94/06/28

PGM=INVENT

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-------------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 39032 PCP | TOT UG/L WATER | | 10 | 2.620000 | 6.724000 | 2.593100 | 10.000 | 1.800 | 89/03/28 | 92/11/17 |
| 39100 B2ETHHXL PHTHALAT | TOT UG/L WATER | | 10 | 23.18000 | 1450.300 | 38.08300 | 110.000 | 1.500 | 89/03/28 | 92/11/17 |
| 39110 DNB PHTH TOTAL | UG/L WATER | | 10 | 1.370000 | .9023300 | .9499100 | 4.000 | 1.000 | 89/03/28 | 92/11/17 |
| 39180 TRICHLOR ETHYLENE | TOT UG/L WATER | | 9 | 1.000000 | .0000000 | .0000000 | 1.000 | 1.000 | 89/03/28 | 92/11/17 |
| 39330 ALDRIN | TOT UG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 39337 ALPHABHC | TOTUG/L WATER | | 10 | .0100000 | .0000000 | .0000000 | .010 | .010 | 89/03/28 | 92/11/17 |
| 39338 BETA BHC | TOTUG/L WATER | | 10 | .0300000 | .0000000 | .0000000 | .030 | .030 | 89/03/28 | 92/11/17 |
| 39340 GAMMABHC LINDANE | TOT.UG/L WATER | | 10 | .0100000 | .0000000 | .0000000 | .010 | .010 | 89/03/28 | 92/11/17 |
| 39350 CHLRDANE TECH&MET | TOT UG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39360 DDD WHL SMPL | UG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39365 DDE WHL SMPL | UG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39370 DDT WHL SMPL | UG/L WATER | | 10 | .1000000 | .0000000 | .0000000 | .100 | .100 | 89/03/28 | 92/11/17 |
| 39380 DIELDRIIN | TOTUG/L WATER | | 10 | .0500000 | .0000000 | .0000000 | .050 | .050 | 89/03/28 | 92/11/17 |
| 39388 ENDOSULN WHL SMPL | UG/L WATER | | 10 | .0400000 | .0000000 | .0000000 | .040 | .040 | 89/03/28 | 92/11/17 |
| 39390 ENDRIN | TOT UG/L WATER | | 10 | .0800000 | .0000000 | .0000000 | .080 | .080 | 89/03/28 | 92/11/17 |
| 39400 TOXAPHEN | TOTUG/L WATER | | 10 | 2.000000 | .0000000 | .0000000 | 2.000 | 2.000 | 89/03/28 | 92/11/17 |
| 39410 HEPTCHLR | TOTUG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 39420 HPCHLREP | TOTUG/L WATER | | 10 | .0200000 | .0000000 | .0000000 | .020 | .020 | 89/03/28 | 92/11/17 |
| 39480 MTHXYCLR WHL SMPL | UG/L WATER | | 10 | .2000000 | .0000000 | .0000000 | .200 | .200 | 89/03/28 | 92/11/17 |
| 39488 PCB-1221 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39492 PCB-1232 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39496 PCB-1242 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39500 PCB-1248 | TOTUG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 39504 PCB-1254 | TOTUG/L WATER | | 10 | .8000000 | .0666670 | .2582000 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 39508 PCB-1260 | TOTUG/L WATER | | 10 | .8000000 | .0666670 | .2582000 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 39700 HCB | TOT UG/L WATER | | 10 | 7.180000 | 39.20400 | 6.261300 | 25.000 | 5.200 | 89/03/28 | 92/11/17 |
| 39702 HEXCLBD | TOT UG/L WATER | | 10 | 3.700000 | 4.900000 | 2.213600 | 10.00 | 3.00 | 89/03/28 | 92/11/17 |
| 47001 WEATHER SAMPLING | CODE WATER | | 61 | 29512.00 | 3608E+05 | 18995.00 | 81834 | 10014 | 86/05/22 | 92/07/27 |
| RESIDUE DISS-180 C | MG/L WATER | | 79 | 171.7900 | 1076.600 | 32.81100 | 430 | 82 | 85/12/19 | 93/11/17 |
| MERCURY HG,TOTAL | UG/L WATER | | 125 | .1200000 | .0390320 | .1975700 | 2.3 | .1 | 82/01/26 | 93/08/02 |
| 74041 WQF SAMPLE | UPDATED WATER | | 88 | 902100.0 | 5189E+05 | 22780.00 | 940518 | 861001 | 85/08/22 | 93/11/17 |
| 77089 ANILINE TOTAL | UG/L WATER | | 10 | 2.350000 | 7.225000 | 2.687900 | 10.000 | 1.500 | 89/03/28 | 92/11/17 |
| 77147 BNZYLAIC TOTAL | UG/L WATER | | 10 | 3.250000 | 5.625000 | 2.371700 | 10.000 | 2.500 | 89/03/28 | 92/11/17 |
| 77247 BENZOICA TOTAL | UG/L WATER | | 10 | 2.530000 | 6.889000 | 2.624700 | 10.000 | 1.700 | 89/03/28 | 92/11/17 |
| 77416 2MNAPTHA TOTAL | UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 77571 CARBAZOL TOTAL | UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 77687 245TCLPH TOTAL | UG/L WATER | | 10 | 4.840000 | 50.17600 | 7.083500 | 25.000 | 2.600 | 89/03/28 | 92/11/17 |
| 78113 ETH BENZ WH WTR | UG/L WATER | | 9 | 2.000000 | .0000000 | .0000000 | 2.00 | 2.00 | 89/03/28 | 92/11/17 |
| 78300 3-NITRO ANILINE | TOT UG/L WATER | | 10 | 4.750000 | 50.62500 | 7.115100 | 25.000 | 2.500 | 89/03/28 | 92/11/17 |
| 81302 DIBENZO FURAN | TOT UG/L WATER | | 10 | 1.900000 | 8.100000 | 2.846100 | 10.000 | 1.000 | 89/03/28 | 92/11/17 |
| 81551 XYLENE | TOT UG/L WATER | | 9 | 9.000000 | .0000000 | .0000000 | 9.000 | 9.000 | 89/03/28 | 92/11/17 |
| 81552 ACETONE | TOT UG/L WATER | | 9 | 20.00000 | .0000000 | .0000000 | 20.000 | 20.000 | 89/03/28 | 92/11/17 |

STORET RETRIEVAL DATE 94/06/28

PGM=INVENT

PAGE: 11

GROSS

1 TOTAL STATIONS PROCESSED

| PARAMETER | MEDIUM | RMK | NUMBER | MEAN | VARIANCE | STAN DEV | MAXIMUM | MINIMUM | BEG DATE | END DATE |
|-----------------------------|----------------|-----|--------|----------|----------|----------|---------|---------|----------|----------|
| 81595 MTH ETH KETONE | TOT UG/L WATER | | 9 | 8.422200 | 43.80500 | 6.618500 | 26.000 | 6.000 | 89/03/28 | 92/11/17 |
| 81596 MTHISOBU KETONE | TOT UG/L WATER | | 9 | 3.000000 | .0000000 | .0000000 | 3.000 | 3.000 | 89/03/28 | 92/11/17 |
| 81648 PCB 1016 /1242 | TOT UG/L WATER | | 10 | .5000000 | .0000000 | .0000000 | .500 | .500 | 89/03/28 | 92/11/17 |
| 81649 PCB-1262 TOT | UG/L WATER | | 8 | .7500000 | .0714290 | .2672600 | 1.000 | .500 | 89/03/28 | 92/11/17 |
| 82623 ENDOSLFM -SO4 TOT REC | UG/L WATER | | 10 | .1400000 | .0060001 | .0774600 | .2 | .05 | 89/03/28 | 92/11/17 |
| 82624 ENDOSLFM BETA TOT REC | UG/L WATER | | 10 | .0800000 | .0006666 | .0258200 | .1 | .05 | 89/03/28 | 92/11/17 |
| 85810 12D1CLR ETHL TRN EFF | UG/L WATER | | 1 | 1.000000 | | | 1.000 | 1.000 | 89/03/28 | 89/03/28 |

HAT'S ALL FOLKS

STORET RETRIEVAL DATE 94/06/28

8

ATTACHMENT 8

SOUTHERN END OF LAKE MICHIGAN REPRESENTATIVE FISHERIES



Table 18. Fish Species Collected from the Grand Calumet River, Indiana Harbor Canal, Indiana Harbor, and southwestern Lake Michigan During Various Sampling Activities.

| | | GCR/IHC | Harbor | Lake |
|------------------------|------------------------------------|---------|--------|------|
| Alewife | <i>Alosa pseudoharengus</i> | + | + | + |
| Gizzard shad | <i>Dorosoma cepedianum</i> | + | + | + |
| Steelhead trout | <i>Salmo gairdneri</i> | + | + | + |
| Brown trout | <i>S. trutta</i> | | + | + |
| Lake trout | <i>Salvelinus namaycush</i> | | | + |
| Chinook salmon | <i>Oncorhynchus tshawytscha</i> | + | + | + |
| Coho salmon | <i>O. kisutch</i> | + | | + |
| Lake whitefish | <i>Coregonus clupeaformis</i> | | | + |
| Rainbow smelt | <i>Osmerus mordax</i> | + | | + |
| Central mudminnow | <i>Umbra limi</i> | + | | |
| Goldfish | <i>Carassius auratus</i> | + | + | |
| Carp | <i>Cyprinus carpio</i> | + | + | + |
| Goldfish x Carp hybrid | | + | | |
| Rudd | <i>Scardinius erythrophthalmus</i> | + | + | |
| Golden shiner | <i>Notemigonus crysoleucas</i> | + | | |
| Emerald shiner | <i>Notropis atherinoides</i> | + | + | |
| Spottail shiner | <i>N. hudsonius</i> | + | + | + |
| Blacknose shiner | <i>N. heterolepis</i> | | + | |
| Spotfin shiner | <i>N. spilopterus</i> | + | | |
| Sand shiner | <i>N. stramineus</i> | | + | + |
| Bluntnose minnow | <i>Pimephales notatus</i> | + | + | |
| Fathead minnow | <i>P. promelas</i> | + | + | |
| Bullhead minnow | <i>P. vigilax</i> | + | | |
| Longnose dace | <i>Rhinichthys cataractae</i> | | | + |
| White sucker | <i>Catostomus commersoni</i> | | | + |
| Longnose sucker | <i>C. catostomus</i> | | | + |
| Silver redhorse | <i>Moxostoma anisurum</i> | | + | |
| Golden redhorse | <i>M. erythrurum</i> | + | | |
| Channel catfish | <i>Ictalurus punctatus</i> | | | + |
| Black bullhead | <i>Ameiurus melas</i> | + | | |
| Trout-perch | <i>Percopsis omiscomaycus</i> | | | + |

| | | | | |
|------------------------|-------------------------------|---|---|---|
| Burbot | <i>Lota lota</i> | | | + |
| Rock bass | <i>Ambloplites rupestris</i> | | + | + |
| Green sunfish | <i>Lepomis cyanellus</i> | + | | |
| Pumpkinseed | <i>L. gibbosus</i> | + | + | + |
| Orangespotted sunfish | <i>L. humilis</i> | | + | |
| Bluegill | <i>L. macrochirus</i> | + | | |
| Smallmouth bass | <i>Micropterus dolomieu</i> | | + | + |
| Largemouth bass | <i>M. salmoides</i> | + | | |
| Black crappie | <i>Pomoxis nigromaculatus</i> | | + | + |
| Yellow perch | <i>Perca flavescens</i> | + | + | + |
| Johnny darter | <i>Etheostoma nigrum</i> | | + | + |
| Freshwater drum | <i>Aplodinotus grunniens</i> | | + | + |
| Mottled sculpin | <i>Cottus bairdi</i> | | + | + |
| Slimy sculpin | <i>C. cognatus</i> | | | + |
| Threespine stickleback | <i>Gasterosteus aculeatus</i> | | + | |

Sources: Indiana Department of Natural Resources studies; Polls and Dennison 1984; IDEM 1988; Risatti and Ross 1989; Simon et al. 1989; Simon 1992; Sobiech et al. 1994; Chicago District Corps sampling in 1994, 1995, and 1996

9

ATTACHMENT 9

**1997 INDIANA ENDANGERED, THREATENED,
AND RARE SPECIES LISTS**

**1995 MICHIGAN NON-INDIGENOUS AQUATIC
NUISANCE SPECIES STATE MANAGEMENT PLAN:
EXECUTIVE SUMMARY**



ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES. INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE: ... SPECIES NAME: ... COMMON NAME: ... SPROT: USESA:SRANK:.. GRANK

**** Mammal**

| | | | | | | |
|------------|---------------------------|----------------------------|-----|-------|-----|------|
| AMALE01010 | BOS BISON | AMERICAN BISON | SX | ** | SX | G4 |
| AMAJA01030 | CANIS LUPUS | GRAY WOLF | SX | LELT | SX | G4 |
| AMAJA01020 | CANIS RUFUS | RED WOLF | SX | LEXN | SX | G1 |
| AMALC01010 | CERVUS ELAPHUS | WAPITI OR ELK | SX | ** | SX | G5 |
| AMABB05010 | CONDYLURA CRISTATA | STAR-NOSED MOLE | SSC | ** | S2? | G5 |
| AMACC08020 | CORYNORHINUS RAFINESQUII | RAFINESQUE'S BIG-EARED BAT | SSC | ** | SH | G3 |
| AMAFJ01010 | ERETHIZON DORSATUM | COMMON PORCUPINE | SX | ** | SX | G5 |
| AMAJH01022 | FELIS CONCOLOR COUGUAR | MOUNTAIN LION | SX | LE | SX | G5TH |
| AMAJH03010 | FELIS LYNX | LYNX | SX | ** | SX | G4G5 |
| AMAF02010 | GEOMYS BURSARIUS | PLAINS POCKET GOPHER | SSC | ** | S2 | G5 |
| AMAJF03010 | GULO GULO | WOLVERINE | SX | ** | SX | G4 |
| AMAJF08010 | LUTRA CANADENSIS | NORTHERN RIVER OTTER | SE | ** | S? | G5 |
| AMAJH03020 | LYNX RUFUS | BOBCAT | SE | ** | S1 | G5 |
| AMAJF01020 | MARTES PENNANTI | FISHER | SX | ** | SX | G4G5 |
| AMAJF02020 | MUSTELA NIVALIS | LEAST WEASEL | SSC | ** | S2? | G5 |
| AMACC01030 | MYOTIS AUSTRORIPARIUS | SOUTHEASTERN MYOTIS | SE | ** | S1 | G3 |
| AMACC01040 | MYOTIS GRISESCENS | GRAY MYOTIS | SE | LE | S1 | G2G3 |
| AMACC01100 | MYOTIS SODALIS | INDIANA OR SOCIAL MYOTIS | SE | LE | S1 | G2 |
| AMAFF08100 | NEOTOMA MAGISTER | EASTERN WOODRAT | ST | ** | S2 | G3G4 |
| AMACC06010 | NYCTICEIUS HUMERALIS | EVENING BAT | SE | ** | S1 | G5 |
| AMAFF21010 | RATTUS RATTUS | BLACK RAT | SX | ** | SX | G5 |
| AMAFF02030 | REITHRODONTOMYS MEGALOTIS | WESTERN HARVEST MOUSE | SSC | ** | S2 | G5 |
| AMABA01180 | SOREX FUMEUS | SMOKY SHREW | SSC | ** | S2 | G5 |
| AMABA01250 | SOREX HOYI | PYGHY SHREW | SSC | ** | S2 | G5 |
| AMAFB05120 | SPERMOPHILUS FRANKLINII | FRANKLIN'S GROUND SQUIRREL | ST | ** | S2 | G5 |
| AMAJF05010 | SPILOGALE PUTORIUS | EASTERN SPOTTED SKUNK | SX | ** | SX | G5 |
| AMAE01080 | SYLVILAGUS AQUATICUS | SWAMP RABBIT | SE | ** | S1 | G5 |
| AMAJF04010 | TAXIDEA TAXUS | AMERICAN BADGER | ST | ** | S2 | G5 |
| AMAJB01010 | URSUS AMERICANUS | BLACK BEAR | SX | T(S/A | SX | G5 |

**** Bird**

| | | | | | | |
|------------|------------------------|------------------------------|-----|------|------|------|
| ABNKC12040 | ACCIPITER COOPERII | COOPER'S HAWK | WL | ** | S3 | G4 |
| ABNKC12020 | ACCIPITER STRIATUS | SHARP-SHINNED HAWK | SSC | ** | S2 | G5 |
| ABNSB15020 | AEGOLIUS ACADICUS | NORTHERN SAW-WHET OWL | | ** | S1S2 | G5 |
| ABPBX91050 | AIMOPHILA AESTIVALIS | BACHMAN'S SPARROW | SE | ** | S1 | G3 |
| ABPBXA0030 | AMMODRAMUS HENSLOWII | HENSLOW'S SPARROW | ST | ** | S2 | G3G4 |
| ABNJB10150 | ANAS CLYPEATA | NORTHERN SHOVELER | | ** | S2? | G5 |
| ABNJB10010 | ANAS CRECCA | GREEN-WINGED TEAL | | ** | S2? | G5 |
| ABNJB10040 | ANAS RUBRIPES | AMERICAN BLACK DUCK | | ** | S2? | G4 |
| ABNGA04040 | ARDEA ALBA | GREAT EGRET | SE | ** | S1 | G5 |
| ABNGA04010 | ARDEA HERODIAS | GREAT BLUE HERON | SSC | ** | S4 | G5 |
| ABNSB13040 | ASIO FLAMMEUS | SHORT-EARED OWL | SE | ** | S2 | G5 |
| ABNSB13010 | ASIO OTUS | LONG-EARED OWL | WL | ** | S2 | G5 |
| ABNJB11030 | AYTHYA AMERICANA | REDHEAD | | ** | S1 | G5 |
| ABNJB11040 | AYTHYA COLLARIS | RING-NECKED DUCK | | ** | S2 | G5 |
| ABNNF06010 | BARTRAMIA LONGICAUDA | UPLAND SANDPIPER | SE | ** | S1 | G5 |
| ABNGA01020 | BOTAURUS LENTIGINOSUS | AMERICAN BITTERN | SE | ** | S2 | G4 |
| ABNKC19030 | BUTEO LINEATUS | RED-SHOULDERED HAWK | SSC | ** | S3 | G5 |
| ABNKC19050 | BUTEO PLATYPTERUS | BROAD-WINGED HAWK | SSC | ** | S3 | G5 |
| ABPBY06030 | CARDUELIS PINUS | PINE SISKIN | | ** | S2S3 | G5 |
| ABPBA01010 | CERTHIA AMERICANA | BROWN CREEPER | WL | ** | S3 | G5 |
| ABNNB03070 | CHARADRIUS MELODUS | PIPING PLOVER | SE | LELT | S1 | G3 |
| ABNNM10020 | CHLIDONIAS NIGER | BLACK TERN | SE | ** | S1 | G4 |
| ABNKC11010 | CIRCUS CYANEUS | NORTHERN HARRIER | SE | ** | S2 | G5 |
| ABPBG10020 | CISTOTHORUS PALUSTRIS | MARSH WREN | SE | ** | S3 | G5 |
| ABPBG10010 | CISTOTHORUS PLATENSIS | SEDGE WREN | ST | ** | S3 | G5 |
| ABNKA01010 | CORAGYPS ATRATUS | BLACK VULTURE | WL | ** | S3 | G5 |
| ABPAV10110 | CORVUS CORAX | COMMON RAVEN | SX | ** | SX | G5 |
| ABNJB02030 | CYGNUS BUCCINATOR | TRUMPETER SWAN | SE | ** | S? | G4 |
| ABPBX03240 | DENDROICA CERULEA | CERULEAN WARBLER | SSC | ** | S2 | G4 |
| ABPBX03180 | DENDROICA KIRTLANDII | KIRTLAND'S WARBLER | SE | LE | S1 | G1 |
| ABPBX03100 | DENDROICA VIRENS | BLACK-THROATED GREEN WARBLER | | ** | S1S2 | G5 |
| ABNGA06040 | EGRETTA CAERULEA | LITTLE BLUE HERON | WL | ** | S1 | G5 |
| ABPAE33070 | EMPIDONAX MINIMUS | LEAST FLYCATCHER | WL | ** | S3 | G5 |
| ABPBX85020 | EUPHAGUS CYANOCEPHALUS | BREWER'S BLACKBIRD | SX | ** | S?N | G5 |

STATE: SX=extirpated. SE=endangered. ST=threatened. SR=rare. SSC=special concern. WL=watch list.
SG=significant. SRE=state reintroduced
FEDERAL: LE=endangered. LT=threatened. LELT=different listings for specific ranges of species. PE=proposed
endangered. PT=proposed threatened. E/SA=appearance similar to LE species. **=not listed

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES, INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE:... SPECIES NAME:..... COMMON NAME:..... SPROT: USESA:SRANK:.. GRANK

| | | | | | | |
|--------------|-----------------------------------|----------------------------|-----|-------|------|--------|
| ABNKD06070 | FALCO PEREGRINUS | PEREGRINE FALCON | SE | E(S/A | S1 | G4 |
| ABNNF18010 | GALLINAGO GALLINAGO | COMMON SNIE | | ** | S2? | G5 |
| ABNBA01030 | GAVIA IMMER | COMMON LOON | SX | ** | S?N | G5 |
| ABNMK01010 | GRUS CANADENSIS | SANDHILL CRANE | ST | ** | S2 | G5 |
| ABNKC10010 | HALIAEETUS LEUCOCEPHALUS | BALD EAGLE | SE | LTNL | S1 | G4 |
| ABPBX08010 | HELMITHEROS VERMIVORUS | WORM-EATING WARBLER | SSC | ** | S3 | G5 |
| ABNKC09010 | ICTINIA MISSISSIPPIENSIS | MISSISSIPPI KITE | SSC | ** | SA | G5 |
| ABNGA02010 | IXOBRYCHUS EXILIS | LEAST BITTERN | SE | ** | S3 | G5 |
| ABPBR01030 | LANIUS LUDOVICIANUS | LOGGERHEAD SHRIKE | SE | ** | S1 | G4G5 |
| ABNJB20010 | LOPHODYTES CUCULLATUS | HOODED Merganser | | ** | S2S3 | G5 |
| ABPBX05010 | MNIOTILTA VARIA | BLACK-AND-WHITE WARBLER | SSC | ** | S3 | G5 |
| ABNGA13010 | NYCTANASSA VIOLACEA | YELLOW-CROWNED NIGHT-HERON | SE | ** | S2 | G5 |
| ABNGA11010 | NYCTICORAX NYCTICORAX | BLACK-CROWNED NIGHT-HERON | SE | ** | S1 | G5 |
| ABNKC01010 | PANDION HALIAEETUS | OSPREY | SE | ** | S1 | G5 |
| ABNFO01020 | PHALACROCORAX AURITUS | DOUBLE-CRESTED CORMORANT | SX | ** | S?N | G5 |
| ABNNF20010 | PHALAROPUS TRICOLOR | WILSON'S PHALAROPE | SX | ** | S?N | G4 |
| ABNME05020 | RALLUS ELEGANS | KING RAIL | SE | ** | S1 | G4G5 |
| ABNME05030 | RALLUS LIMICOLA | VIRGINIA RAIL | SSC | ** | S2 | G5 |
| ABPBX10020 | SEIURUS NOVEBORACENSIS | NORTHERN WATERTHRUSH | | ** | S1 | G5 |
| ABNYF05010 | SPHYRAPICUS VARIUS | YELLOW-BELLIED SAPSUCKER | | ** | S2? | G5 |
| ABNNM08102 | STERNA ANTILLARUM ATHALASSOS | INTERIOR LEAST TERN | SE | LENL | S1 | G4T2Q |
| ABNNM08090 | STERNA FORSTERI | FORSTER'S TERN | SX | ** | S?N | G5 |
| ABNNM08070 | STERNA HIRUNDO | COMMON TERN | SX | ** | S?N | G5 |
| ABPBX82030 | STURNELLA NEGLECTA | WESTERN MEADOWLARK | SSC | ** | S2 | G5 |
| ABPBG07010 | THRYOMANES BEWICKII | BEWICK'S WREN | SE | ** | S1 | G4 |
| ABNLC13010 | TYMPANUCHUS CUPIDO | GREATER PRAIRIE-CHICKEN | SX | ** | SX | G4 |
| ABNSA01010 | TYTO ALBA | BARN OWL | SE | ** | S2 | G5 |
| ABPBX01030 | VERMIVORA CHRYSOPTERA | GOLDEN-WINGED WARBLER | SE | ** | S1 | G4 |
| ABPBX16030 | WILSONIA CANADENSIS | CANADA WARBLER | SSC | ** | S1S2 | G5 |
| ABPBX16010 | WILSONIA CITRINA | HOODED WARBLER | SSC | ** | S3 | G5 |
| ABPBX83010 | XANTHOCEPHALUS XANTHOCEPHALUS | YELLOW-HEADED BLACKBIRD | ST | ** | S2 | G5 |
| ** Reptile | | | | | | |
| ARADE01022 | AGKISTRODON PISCIVORUS LEUCOSTOMA | WESTERN COTTONMOUTH | ST | ** | S1 | G5T5 |
| ARADB03012 | CEMOPHORA COCCINEA COPEI | NORTHERN SCARLET SNAKE | ST | ** | S1 | G5T5 |
| ARAAD02010 | CLEMYS GUTTATA | SPOTTED TURTLE | ST | ** | S2 | G5 |
| ARADB06010 | CLONOPHIS KIRTLANDII | KIRTLAND'S SNAKE | ST | ** | S2 | G2 |
| ARADE02040 | CROTALUS HORRIDUS | TIMBER RATTLESNAKE | ST | ** | S2 | G5 |
| ARAAD04010 | EMYDOIDEA BLANDINGII | BLANDING'S TURTLE | SE | ** | S2 | G4 |
| ARADB14012 | FARANCIA ABACURA REINWARDTII | WESTERN MUD SNAKE | SX | ** | SX | G5T5 |
| ARAAE01050 | KINOSTERNON SUBRUBRUM | EASTERN MUD TURTLE | ST | ** | S2 | G5 |
| ARAAB02010 | MACROCLEMYS TEMMINCKII | ALLIGATOR SNAPPING TURTLE | SE | ** | S1 | G3G4 |
| ARADB22023 | NERODIA ERYTHROGASTER NEGLECTA | COPPERBELLY WATER SNAKE | ST | PT | S2 | G5T2 |
| ARADB23010 | OPHEODRYS AESTIVUS | ROUGH GREEN SNAKE | SSC | ** | S3 | G5 |
| ARADB23020 | OPHEODRYS VERNALIS | SMOOTH GREEN SNAKE | ST | ** | S2 | G5 |
| ARACB02010 | OPHISAURUS ATTENUATUS | SLENDER GLASS LIZARD | | ** | S2 | G5 |
| ARAAD07024 | PSEUDEMYS CONCINNA HIEROGLYPHICA | HIEROGLYPHIC RIVER COOTER | SE | ** | S1 | G5T4 |
| ARADE03011 | SISTRURUS CATENATUS CATENATUS | EASTERN MASSASAUGA | ST | ** | S2 | G3G4T3 |
| ARADB35020 | TANTILLA CORONATA | SOUTHEASTERN CROWNED SNAKE | ST | ** | S1 | G5 |
| ARAAD08020 | TERRAPENE ORNATA | ORNATE BOX TURTLE | SSC | ** | S2 | G5 |
| ARADB36020 | THAMNOPHIS BUTLERI | BUTLER'S GARTER SNAKE | ST | ** | S1 | G5 |
| ARADB36090 | THAMNOPHIS PROXIMUS | WESTERN RIBBON SNAKE | SSC | ** | S3 | G5 |
| ** Amphibian | | | | | | |
| AAABC01010 | ACRIS CREPITANS | NORTHERN CRICKET FROG | | ** | S? | G5 |
| AAAAA01170 | AMBYSTOMA BARBOURI | STREAMSIDE SALAMANDER | WL | ** | S3 | G4 |
| AAAAA01060 | AMBYSTOMA LATERALE | BLUE-SPOTTED SALAMANDER | SSC | ** | S2 | G5 |
| AAAAO01010 | ANEIDES AENEUS | GREEN SALAMANDER | SE | ** | S? | G3G4 |
| AAAAO01011 | CRYPTOBRANCHIUS ALLEGANIENSIS | HELLBENDER | SE | ** | S1 | G4T4 |
| AAAAO08010 | HEMIDACTYLUM SCUTATUM | FOUR-TOED SALAMANDER | ST | ** | S2 | G5 |
| AAAAE01040 | NECTURUS MACULOSUS | MUDPUPPY | SSC | ** | S2 | G5 |
| AAAAI2150 | PLETHODON RICHMONDI | RAVINE SALAMANDER | WL | ** | S2 | G5 |
| AAAAI3022 | PSEUDOTRITON RUBER RUBER | NORTHERN RED SALAMANDER | SE | ** | S1 | G5T5 |
| AAABH01014 | RANA AREOLATA CIRCULOSA | NORTHERN CRAWFISH FROG | ST | ** | S2 | G4T4 |
| AAABH01040 | RANA BLAIRI | PLAINS LEOPARD FROG | SSC | ** | S2 | G5 |

STATE: SX-extirpated. SE-endangered. ST-threatened. SR-rare. SSC-special concern. WL-watch
SG-significant. SRE=state reintroduced
FEDERAL: LE-endangered. LT-threatened. LELT-different listings for specific ranges of species. PE-pr
endangered. PT-proposed threatened. E/SA-appearance similar to LE species. **=not listed

January 22, 1997

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES. INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE: ... SPECIES NAME: ... COMMON NAME: ... SPROT: USESA:SRANK: GRANK

| | | | | | |
|---|-----------------------|-----|----|----|------|
| AAABH01170 RANA PIPIENS | NORTHERN LEOPARD FROG | SSC | ** | S2 | G5 |
| AAABF01041 SCAPHIOPUS HOLBROOKII HOLBROOKII | EASTERN SPADEFOOT | SSC | ** | S2 | G5T5 |

** Fish

| | | | | | |
|--------------------------------------|---------------------|-----|----|----|------|
| AFCAA01020 ACIPENSER FULVESCENS | LAKE STURGEON | SE | ** | S1 | G3 |
| AFCFA01020 ALOSA ALABAMAE | ALABAMA SHAD | SX | ** | SX | G4 |
| AFCLA01020 AMBLYOPSIS SPELAEA | NORTHERN CAVEFISH | SE | ** | S1 | G3 |
| AFCJC02030 CATOSTOMUS CATOSTOMUS | LONGNOSE SUCKER | WL | ** | S2 | G5 |
| AFCJB05010 CLINOSTOMUS ELONGATUS | REDSIDE DACE | SE | ** | S1 | G5 |
| AFCHA01020 COREGONUS ARTEDI | CISCO | SSC | ** | S2 | G5 |
| AFCHA01050 COREGONUS HOYI | BLOATER | WL | ** | S1 | G3 |
| AFCHA01060 COREGONUS JOHANNAE | DEEPWATER CISCO | WL | ** | SX | GX |
| AFCHA01070 COREGONUS KIYI | KIYI | WL | ** | S1 | G3 |
| AFCHA01100 COREGONUS NIGRIPINNIS | BLACKFIN CISCO | SX | ** | SX | GX0 |
| AFCHA01120 COREGONUS REIGHARDI | SHORTNOSE CISCO | SX | ** | SX | GH |
| AFCHA01140 COREGONUS ZENITHICUS | SHORTJAW CISCO | WL | ** | S1 | G2 |
| AFCJB06010 COUESIUS PLUMBEUS | LAKE CHUB | WL | ** | S2 | G5 |
| AFCQC01010 CRYSTALLARIA ASPRELLA | CRYSTAL DARTER | SX | ** | SX | G3 |
| AFCJC04010 CYCLEPTUS ELONGATUS | BLUE SUCKER | SSC | ** | S2 | G3 |
| AFCQC02100 ETHEOSTOMA CAMURUM | BLUEBREAST DARTER | SE | ** | S1 | G4 |
| AFCQC02860 ETHEOSTOMA CLARUM | WESTERN SAND DARTER | SE | ** | S3 | G3 |
| AFCQC02310 ETHEOSTOMA HISTRIO | HARLEQUIN DARTER | SE | ** | S1 | G5 |
| AFCQC02420 ETHEOSTOMA MACULATUM | SPOTTED DARTER | SE | ** | S1 | G2 |
| AFCQC02880 ETHEOSTOMA PELLUCIDUM | EASTERN SAND DARTER | SSC | ** | S2 | G3 |
| AFCQC02730 ETHEOSTOMA SQUAMICEPS | SPOTTAIL DARTER | SE | ** | S1 | G5 |
| AFCQC02800 ETHEOSTOMA TIPECANOE | TIPPECANOE DARTER | SE | ** | S1 | G3 |
| AFCQC02830 ETHEOSTOMA VARIATUM | VARIEGATE DARTER | SE | ** | S1 | G5 |
| AFCNB04020 FUNDULUS CATENATUS | NORTHERN STUDDISH | SSC | ** | S2 | G5 |
| AFCJB16030 HYBOGNATHUS HAYI | CYPRESS MINNOW | WL | ** | S2 | G5 |
| AFCJB28880 HYBOPSIS AMBLOPS | BIGEYE CHUB | WL | ** | S2 | G5 |
| AFCJB28050 HYBOPSIS AMNIS | PALLID SHINER | WL | ** | S2 | G4 |
| AFBAA01010 ICHTHYOMYZON BOELLII | OHIO LAMPREY | WL | ** | S2 | G3G4 |
| AFCJC07030 ICTIOBUS NIGER | BLACK BUFFALO | WL | ** | S2 | G5 |
| AFBAA02010 LAMPETRA AEPYPTERA | LEAST BROOK LAMPREY | WL | ** | S2 | G5 |
| AFCBA01050 LEPISTOSTEUS SPATULA | ALLIGATOR GAR | WL | ** | S2 | G5 |
| AFCQB11110 LEPOMIS SYMMETRICUS | BANTAM SUNFISH | SX | ** | S1 | G5 |
| AFCJC10040 MOXOSTOMA CARINATUM | RIVER REDHORSE | SSC | ** | S3 | G4 |
| AFCJC10170 MOXOSTOMA VALENCIENNESI | GREATER REDHORSE | SSC | ** | S2 | G3 |
| AFCJB28080 NOTROPIS ANOGENUS | PUGNOSE SHINER | WL | ** | S1 | G3 |
| AFCJB28410 NOTROPIS DORSALIS | BIGMOUTH SHINER | WL | ** | S2 | G5 |
| AFCJB28530 NOTROPIS HETEROLEPIS | BLACKNOSE SHINER | WL | ** | S2 | G5 |
| AFCJB28950 NOTROPIS TEXANUS | WEED SHINER | WL | ** | S1 | G5 |
| AFCKA02180 NOTURUS NOCTURNUS | FRECKLED MADTOM | WL | ** | S1 | G4 |
| AFCKA02220 NOTURUS STIGMOSUS | NORTHERN MADTOM | WL | ** | S2 | G5 |
| AFCJB55010 OPSOPOEODUS EMILIAE | PUGNOSE MINNOW | WL | ** | S2 | G4 |
| AFCQC04060 PERCINA COPELANDI | CHANNEL DARTER | WL | ** | S2 | G4 |
| AFCQC04090 PERCINA EVIDES | GILT DARTER | SE | ** | S1 | G3 |
| AFCQC04300 PERCINA URANIDEA | STARGAZING DARTER | SX | ** | SX | G3 |
| AFCLC01010 PERCOPSIS OMISCOMAYCUS | TROUT-PERCH | WL | ** | S2 | G5 |
| AFCA01010 POLYODON SPATHULA | PADDLEFISH | WL | ** | S3 | G4 |
| AFCHA05050 SALVELINUS NAMAYCUSH | LAKE TROUT | WL | ** | S2 | G5 |
| AFCLA04010 TYPHLICHTHYS SUBTERRANEUS | SOUTHERN CAVEFISH | SE | ** | S1 | G3 |

** Crustacean

| | | | | | |
|--|---------------------------|----|----|-----|------|
| ICCOPO8011 BRYOCAMPTUS MORRISONI MORRISONI | MORRISON'S CAVE COPEPOD | SE | ** | S1 | G7? |
| ICMAL01190 CAECIDOTEA JORDANI | JORDAN CAVE ISOPOD | SE | ** | S2 | G1 |
| ICMAL01340 CAECIDOTEA ROTUNDA | NORTHEASTERN CAVE ISOPOD | SE | ** | S1 | G2 |
| ICMAL01470 CAECIDOTEA TERESAE | GROUNDWATER ISOPOD | SE | ** | S1 | G7 |
| ICMAL07110 CAMBARUS ORTMANNI | BURROWING CRAYFISH | | ** | S2 | G2G3 |
| ICMAL07120 CAMBARUS ROBUSTUS | A CRAYFISH | | ** | S2 | G5 |
| ICMAL06090 CRANGONYX PACKARDI | PACKARD'S CAVE AMPHIPOD | SR | ** | S2 | G2 |
| ICMAL06X10 CRANGONYX SP 1 | UNDESCRIBED CAVE AMPHIPOD | SR | ** | S2 | G2 |
| ICCOPO2020 DIACYCLOPS JEANNELI | JEANNEL'S CAVE COPEPOD | SE | ** | S1 | G1 |
| ICMAL10010 GAMMARUS BOUSFIELDI | SPRING AMPHIPOD | SE | ** | S1 | G1 |
| ICBRA08010 LYNCEUS BRACHYURUS | CLAM SHRIMP | WL | ** | S1? | G? |

STATE: SX=extirpated. SE=endangered. ST=threatened. SR=rare. SSC=special concern. WL=watch list.
SG=significant. SRE=state reintroduced
FEDERAL: LE=endangered. LT=threatened. LELT=different listings for specific ranges of species. PE=proposec
endangered. PT=proposed threatened. E/SA=appearance similar to LE species. **=not listed

January 22, 1997

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES. INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE:... SPECIES NAME:..... COMMON NAME:..... SPROT: USESA:SRANK:.. GRANK

| | | | | | | |
|------------|----------------------------|-------------------------------------|-----|----|------|------|
| ICOP09010 | MEGACYCLOPS DONNALDSONI | DONALDSONS CAVE COPEPOD | SE | ** | S1 | G1 |
| ICMAL11100 | ORCONECTES INDIANENSIS | INDIANA CRAYFISH | SSC | ** | S2 | G2G3 |
| ICMAL11031 | ORCONECTES INERMIS INERMIS | A TROGLOBITIC CRAYFISH | | ** | S3 | G5T4 |
| ICMAL11032 | ORCONECTES INERMIS TESTII | TROGLOBITIC CRAYFISH | ST | ** | S2 | G5T3 |
| ICMAL11610 | ORCONECTES PUTNAMI | A CRAYFISH | | ** | S2 | G3 |
| ICMAL11150 | ORCONECTES SLOANII | CRAYFISH | | ** | S1S2 | G2 |
| ICMAL14440 | PROCAMBARUS CLARKII | RED SWAMP CRAYFISH | | ** | S? | G5 |
| ICMAL14310 | PROCAMBARUS GRACILIS | PRAIRIE CRAYFISH | | ** | S1S2 | G5 |
| ICOST11010 | PSEUDOCANDONA JEANNELI | JEANNEL'S CAVE OSTRACOD | SE | ** | S1 | G? |
| ICOST11020 | PSEUDOCANDONA MARENGOENSIS | MARENGO CAVE OSTRACOD | SE | ** | S1 | G? |
| ICMAL05300 | STYGOBROMUS MACKINI | SOUTHWESTERN VIRGINIA CAVE AMPHIPOD | SE | ** | S1 | G3G4 |
| ICMAL05X20 | STYGOBROMUS SP 2 | UNDESCRIBED AMPHIPOD | SE | ** | S1 | G1 |

** Mussel

| | | | | | | |
|------------|---------------------------------|--------------------------------|-----|----|----|--------|
| IMBIV02110 | ALAS MIDONTA VIRIDIS | SLIPPERSHELL MUSSEL | WL | ** | S2 | G4 |
| IMBIV06010 | ARCIDENS CONFRAGOSUS | ROCK-POCKETBOOK | WL | ** | S2 | G3 |
| IMBIV08010 | CUMBERLANDIA MONODONTA | SPECTACLECASE | SX | ** | SX | G2G3 |
| IMBIV10020 | CYPROGENIA STEGARIA | EASTERN FAN SHELL PEARLYMUSSEL | SE | LE | S1 | G1 |
| IMBIV16050 | EPIOBLASMA FLEXUOSA | LEAF SHELL | SX | ** | SX | GX |
| IMBIV16111 | EPIOBLASMA OBLIQUATA OBLIQUATA | PURPLE CATSPAW | SX | LE | SX | G1T? |
| IMBIV16112 | EPIOBLASMA OBLIQUATA PEROBLIQUA | WHITE CAT'S PAW PEARLYMUSSEL | SE | LE | S1 | G1T1 |
| IMBIV16140 | EPIOBLASMA PERSONATA | ROUND COMBSHELL | SX | ** | SX | GX |
| IMBIV16150 | EPIOBLASMA PROPINQUA | TENNESSEE RIFFLESHELL | SX | ** | SX | GX |
| IMBIV16160 | EPIOBLASMA SAMPSONII | WABASH RIFFLESHELL | SX | ** | SX | GX |
| IMBIV16184 | EPIOBLASMA TORULOSA RANGIANA | NORTHERN RIFFLESHELL | SE | LE | S1 | G2T2 |
| IMBIV16183 | EPIOBLASMA TORULOSA TORULOSA | TUBERCLED BLOSSOM | SE | LE | S1 | G2TX |
| IMBIV16190 | EPIOBLASMA TRIQUETRA | SNUFFBOX | SE | ** | S1 | G3 |
| IMBIV17120 | FUSCONAIA SUBROTUNDA | LONG-SOLID | SE | ** | S1 | G4 |
| IMBIV20010 | HEMISTENA LATA | CRACKING PEARLYMUSSEL | SX | LE | SX | G1 |
| IMBIV21110 | LAMPSILIS ABRUPTA | PINK MUCKET | SE | LE | S1 | G2 |
| IMBIV21070 | LAMPSILIS FASCIOLA | WAVY-RAYED LAMP MUSSEL | SSC | ** | S2 | G4 |
| IMBIV21130 | LAMPSILIS OVATA | POCKETBOOK | WL | ** | S2 | G5 |
| IMBIV21240 | LAMPSILIS TERES | YELLOW SANDSHELL | WL | ** | S2 | G5 |
| IMBIV24020 | LEPTODEA LEPTODON | SCALESHELL | SX | ** | SX | G2G3 |
| IMBIV26020 | LIGUMIA RECTA | BLACK SANDSHELL | WL | ** | S2 | G5 |
| IMBIV31030 | OBOVARIA RETUSA | RING PINK | SX | LE | SX | G1 |
| IMBIV31050 | OBOVARIA SUBROTUNDA | ROUND HICKORYNUT | SSC | ** | S2 | G3 |
| IMBIV34010 | PLETHOBASUS CICATRICOSUS | WHITE WARTYBACK | SE | LE | S1 | G1 |
| IMBIV34020 | PLETHOBASUS COOPERIANUS | ORANGE-FOOT PIMPLEBACK | SE | LE | S1 | G1 |
| IMBIV34030 | PLETHOBASUS CYPHYUS | SHEEPNOSE | SE | ** | S1 | G3 |
| IMBIV35060 | PLEUROBEMA CLAVA | CLUBSHELL | SE | LE | S1 | G1 |
| IMBIV35070 | PLEUROBEMA COCCINEUM | ROUND PIGTOE | | ** | S3 | G3G4 |
| IMBIV35090 | PLEUROBEMA CORDATUM | OHIO PIGTOE | SSC | ** | S2 | G3 |
| IMBIV35240 | PLEUROBEMA PLENUM | ROUGH PIGTOE | SE | LE | S1 | G1 |
| IMBIV35250 | PLEUROBEMA PYRAMIDATUM | PYRAMID PIGTOE | SE | ** | S1 | G2G3 |
| IMBIV37030 | POTAMILUS CAPAX | FAT POCKETBOOK | SE | LE | S1 | G1 |
| IMBIV38010 | PTYCHOBANCHUS FASCIOLARIS | KIDNEYSHELL | SSC | ** | S2 | G4 |
| IMBIV39041 | QUADRULA CYLINDRICA CYLINDRICA | RABBITSFOOT | SE | ** | S1 | G4T2T3 |
| IMBIV39050 | QUADRULA FRAGOSA | WINGED MAPLELEAF | SX | LE | SX | G1 |
| IMBIV39080 | QUADRULA METANEVRA | MONKEYFACE | | ** | S3 | G3 |
| IMBIV39090 | QUADRULA NODULATA | WARTYBACK | | ** | S3 | G3G4 |
| IMBIV41010 | SIMPSONIA AMBIGUA | SALAMANDER MUSSEL | SSC | ** | S2 | G2 |
| IMBIV43030 | TOXOLASMA LIVIDUM | PURPLE LILLIPUT | SSC | ** | S2 | G1G2Q |
| IMBIV43050 | TOXOLASMA PARVUM | LILLIPUT | WL | ** | S2 | G4 |
| IMBIV44010 | VENUSTACONCHA ELLIPSIFORMIS | ELLIPSE | SSC | ** | S2 | G3 |
| IMBIV47050 | VILLOSA FABALIS | RAYED BEAN | SSC | ** | S1 | G2 |
| IMBIV47070 | VILLOSA LIENOSA | LITTLE SPECTACLECASE | SSC | ** | S2 | G5 |

** Gastropod

| | | | | | | |
|------------|---------------------------------|----------------------|-----|----|----|------|
| IMGASJ8010 | ANTROSELATUS SPIRALIS | SHAGGY CAVE SNAIL | ST | ** | S2 | G2G3 |
| IMGASE6040 | CAMPELOMA DECISUM | POINTED CAMPELOMA | SSC | ** | S2 | G5 |
| IMGASK2601 | ELIMIA SEMICARINATA INDIANENSIS | INDIANA RIVER SNAIL | WL | ** | S1 | G?T? |
| IMGASG5020 | FONTIGENS CRYPTICA | HIDDEN SPRINGS SNAIL | SE | ** | S1 | G1 |
| IMGASK6010 | LITHASIA ARMIGERA | ARMORED ROCKSNAIL | WL | ** | S? | G? |
| IMGASL2020 | LYMNAEA STAGNALIS | SWAMP LYMNAEA | SSC | ** | S2 | G5 |
| IMGASA1280 | TRIODOPSIS OBSTRICTA | SHARP WEDGE | SE | ** | S1 | G? |

STATE: SX=extirpated, SE=endangered, ST=threatened, SR=rare, SSC=special concern, WL=watch

FEDERAL: SG=significant, SRE=state reintroduced

LE=endangered, LT=threatened, LEFT=different listings for specific ranges of species, PE=proposed
endangered, PT=proposed threatened, E/SA=appearance similar to LE species, **=not listed

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES, INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE:... SPECIES NAME:..... COMMON NAME:..... SPROT: USESA:SRANK:.. GRANK

** Lepidoptera: Butterflies, Skippers, Moths

| | | | | | |
|------------|---------------------------------|-------------------------------|-------|------|--------|
| IILEP80120 | AMBLYSKIRTES AESCULAPIUS | | ** | S1 | G4 |
| IILEP80200 | AMBLYSKIRTES BELLI | BELL'S ROADSIDE SKIPPER | ** | S1S2 | G4 |
| IILEP80080 | AMBLYSKIRTES HEGON | SALT-AND-PEPPER SKIPPER | WL ** | S1S3 | G5 |
| IILEPA2014 | ARTOGEIA NAPI OLERACEA | VEINED WHITE | SE ** | S1 | G5T4 |
| IILEPA2020 | ARTOGEIA VIRGINIENSIS | WEST VIRGINIA WHITE | SR ** | S3 | G4 |
| IILEP79010 | ATRYTONOPSIS HIANNA | DUSTED SKIPPER | ST ** | S2S3 | G4G5 |
| IILEP14010 | AUTOCHTON CELLUS | GOLDEN-BANDED SKIPPER | WL ** | S1S2 | G4 |
| IILEYC4040 | BELLURA DENSA | NOCTUID MOTH | ** | S? | G5 |
| IILEPJ7031 | BOLORIA SELENE MYRINA | SILVER-BORDERED FRITILLARY | ** | S2S3 | G5T5 |
| IILEPJ7036 | BOLORIA SELENE NEBRASKENSIS | NEBRASKA FRITILLARY | ** | S1? | |
| IILEPH2020 | CALEPHELIS BOREALIS | NORTHERN METALMARK | ** | S3 | G3G4 |
| IILEPH2060 | CALEPHELIS MUTICA | SWAMP METALMARK | SR ** | S2S3 | G4 |
| IILEPE1010 | CALYCOPSIS CECROPS | RED-BANDED HAIRSTREAK | ** | S2S3 | G5 |
| IILEY89A40 | CATOCALA DULCIOLA | | ** | S? | G3 |
| IILEY89350 | CATOCALA MARMORATA | MARBLED UNDERWING MOTH | ** | S1 | G4 |
| IILEPG0020 | CELASTRINA EBENINA | SOOTY AZURE | WL ** | S2 | G4 |
| IILEPG0030 | CELASTRINA NEGLECTAMAJOR | APPALACHIAN BLUE | ** | S1S2 | G4 |
| IILEPJ9150 | CHLOSYPSE HARRISII | HARRIS' CHECKERSPOT | SR ** | S2 | G4 |
| IILEPN1040 | CYLLOPSIS GEMMA | GEMMED SATYR | SR ** | S2 | G5 |
| IILEPM9030 | ENODIA CREOLA | CREOLE PEARLY EYE | SX ** | SU | G4? |
| IILEY80010 | EOPHROPTERYX THYATYROIDES | PINKPATCHED LOOPER MOTH | ST ** | S2 | G4G5 |
| IILEP37140 | ERYNNIS LUCILIUS | COLUMBINE DUSKYWING | ** | S1? | G4 |
| IILEP37100 | ERYNNIS MARTIALIS | MOTTLED DUSKYWING | ST ** | S3 | G4 |
| IILEP37171 | ERYNNIS PERSIUS PERSIUS | PERSIUS DUSKYWING | SE ** | S1S2 | G4T2T3 |
| IILEPA5040 | EUCHLOE OLYMPIA | OLYMPIA MARBLEWING | ST ** | S2 | G4 |
| IILEPK4060 | EUPHYDRYAS PHAETON | BALTIMORE | ** | S2S4 | G4 |
| IILEP77090 | EUPHYES BIMACULA | TWO-SPOTTED SKIPPER | SR ** | S2 | G4 |
| IILEP77050 | EUPHYES DUKESI | SCARCE SWAMP SKIPPER | SR ** | S2 | G3 |
| IILEPE9010 | EURISTRYMON ONTARIO | NORTHERN HAIRSTREAK | WL ** | S2S4 | G4 |
| IILEPG4022 | GLAUCOPSYCHE LYGDAMUS COUPERI | SILVERY BLUE | SE ** | S1 | G5T4 |
| IILEW0M30 | HEMILEUCA SP 3 | MIDWESTERN FEN BUCKMOTH | ** | S1? | G3G4 |
| IILEPN2020 | HERMEUPTYCHIA SOSYBIUS | CAROLINA SATYR | ** | S1S2 | G50 |
| IILEP65060 | HESPERIA LEONARDUS | LEONARDUS SKIPPER | SR ** | S2 | G4 |
| IILEP65100 | HESPERIA METEA | COBWEB SKIPPER | ST ** | S2S3 | G4G5 |
| IILEP65050 | HESPERIA OTTOE | OTTOE SKIPPER | SE ** | S1 | G3? |
| IILEP65160 | HESPERIA SASSACUS | INDIAN SKIPPER | SR ** | S3 | G5 |
| IILEY04010 | HYPERAESCHRA TORTUOSA | A PROMINENT MOTH | ST ** | S2 | G? |
| IILEPE7051 | INCISALIA HENRICI TURNERI | HENRY'S ELFIN | ** | S2S4 | G5T4T5 |
| IILEPE7040 | INCISALIA IRUS | FROSTED ELFIN | SR ** | S2 | G4 |
| IILEPE7030 | INCISALIA POLIA | HOARY ELFIN | SR ** | S1? | G5 |
| IILEPG5021 | LYCAEIDES MELISSA SAMUELIS | KARNER BLUE BUTTERFLY | SE LE | S1 | G5T2 |
| IILEPC1121 | LYCAENA DORCAS DORCAS | DORCAS COPPER | ** | S2 | G4TU |
| IILEPC1110 | LYCAENA EPIXANTHE | BOG COPPER | SX ** | SX | G4G5 |
| IILEPC1130 | LYCAENA HELLOIDES | PURPLISH COPPER | ** | S2S4 | G5 |
| IILEPC1040 | LYCAENA XANTHOIDES | GREAT COPPER | WL ** | S? | G5 |
| IILEU2E040 | LYTROSIS PERMAGNARIA | A LYTROSIS MOTH | ST ** | S2 | GU |
| IILEU3C110 | METARRANTHIS APICIARIA | BARRENS METARRANTHIS MOTH | WL ** | SH | GU |
| IILEPE4091 | MITOURA GRYNEA GRYNEA | OLIVE HAIRSTREAK | ** | S2S4 | G5T5 |
| IILEPN3021 | NEONYMPHA MITCHELLII MITCHELLII | MITCHELL'S SATYR | SE LE | S1 | G2T2 |
| IILEP57010 | OARISMA POWESHEIK | POWESHEIK SKIPPER | SX ** | SH | G2G3 |
| IILEYC0310 | PAPAIPEMA ERYNGII | RATTLESNAKE-MASTER BORER MOTH | SX ** | SX | G1 |
| IILEYC0150 | PAPAIPEMA LEUCOSTIGMA | COLUMBINE BORER | WL ** | S? | G4 |
| IILEPF1010 | PARRHASIUS M-ALBUM | WHITE M HAIRSTREAK | ** | S1S3 | G5 |
| IILEP73071 | POANES VIATOR VIATOR | BROAD-WINGED SKIPPER | SR ** | S2 | G5T4 |
| IILEPK5100 | POLYGONIA PROGNE | GRAY COMMA | ** | S2S4 | G5 |
| IILEP71010 | PROBLEMA BYSSUS | BUNCHGRASS SKIPPER | SR ** | S2 | G3G4 |
| IILEYFF030 | PYREFERRA CEROMATICA | ANNOINTED SALLOW MOTH | SR ** | S2 | GU |
| IILEPN0022 | SATYRODES APPALACHIA APPALACHIA | APPALACHIAN EYED BROWN | SE ** | S1 | G5T5 |
| IILEPN0012 | SATYRODES EURYDICE FUMOSA | SMOKEY-EYED BROWN | ** | S1S2 | G5T3T4 |
| IILEYMP890 | SCHINIA GLORIOSA | GLORIOUS FLOWER MOTH | WL ** | SU | G4 |
| IILEYMP130 | SCHINIA INDIANA | PHLOX MOTH | SE ** | S1 | GU |
| IILEPJ6110 | SPEYERIA ATLANTIS | ATLANTIS FRITILLARY | ** | S1? | G5 |
| IILEPJ6010 | SPEYERIA DIANA | DIANA | ** | SX | G3 |
| IILEPJ6040 | SPEYERIA IDALIA | REGAL FRITILLARY | SE ** | S1 | G3 |
| IILEP16050 | THORYBES CONFUSIS | EASTERN CLOUDYWING | ** | S1? | G4 |

STATE: SX=extirpated. SE=endangered. ST=threatened. SR=rare. SSC=special concern. WL=watch list.
FEDERAL: SG=significant. SRE=state reintroduced
LE=endangered. LT=threatened. LELT=different listings for specific ranges of species. PE=proposed
endangered. PT=proposed threatened. E/SA=appearance similar to LE species. **=not listed

January 22, 1997

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES, INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE:... SPECIES NAME:..... COMMON NAME:..... SPROT: USESA:SRANK:.. GRANK

**** Odonata: Dragonflies, Damselflies**

| | | | | | |
|------------|-----------------------------|---------------------------------|-------|-------|--------|
| I10D014020 | AESHNA CANADENSIS | CANADA DARNER | ** | S1 | G5 |
| I10D014030 | AESHNA CLEPSYDRA | MOTTLED DARNER | ** | S1 | G4 |
| I10D014110 | AESHNA MUTATA | SPATTERDOCK DARNER | ** | S1S2 | G3G4 |
| I10D014180 | AESHNA TUBERCULIFERA | BLACK-TIPPED DARNER | ** | S2 | G4 |
| I10D015030 | ANAX LONGIPES | COMET DARNER | ** | S2 | G5 |
| I10D075010 | ARCHILESTES GRANDIS | GREAT SPREADING | SR ** | S3 | G5 |
| I10D081040 | ARIGOMPHUS CORNUTUS | HORNED CLUBTAIL | ** | S1 | G4 |
| I10D081050 | ARIGOMPHUS FURCIFER | LILYPAD CLUBTAIL | ** | S1 | G5 |
| I10D081010 | ARIGOMPHUS LENTULUS | STILLWATER CLUBTAIL | ** | S1 | G5 |
| I10D065010 | CALOPTYRYX AEQUABILIS | RIVER JEWELWING | ** | S1 | G5 |
| I10D065020 | CALOPTYRYX ANGUSTIPENNIS | APPALACHIAN JEWELWING | ** | S1 | G4 |
| I10D037090 | CELITHEMIS VERNA | DOUBLE-RINGED PENNANT | ** | S1 | G5 |
| I10D078010 | CHROMAGRION CONDITUM | AURORA DAMSEL | ** | S2S3 | G5 |
| I10D003090 | CORDULEGASTER BILINEATA | BROWN SPIKETAIL | ** | S1 | G5 |
| I10D003020 | CORDULEGASTER DIASTATOPS | DELTA-SPOTTED SPIKETAIL | ** | S1 | G5 |
| I10D003040 | CORDULEGASTER ERRONEA | TIGER SPIKETAIL | ** | S1 | G4 |
| I10D003060 | CORDULEGASTER MACULATA | TWIN-SPOTTED SPIKETAIL | ** | S2S3 | G5 |
| I10D003070 | CORDULEGASTER OBLIQUA | ARROWHEAD SPIKETAIL | ** | S2S3 | G4 |
| I10D028020 | DOROCORDULIA LIBERA | RACKET-TAILED EMERALD | ** | S1 | G5 |
| I10D071010 | ENALLAGMA BOREALE | BOREAL BLUET | ** | S1S2 | G5 |
| I10D071150 | ENALLAGMA CYATHIGERUM | NORTHERN BLUET | ** | S1S2 | G5 |
| I10D071160 | ENALLAGMA DIVAGANS | TURQUOISE BLUET | ** | S3 | G5 |
| I10D006040 | ERPETOGRYPHUS DESIGNATUS | EASTERN RINGTAIL | ** | S2 | G5 |
| I10D008090 | GOMPHUS CRASSUS | HANDSOME CLUBTAIL | ** | S2 | G3G4 |
| I10D008110 | GOMPHUS EXTERNUS | PLAINS CLUBTAIL | ** | S2S3 | G5 |
| I10D008140 | GOMPHUS LINEATIFRONS | SPLENDID CLUBTAIL | ** | S2 | G4 |
| I10D008380 | GOMPHUS QUADRICOLOR | RAPIDS CLUBTAIL | ** | S2 | G3G4 |
| I10D008400 | GOMPHUS SPICATUS | DUSKY CLUBTAIL | ** | S2 | G5 |
| I10D008210 | GOMPHUS VENTRICOSUS | SKILLET CLUBTAIL | ** | S1S2 | G3 |
| I10D008460 | GOMPHUS VIRIDIFRONS | GREEN-FACED CLUBTAIL | ** | S1S2 | G3 |
| I10D009010 | HAGENIUS BREVI-STYLUS | DRAGONHUNTER | ** | S2S3 | G5 |
| I10D066020 | HETAERINA TITIA | SMOKY RUBYSPO | ** | S2S3 | G5 |
| I10D072020 | ISCHNURA KELLICOTTI | LILYPAD FORKTAIL | ** | S2 | G5 |
| I10D072040 | ISCHNURA PROGNOTA | FURTIVE FORKTAIL | ** | S1 | G4 |
| I10D045230 | LADONA JULIA | CHALK-FRONTED SKIMMER | ** | S2S3 | G5 |
| I10D044020 | LEUCORRHINIA FRIGIDA | FROSTED WHITEFACE | ** | S2 | G5 |
| I10D026080 | MACROMIA PACIFICA | GILDED RIVER CRUISER | ** | S1S2 | G4 |
| I10D026110 | MACROMIA WABASHENSIS | WABASH BELTED SKIMMER DRAGONFLY | ** | S1 | G1G3G4 |
| I10D050010 | NANNOTHEMIS BELLA | DWARF SKIMMER | ** | S1 | G4 |
| I10D074030 | NEHALENNIA GRACILIS | SPHAGNUM SPRITE | ** | S1 | G5 |
| I10D074020 | NEHALENNIA IRENE | SEDGE SPRITE | ** | S2S3 | G5 |
| I10D031040 | NEUROCORDULIA OBSOLETA | UMBER SHADOWFLY | ** | S1S2 | G4 |
| I10D031070 | NEUROCORDULIA YAMASKANENSIS | STYGIAN SHADOWFLY | ** | S1S2 | G5 |
| I10D012150 | OPHIOMPHUS RUPINSULENSIS | RUSTY SNAKETAIL | ** | S2S3 | G5 |
| I10D032060 | SOMATOCHLORA ENSIGERA | LEMON-FACED EMERALD | ** | S1 | G4 |
| I10D032110 | SOMATOCHLORA HINEANA | OHIO EMERALD DRAGONFLY | SX ** | LE SX | G2 |
| I10D032150 | SOMATOCHLORA LINEARIS | MOCHA EMERALD | ** | S2S3 | G5 |
| I10D032230 | SOMATOCHLORA TENEBROSA | CLAMP-TIPPED EMERALD | ** | S2S3 | G5 |
| I10D080010 | STYLURUS AMNICOLA | RIVERINE CLUBTAIL | ** | S1S2 | G3G4 |
| I10D080040 | STYLURUS LAURAE | LAURA'S CLUBTAIL | ** | S1 | G3G4 |
| I10D080050 | STYLURUS NOTATUS | ELUSIVE CLUBTAIL DRAGONFLY | ** | S1 | G3G4 |
| I10D080090 | STYLURUS SCUDDERI | ZEBRA CLUBTAIL | ** | S1 | G3 |
| I10D061050 | SYMPETRUM DANAE | BLACK MEADOWFLY | ** | S1 | G5 |
| I10D061130 | SYMPETRUM SEMICINCTUM | BAND-WINGED MEADOWFLY | ** | S2S3 | G5 |
| I10D001010 | TACHOPTERYX THOREYI | GRAY PETALTAIL | ** | S2S3 | G4 |
| I10D029080 | TETRAONEURIA SPINIGERA | SPINY BASKETTAIL | ** | S1 | G5 |

**** Coleoptera: Beetles**

| | | | | | |
|------------|-------------------------|----------------------------|-------|----|------|
| I1COLA8060 | BATRISODES KREKELERI | CAVE BEETLE | SE ** | S1 | G1 |
| I1COL02060 | CICINDELA MARGINIPENNIS | COBBLESTONE TIGER BEETLE | SE ** | S1 | G2G3 |
| I1COL02230 | CICINDELA PATRUELA | A TIGER BEETLE | ** | S3 | G3 |
| I1COL03010 | DRYOBIVUS SEXNOTATUS | SIX-BANDED LONGHORN BEETLE | ST ** | S? | G? |
| I1COL86020 | DYNASTES TITYUS | UNICORN BEETLE | SR ** | S2 | G? |
| I1COL72010 | LISSOBIOPS SERPENTINUS | A ROVE BEETLE | SE ** | S1 | G? |
| I1COL42010 | MICROPHORUS AMERICANUS | AMERICAN BURYING BEETLE | SX LE | SH | G1 |

STATE: SX=extirpated, SE=endangered, ST=threatened, SR=rare, SSC=special concern, WL=watch
SG=significant, SRE=state reintroduced
FEDERAL: LE=endangered, LT=threatened, LELT=different listings for specific ranges of species, PE=proposed
endangered, PT=proposed threatened, E/SA=appearance similar to LE species, **=not listed

January 22, 1997

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES. INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE: ... SPECIES NAME: ... COMMON NAME: ... SPROT: USESA:SRANK:.. GRANK

| | | | | | | |
|------------------------------------|---|---------------------------------------|----|----|----|------|
| IICOL55020 | OCHTHEBIUS PUTNAMENSIS | INDIANA OCHTHEBIUS MINUTE MOSS BEETLE | SR | ** | S2 | GH |
| IICOL4EAEO | PSEUDANOPHTHALMUS BARRI | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EAF0 | PSEUDANOPHTHALMUS CHTHONIUS | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EA90 | PSEUDANOPHTHALMUS EMERSONI | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EA80 | PSEUDANOPHTHALMUS EREMITA | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EA83 | PSEUDANOPHTHALMUS JEANNELI | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL4EAA0 | PSEUDANOPHTHALMUS LEONAE | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EAD0 | PSEUDANOPHTHALMUS SHILOHENSIS | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EAD2 | PSEUDANOPHTHALMUS SHILOHENSIS BOONENSIS | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL4EAD1 | PSEUDANOPHTHALMUS SHILOHENSIS MAYFIELDENSIS | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL4EAB0 | PSEUDANOPHTHALMUS TENUIS | CAVE BEETLE | ST | ** | S2 | G2 |
| IICOL4EAB2 | PSEUDANOPHTHALMUS TENUIS BLATCHLEYI | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL4EAB1 | PSEUDANOPHTHALMUS TENUIS MORRISONI | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL4EAC0 | PSEUDANOPHTHALMUS YOUNGI | CAVE BEETLE | SE | ** | S1 | G1 |
| IICOL4EAC1 | PSEUDANOPHTHALMUS YOUNGI DONALDSONI | CAVE BEETLE | SE | ** | S1 | G? |
| IICOL5F020 | STENELMIS DOUGLASSENSIS | DOUGLAS STENELMIS RIFFLE BEETLE | WL | ** | S? | G1G3 |
| ** Ephemeroptera: Mayflies | | | | | | |
| IIEPH19010 | ANEPEORUS SIMPLEX | A FLAT-HEADED MAYFLY | SE | ** | S1 | G3G5 |
| IIEPH43010 | EPEORUS NAMATUS | A MAYFLY | SE | ** | S1 | G? |
| IIEPH11010 | EPHEMERELLA ARGO | ARGO EPHEMERELLAN MAYFLY | SE | ** | S? | G1G3 |
| IIEPH03030 | HOMOEONEURIA AMMOPHILA | A SAND-FILTERING MAYFLY | SE | ** | S1 | G4G5 |
| IIEPH22010 | PARACLOEODES MINUTUS | A SMALL MINNOW MAYFLY | SR | ** | S2 | G? |
| IIEPH13010 | PENTAGENIA ROBUSTA | ROBUST PENTAGENIA BURROWING MAYFLY | SX | ** | SX | GH |
| IIEPH13020 | PENTAGENIA VITTIGERA | A PENTAGENIAN BURROWING MAYFLY | ST | ** | S2 | G4G5 |
| IIEPH04020 | PSEUDIRON CENTRALIS | A MAYFLY | SE | ** | S1 | G? |
| IIEPH44010 | RAPTOHEPTAGENIA CRUENTATA | A FLATHEADED MAYFLY | SE | ** | S1 | G? |
| IIEPH21020 | SIPHLOPLECTON BASALE | A SAND MINNOW MAYFLY | SE | ** | S2 | G? |
| IIEPH21010 | SIPHLOPLECTON INTERLINEATUM | A SAND MINNOW MAYFLY | SE | ** | S1 | G? |
| IIEPH20010 | SPINADIS WALLACEI | WALLACE'S DEEPWATER MAYFLY | SE | ** | S? | G? |
| IIEPH06010 | TORTOPUS PRIMUS | A MAYFLY | ST | ** | S2 | G? |
| ** Trichoptera: Caddisflies | | | | | | |
| IITRI33060 | AGAPETUS GELBAE | AN AGAPETUS CADDISFLY | | ** | S2 | G? |
| IITRI33050 | AGAPETUS ILLINI | AN AGAPETUS CADDISFLY | | ** | S2 | G? |
| IITRI2A060 | CERACLEA SP 1 | A SPONGE-FEEDING CADDISFLY | ST | ** | S2 | G? |
| IITRI23020 | DIPLECTRONA METAQUI | A DIPLECTRONAN CADDISFLY | | ** | S2 | G? |
| IITRI95010 | GOERA STYLATA | A NORTHERN CASEMAKER CADDISFLY | SE | ** | S1 | G? |
| IITRI24020 | HOMOPLECTRA DORINGA | A HOMOPLECTRAN CADDISFLY | SE | ** | S1 | G? |
| IITRI85010 | NECTOPSYCHE PAVIDA | A LONGHORNED CASEMAKER CADDISFLY | SR | ** | S2 | G? |
| IITRI90010 | PYCNOPSYCHE ROSSI | A NORTHERN CASEMAKER CADDISFLY | SE | ** | S1 | G? |
| IITRI86010 | SETODES OLIGIUS | A CADDISFLY | SE | ** | S1 | G? |
| ** Homoptera: Leafhoppers | | | | | | |
| IIHOM18010 | MESAMIA STRAMINEA | HELIANTHUS LEAFHOPPER | WL | ** | S? | G? |
| IIHOM17010 | PRAIRIANA KANSANA | A LEAFHOPPER | WL | ** | S? | G? |
| ** Neuroptera: Lacewings | | | | | | |
| IINEU15010 | CLIMACIA SP 1 | A SPONGILLA FLY | ST | ** | S2 | G? |
| IINEU07020 | LOMAMYIA BANKSI | A BEADED LACEWING | | ** | S2 | G? |
| IINEU07010 | LOMAMYIA FLAVICORNIS | A BEADED LACEWING | | ** | S2 | G? |
| IINEU09010 | NALLACHIUS AMERICANUS | A PLEASING LACEWING | | ** | S2 | G? |
| IINEU08010 | POLYSTOECHOTES PUNCTATUS | A GIANT LACEWING | SX | ** | SX | G? |
| IINEU11020 | SISYRA SP 1 | A SPONGILLA FLY | ST | ** | S2 | G? |
| ** Mecoptera | | | | | | |
| IIMEC08150 | BOREUS SP 1 | | | ** | S2 | G1 |
| IIMEC01010 | MEROPE TUBER | EARWIG SCORPIONFLY | SE | ** | S1 | G3G5 |
| ** Other Type | | | | | | |
| ILARA29050 | APOCTHONIUS INDIANENSIS | CAVE PSEUDOSCORPION | SE | ** | S1 | G? |
| IICLL04070 | ARRHOPALITES BIMUS | SPRINGTAIL | SE | ** | S1 | G? |

STATE: SX=extirpated. SE=endangered. ST=threatened. SR=rare. SSC=special concern. WL=watch list.
FEDERAL: SG=significant. SRE=state reintroduced
LE=endangered. LT=threatened. LELT=different listings for specific ranges of species. PE=proposed
endangered. PT=proposed threatened. E/SA=appearance similar to LE species. **=not listed

January 22, 1997

ENDANGERED, THREATENED AND RARE VERTEBRATES AND INVERTEBRATES. INDIANA
INDIANA NATURAL HERITAGE DATA CENTER

ELCODE:... SPECIES NAME:..... COMMON NAME:..... SPROT: USESA:SRANK:. GRANK

| | | | | | | |
|------------|---------------------------|-----------------------------|----|----|----|------|
| ILARA92010 | CHTHONIUS VIRGINICUS | PSEUDOSCORPION | SE | ** | S1 | G? |
| ITUNI04090 | CONOTYLA BOLLMANI | MILLIPEDE | SR | ** | S2 | G? |
| ILARA48030 | HESPEROCHERNES MIRABILIS | CAVE PSEUDOSCORPION | SE | ** | S1 | G3G4 |
| ILARA21010 | PORHOMMA CAVERNICOLA | CAVE SPIDER | SE | ** | S1 | GU |
| ITUNI60010 | PSEUDOPOLYDESMUS COLLINUS | MILLIPEDE | SE | ** | S1 | G4 |
| ITUNI03140 | PSEUDOTREMIA NEFANDA | CAVE MILLEPEDE | SE | ** | S1 | G? |
| IICLL05060 | SINELLA ALATA | SPRINGTAIL | SE | ** | S2 | G? |
| IPTUR04070 | SPHALLOPLANA CHANDLERI | CHANDLER'S CAVE FLATWORM | SE | ** | S1 | G1 |
| IPTUR04090 | SPHALLOPLANA WEINGARTNERI | WEINGARTNER'S CAVE FLATWORM | ST | ** | S2 | G2G3 |

STATE: SX=extirpated. SE=endangered. ST=threatened. SR=rare. SSC=special concern. WL=watch
FEDERAL: SG=significant. SRE=state reintroduced
LE=endangered. LT=threatened. LEIT=different listings for specific ranges of species. PE=proposed
endangered. PT=proposed threatened. E/SA=appearance similar to LE species. **=not listed

 [GLIN Home](#) [Search](#) [Contents](#) [Index](#) [Tips](#) [New](#)

[About GLIN](#) | [Economy](#) | [Ecosystem](#) | [Education](#) | [Environment](#) | [Grants and Funding Sources](#)
[Great Lakes](#) | [Great Links](#) | [Laws and Policies](#) | [Places](#) | [Reference Desk](#) | [Regional Calendar](#)

Exotic Species in the Great Lakes Region

[Biodiversity](#) | [Habitat](#) | [Plants](#) | [Publications](#) | [State Management Plans](#) | [Select Exotic Species](#) | [Task Forces](#) | [Wildlife](#)

An Overview of Exotic Species

Exotic species have threatened the Great Lakes ever since Europeans settled in the region. Since the 1800s, at least 136 exotic aquatic organisms of all types - including plants, fish, algae and mollusks - have become established in the Great Lakes. As human activity has increased in the Great Lakes watershed, the rate of introduction of exotic species has increased. More than one-third of the organisms have been introduced in the past 30 years, a surge coinciding with the opening of the St. Lawrence Seaway.

Select Exotic Species

Mollusks

- [Zebra Mussel](#)

Crustaceans

- [Rusty Crayfish](#)
- [Spiny Water Flea](#)

Fish

- [Common Carp](#)
- [Goby](#)
- [Ruffe](#)
- [Sea Lamprey](#)
- [White Perch](#)

Plants

- [Curly-leaf Pondweed](#)
 - [Eurasian Watermilfoil](#)
 - [Flowering Rush](#)
 - [Purple Loosestrife](#)
-

Recommended Resources

[Biological Pollution](#), Northeast-Midwest Institute

The institute is undertaking a number of efforts to prevent the introduction and spread of nonindigenous aquatic nuisance species.

[Exotic Species](#), Minnesota Sea Grant



Nonindigenous Aquatic Nuisance Species State Management Plan:

A Strategy to Confront Their Spread in Michigan

Table of Contents

I. Executive Summary ii

II. The Present State of Affairs 1

Species of Concern 2

Michigan Efforts 5

Financial Impacts 11

State and Federal Policy 13

Ballast Water Control 17

Integrated Pest Management 21

Research Initiatives 22

Summary 24

III. The Plan 25

Problems and Strategies

Information and Education 26

Research and Monitoring 28

Policy and Regulation 32

Implementation Tables 34

Implementation Schedule 38

Annual Objectives ` 39

Appendix A

Referenced Materials 42

I. Executive Summary

Nonindigenous species are plants and animals found beyond their natural ranges and are now part of the North American landscape. Many are highly beneficial. Most U.S. crops and domesticated animals, many sport fish and aquaculture species, numerous horticultural plants, and most biological control organisms have origins outside Michigan. A large number of nonindigenous species, however, cause significant environmental, socio-economic, and public health damage. The severity of these impacts are not widely recognized, impeding the commitment needed to prevent future introductions. Also, a "crisis response" mentality often limits the vision and opportunity for the prevention of future introductions, leaving the state with control problems that are economically costly, technically challenging, often impossible to solve. Although at least 139 nonindigenous aquatic species have already become established in the Great Lakes ecosystem, future introductions are still highly probable. It is the harmful aquatic nuisance species (ANS), such as the zebra mussel, ruffe, goby, spiny water flea, Eurasian watermilfoil and others that arrived here unexpectedly, which provide the focal point for this State Management Plan (plan). The prevention of unintended introduction is critical in alleviating ANS problems in Michigan and the entire Great Lakes region.

The 1994 summer beach closings on Lake St. Clair, resulting from bacterial contamination and the massive accumulation of aquatic vegetation is a reminder that ecosystems can undergo dramatic changes due, in part, to the introduction of ANS into the Great Lakes Basin. Many changes in Lake St. Clair are attributed to increased water clarity, resulting from the presence of zebra mussels believed to have arrived in 1986.

We cannot completely stop the tide. Perfect screening, detection, and control are impossible for the foreseeable future. Nevertheless, Federal and State policies, designed to protect us from unplanned invasions and the spread of nonindigenous species, are not safeguarding our local and national interests in important areas. The conclusions of a report filed by the Office of Technology Assessment within the United States Congress (Harmful Non-Indigenous Aquatic Nuisance Species in the United States, September 1993) have a number of policy implications. First, the Nation has no real national policy on harmful aquatic introductions; and the current systems are piecemeal and lack adequate rigor and comprehensiveness. Second, many Federal and State statutes, regulations, and programs are not keeping pace with new and spreading nonindigenous pests. Third, better environmental education and greater accountability regarding actions that cause harm could prevent some problems. Finally, faster response and more adequate funding could limit the impact of those that slip through.

The Nonindigenous Aquatic Nuisance Prevention and Control Act of 1990 (Public Law 101-646), is the federal legislation which calls upon the states to develop and implement comprehensive state management plans for aquatic nuisance species control. The Act was established for the prevention and control of the unintentional introduction of ANS and is based on the following five objectives:

- Prevent further unintentional introductions of nonindigenous aquatic species;
- Coordinate federally funded research, control efforts and information dissemination;
- Develop and carry out environmentally sound control methods to prevent, monitor and control unintentional introductions;
- Understand and minimize economic and ecological damage;
- Establish a program of research and technology development to assist state governments.

The plan requests funding in the amount of \$466,700 over a three-year period and would provide the resources necessary for enhanced information and education efforts, additional monitoring capabilities, and increased technical assistance to private facilities. The resources would also be used for the development of policy options regarding environmental controls and regulations to provide the foundation for a long-term commitment to ANS control in Michigan. In addition, the plan sends the message that the federal government has not met its responsibility to control further introductions of ANS. Existing resources do not adequately address the problem.

While the opportunity for federal funding provided the initial impetus for the development of this plan, it will serve as Michigan's plan of action, to the extent resources allow, even if federal support fails to materialize.

II. The Present State of Affairs

Nonindigenous aquatic species are a source of socio-economic benefits and costs to many sectors of American society and a threat to the maintenance of biological diversity and ecological integrity. The significance of nonindigenous species issues are generally not recognized. Yet, the stakes are hard to overstate. An aquatic nuisance species (ANS) is defined as a waterborne, non-indigenous organism that threatens the diversity or abundance of native species, or the ecological stability of impacted waters, or, that threatens a commercial, agricultural, aquacultural or recreational activity dependent on infested waters. These species have the potential to cause significant ecological problems because they have been introduced into a habitat in which there are no natural controls, such as pathogens, parasites, and predators. Lack of natural controls in a new habitat may allow a species to grow at or near its potential, exponential growth rate. If such species become established, they may disrupt species relationships in the new habitat. As a nuisance species proliferates, other species relationships change in the habitat. The introduced species may prey upon, outcompete, or cause disease in native species.

Because the Great Lakes are open to the St. Lawrence Seaway for shipping, they have been the recipient of many foreign aquatic nuisance species. Since the 1800's, over 130 such organisms have become established in the Great Lakes Basin. Over one-third of the organisms have been introduced unintentionally in the past 30 years, a surge coinciding with the opening of the St. Lawrence Seaway. With the increased speed of ocean transport and improved water quality conditions in some European countries, zebra mussels, ruffe, gobies, and other pests are now able to survive the journey in ship ballast water from Europe to the Great Lakes. Nonindigenous aquatic nuisance species will continue to arrive in the Great Lakes Basin until the pathways by which these species are introduced are adequately addressed by federal, state, and provincial governments, and responsible actions are taken to reduce the rate of introduction. Nonindigenous species, and the control of their spread, are international issues with potential impacts that span economic, social, health, and ecological concerns. Water used for many applications, including ballast control, food processing, bait industry, exotic pet trade, and the aquarium trade are all sources of introduction of nonindigenous species causing adverse impacts to the Great Lakes.

On November 29, 1990, partly in response to the introduction of zebra mussels into the Great Lakes, Congress passed the Nonindigenous Aquatic Nuisance Prevention and Control Act of 1990 (Public Law 101-646). The major focus of the act is to set up a framework to reduce the risk of unintentional introductions and to monitor and control nonindigenous aquatic nuisance species. The act establishes a federal interagency Aquatic Nuisance Species Task Force responsible for developing a framework to address the problem of nonindigenous aquatic nuisance species. The act also contains specific provisions for controlling zebra mussels and a mandate that the United States Coast Guard promulgate ballast

regulations which apply to vessels that enter a United States port on the Great Lakes after operating on the waters beyond the Exclusive Economic Zone (EEZ). The EEZ is defined as an area extending from the baseline of the territorial sea of the United States seaward 200 miles. The Coast Guard ballast water management regulations became effective on May 10, 1993. Because the regulations do not address ballast control measures for vessels operating inside the EEZ, and those entering Great Lakes connected fresh and brackish waters, it provides no safeguards for preventing the dispersion of aquatic nuisance species already established in the United States. The key to the long-term protection of the Great Lakes from unwanted arrivals is to prevent the discharge of ANS contaminated vessel ballast water into the Lakes. Cost effectiveness dictates that the strategic emphasis be placed on prevention of introductions rather than on attempting after-the-fact control of range expansions of ANS. An established nonindigenous organism in the Great Lakes Ecosystem is impossible to eradicate.

Section 1204 of the act is also particularly relevant to the Great Lakes States. This section allows the governor of each state, after notice and opportunity for public comment, to prepare and submit to the nationally appointed Aquatic Nuisance Species Task Force, a comprehensive state management plan which identifies management measures and funding needed to reduce infestations of aquatic nuisance species. Furthermore, development of a state management plan is a key recommendation of Michigan Natural Resources Commission Policy #2001 (Nonindigenous Aquatic Nuisance Species, March, 1993). The plan contained herein requests funding in the amount of \$466,700 over a three-year period to carry out the following objectives:

- Prevent new introductions of ANS into the Great Lakes and inland waters of Michigan.
- Limit the spread of established populations of ANS into uninfested waters of Michigan.
- Abate harmful ecological, economic, social and public health impacts resulting from infestation of ANS.

The environmental and economic costs resulting from the invasion of aquatic nuisance species in Michigan will continue to rise if new introductions continue and with the spread of species already released. While the opportunity for federal funding provided the initial impetus for the development of this plan, it will serve as Michigan's plan of action, to the extent resources allow, even if federal support fails to materialize.

Species of Concern

The invasion of the zebra mussel in 1988 helped bring the serious nature of the aquatic nuisance species issue to the public eye. Prior to the zebra mussel invasion, public perception held that resource management agencies have the ability to control alien invaders. While this belief is partially true, control can only be defined as slowing or preventing the spread; range reduction of a species; mitigation of site specific conditions such as allowing for the treatment of water intake systems to remove colonies of zebra mussels; or cleaning beaches after major storm events which wash thousands of dead zebra mussels ashore. Control of aquatic nuisance species is not complete eradication of the nuisance organism from the ecosystem, rather it means a reduction in abundance or effect of the nuisance.

In the spring of 1988, the zebra mussel (*Dreissena polymorpha*) was discovered in Lake St. Clair. Scientists believe the zebra mussel was transported to North America in the ballast water of a transatlantic freighter that previously visited a port in Eastern Europe where this mollusk is common. Zebra mussels have now spread to all five Great Lakes and are also found in the Mississippi, Tennessee, Hudson, and Ohio River Basins.

Zebra mussels readily attach to most submerged surfaces including boats, rocky shoals, water intake

pipes, navigational buoys, docks, piers, and indigenous species such as clams. They affix themselves to shells of their own species and are able to form dense layered colonies of over 1 million per square meter. The mussels have been able to colonize and foul heat exchangers, valves, and small diameter piping once the organism gains entry into power plants. Irrigation, fire protection, and dust suppression systems have also experienced problems associated with mussel colonization. The U.S. Fish and Wildlife Service assesses the potential economic impact at \$5 billion over the next ten years to U.S. and Canadian factories, water suppliers, power plants, ships and fisheries within the Great Lakes Region.

The ability of zebra mussels to filter suspended particles with high efficiency from the water column was established by European researchers. Consequently, one of the early concerns regarding the appearance of zebra mussels in the Great Lakes was the impact on water quality. During the past several years research in the Western and Central Basins of Lake Erie has confirmed preliminary observations that water clarity had increased as a result of filtering activity by dense populations of zebra mussels. However, attributing an increase in clarity to zebra mussels is not as simple and straightforward as it may appear. Other important factors influence water clarity, such as storms that resuspend sediments, nutrients, phytoplankton, and organisms that graze on phytoplankton.

Over the past few decades, nutrients (especially phosphorus) that support phytoplankton growth have been an important determinant of water clarity in Lake Erie. High phosphorus levels support dense populations of algae, causing reduced water clarity. Since the 1960's improved sewage treatment facilities and low-phosphate detergents have successfully reduced phosphorus inputs to Lake Erie by about 50 percent. Researchers from the Ontario Ministry of the Environment recorded the decline of phytoplankton associated with decreasing phosphorous levels from the late 1960's to the present. With the appearance of zebra mussels in 1988, phytoplankton abundance declined significantly and far more rapidly than could be explained by declining phosphorous levels. A decline of phytoplankton also followed the spread of zebra mussels into Lake St. Clair in 1988, western Lake Erie in 1989, and central Lake Erie in 1990. An additional piece of evidence supports the role of zebra mussels in the decline of phytoplankton. The species composition of the phytoplankton community itself also changed. Researchers noted that as phosphorus levels declined, the dominant species of phytoplankton shifted from a blue-green algal community (high phosphorus) to a green algal community (lower phosphorus levels).

The consequences for organisms that rely on phytoplankton as a food source have yet to be accurately determined. Because phytoplankton is the major food source for open water (pelagic) lake food chains, fisheries impacts may result from zebra mussel filtration activity. Excessive removal of phytoplankton from the water column may cause a decline in planktivorous fish species. As a result, populations of planktivorous fish like gizzard shad might decline, and other desirable fishes such as walleye rely on the shad for forage. As zebra mussels settle and attach to firm substrates, there is also concern that extensive colonization of shoal areas in lakes could impair reproduction of certain fish species. The walleye and lake trout are two species which use rocky substrate for spawning and may be affected by colonies of mussels.

One severe biological impact that has been documented is the near extinction of native American unionid clams in Lake St. Clair and in the western basin of Lake Erie. Zebra mussels attach and build colonies on the clams, eventually leading to their death. One of the earliest and most noticeable natural responses is the increased use by diving ducks of areas with large populations of zebra mussels. Diving ducks feed on zebra mussels. Researchers do not believe that feeding of diving ducks alone will significantly reduce zebra mussel populations, however. The zebra mussels' prolific reproductive cycle along with its ability to adapt to many aquatic environments make it a very successful invader. Scientists believe eradication of the mussel is unlikely. Furthermore, American and Canadian research conducted since 1988, indicate an inevitable dispersion of zebra mussels to every temperate waterbody throughout North America.

Another important aquatic nuisance species already established in the Great Lakes Basin is the ruffe (Gymnocephalus cernuus), a small perch-like, Eurasian fish. It was apparently introduced to the Great Lakes in the St. Louis River near Duluth, Minnesota from a ballast discharge. In Europe the ruffe feeds on whitefish eggs and competes with other more desirable fish. The spiny dorsal fins of the ruffe discourage predation by other fish. In Lake Superior, the species of fish that is most affected by the ruffe is the yellow perch. Populations of perch have declined up to 75% in water bodies where ruffe have become established.

The quagga mussel (Dreissena bugensis) is related to the zebra mussel but is a distinct species. It prefers deeper, colder waters which is consistent with laboratory studies indicating that the quagga has a lower thermal maximum than the zebra mussel. In addition, it may have the same potential as the zebra mussel to clog water intakes. The discovery of this second type of mussel increases the probability that other species of Dreissenidae have been introduced into the Great Lakes.

The round goby (Neogobius melanostomus) is an abundant species with origins in the Black and Caspian Seas. They are a small fish that feed chiefly on bivalves, amphipod crustaceans, small fish, and fish eggs. It is also believed this fish was introduced into the Great Lakes from discharged ballast water. Consumption studies of fish suggests round gobies might have a detrimental impact on native species through competition for food and predation on eggs and young fish.

The spiny water flea (Bythotrephes cederstroemi) is also believed to have entered the waters of the Great Lakes from discharged ballast water. Although its average length is rarely more than one centimeter, this large predaceous zooplankton can have a profound effect on a lake's plankton. The spiny water flea sometimes competes directly with young fish for food. Because this organism can reproduce many times faster than fish, it could monopolize the food supply at times, to the eventual detriment of the fish. Although *Bythotrephes* can also fall prey to fish, its spine seems to frustrate most small fish, which experience great difficulty swallowing the animal.

The sea lamprey (Petromyzon marinus) has been a serious problem in the Great Lakes for more than 50 years. After more than 30 years of trying to eradicate lamprey, the parasitic invader is making a comeback at the expense of the lake trout fishery in northern Lakes Michigan and Huron. An adult lamprey can kill up to 40 pounds of fish in just 12 to 20 months. A lamprey attaches itself to a fish with a sucking disk, pierces its scales and skin and sucks out body fluids, often killing the fish.

Eurasian watermilfoil (Myriophyllum spicatum), a nonindigenous aquatic plant, reached the midwestern states between the 1950s and 1980s. In nutrient rich lakes watermilfoil can form thick underwater stands of tangled stems and vast mats of vegetation at the water's surface. In shallow areas the plant can interfere with water recreation such as boating, fishing, and swimming. The plant's floating canopy can also crowd out dominant native water plants.

Purple Loosestrife (Lythrum salicaria), is a perennial wetland plant native to Europe and Asia. It was introduced into the United States in the early 1800s and continues to spread. The plant is impacting Michigan wetland ecosystems by changing the structure, function, and productivity of the wetlands. The plant forms dense monoculture stands, sometimes hundreds of acres in size, that displace native vegetation and threaten the biotic integrity of wetland ecosystems. The loss of plant species richness and diversity has eliminated natural foods and cover essential to many wetland wildlife species.

Once established in large, open aquatic systems, harmful, nonindigenous species such as those described above have proven impossible to eradicate. These species represent only a small percentage of the most

Public Comment Period

On March 10, 1995, Michigan's Nonindigenous Aquatic Nuisance Species State Management Plan was made available for a 45-day public review and comment period. Notice of the availability of the plan was announced in a statewide press release and in the Department of Natural Resources Calendar. Three hundred copies were printed and all were subsequently distributed. Written comments were received from twenty-six individuals representing fifteen different agencies and organizations. To the extent possible, the comments were addressed and information incorporated in the final document. A summary of the public comments can be obtained by contacting the Office of the Great Lakes. In addition, questions or comments about the State Management Plan should be directed to the Office at 517-373-3588.

Document prepared by Mark Coscarelli, Environmental Specialist, Office of the Great Lakes.

Appendix A

Referenced Materials

The following documents were used in the development of the information presented in this plan.

U.S. Congress, Office of Technology Assessment, *Harmful Nonindigenous Species in the United States*, OTA-F-565 (Washington, DC: U.S. Government Printing Office, September 1993).

International Joint Commission and the Great Lakes Fishery Commission, *Exotic Species and the Shipping Industry: The Great Lakes-St. Lawrence Ecosystem at Risk*, (A special report to the Governments of the United States and Canada, September 1990).

Marine Technology and the Environment, *The Ship As a Vector in Biotic Invasions*, (IMAS 90, May 1990).

United States Coast Guard, *The Defense of the Great Lakes against the Invasion of Nonindigenous Species in Ballast Water*, (Compliance Overview of Ballast Water Regulations, September 2, 1995).

National Oceanic and Atmospheric Administration, Benefits and Costs of the Ruffe Control Program for the Great Lakes Fishery, (May 18, 1994).

Office of the Great Lakes, Michigan Department of Natural Resources, *Nonindigenous Aquatic Nuisance Species*, (Natural Resources Commission Policy Number 2001, March 1993).

Office of the Great Lakes, Michigan Department of Natural Resources, *The Zebra Mussel, (Dreissena polymorpha): A Strategy to Control Its Spread in Michigan*, (A Report to the Michigan Legislature, February 1991).

Michigan Department of Natural Resources, *DNR Action Plan for Lake St. Clair*, (Surface Water Quality Division, August 1994).

Wisconsin Department of Natural Resources, University of Wisconsin Sea Grant Institute, *Protecting Wisconsin Waters from Exotic Invaders*, (A Zebra Mussel Report to the Legislature, December 1994).

New York State Department of Environmental Conservation, *Nonindigenous Aquatic Species Comprehensive Management Plan*, (November 1993).

Michigan State University Extension, *Aquatic Pest Management: A Training Manual for Commercial Pesticide Applicators*, (Extension Bulletin E-2437, June 1993).

Ontario Ministry of the Environment, The zebra mussel, (*Dreissena polymorpha*): A Synthesis of European Experiences and a Preview for North America, (1989).

Center for Evaluative Studies, Michigan State University, Evaluation of the Great Lakes Sea Grant Network's Zebra Mussel Outreach Activities for Industrial and Municipal Water Users, (September 1994).

Questions or Comments?

Contact Martha Waszak (517) 335-4112 FAX: (517) 335-4053

e-mail address: waszakm@deq.state.mi.us



[Home Page](#)

Revised December 18, 1996, by Martha Waszak
<http://www.deq.state.mi.us>